




BHUTAN POWER CORPORATION LIMITED
(An ISO 9001:2015, ISO 14001:2015 & OHSAS 18001:2007 Certified Company)

P.O. Box : 580, Yarden Lam
Thimphu, Bhutan (Registered Office)
Website: www.bpc.bt

DISTRIBUTION SYSTEM MASTER PLAN (2020-2030) CHHUKHA DZONGKHAG



**Distribution and Customer Services Department
Distribution Services
Bhutan Power Corporation Limited**

2020



DISTRIBUTION SYSTEM MASTER PLAN (2020-2030) CHHUKHA DZONGKHAG

**Distribution and Customer Services Department
Distribution Services
Bhutan Power Corporation Limited
2020**


FOREWORD

The Distribution System Master Plan (DSMP) identifies, prioritizes and opts for adequate and optimal distribution system expansion and augmentation programs to meet the expected electricity growth and demand development in the Country. This timely formulation of DSMP is in line with the stated corporate strategic objective of providing affordable, reliable and quality services to customers and will enable to traverse the changing technological, regulatory and social constraints for the time horizons considered.

The DSMP has been finalized after a series of consultative discussions with all the relevant stakeholders to obtain a shared outcome. In particular, adequate efforts have been taken to ensure that the DSMP aligns and integrates with the stated plans and programs of the Royal Government of Bhutan (RGoB) for the energy sector.

Based on the expected demand development for the time horizons considered, the DSMP outlines the road map for the implementation of optimized distribution network expansion programs and projects in stages with the expected investment required and financial commitments. The DSMP will be updated on a regular basis to incorporate changing business imperatives and contexts to ensure its relevance.

Appreciation goes to all the officials of the Distribution Services for formulating and coming out a comprehensive document that is timely which will serve as a blueprint for the Distribution Services to build a robust distribution system that will go a long way in contributing towards realization of BPC's objectives of providing a reliable electricity supply to its valued customers.



(Sonam Tobjey)
Chief Executive Officer



Preparation, Review & Approval of the Document


Prepared by:	Distribution & Customer Services Department, Distribution Services, Bhutan Power Corporation Limited, Thimphu.	 GM, DCSD
Reviewed & Vetted by:	Management, Bhutan Power Corporation Limited, Thimphu. (22 nd December 2019 – Meeting No. 557)	 CEO, BPC
Approved by:	Board Tender & Technical Committee (BTTC), Bhutan Power Corporation Limited, Thimphu. (26 th December, 2019 - 15 th BTTC Meeting)	 Chairman, BTCC

Table of Contents

List of Tables.....	iii
List of Figures	iii
Abbreviations	v
Definitions	vi
1. Executive Summary.....	1
2. Introduction.....	2
3. Objectives of the Master Plan	3
4. Scope of the Distribution System Master Plan	3
5. Methodology and Approach.....	3
5.1 Data Collection and Validation.....	4
5.2 Modeling and Mapping.....	4
5.3 Analysis and Identification of System Deficiencies.....	4
5.4 Distribution System Planning	4
5.5 Investment Plan	5
6. Existing Electricity Distribution Network.....	5
6.1 Overview of the Power Supply Sources	5
6.2 Electricity Distribution Lines.....	6
6.3 Distribution Transformers.....	7
7. Analysis of Distribution System.....	10
7.1 Assessment of Power Sources.....	10
7.1.1 HV Substation	10
7.1.2 MV Substation.....	13
7.2 Assessment of MV Feeders.....	14
7.2.1 Assessment of MV Feeder Capacity with Load.....	14
7.2.1 Energy Loss Assessment of MV Feeders	26
7.2.2 Reliability Assessment of the MV Feeders.....	31
7.2.2 Single Phase to Three-Phase Conversion	36

7.3	Assessment of the Distribution Transformers.....	37
7.3.1	Distribution Transformer Loading.....	37
7.3.2	Asset life of Distribution Transformers	39
7.3.3	Replacement of Single Phase Transformers	40
7.4	Power Requirement for Urban Areas by 2030.....	41
7.4.1	MV & LV lines for LAPs	47
7.4.2	Distribution Transformers.....	49
8.	Distribution System Planning.....	50
8.1	Power Supply Sources	50
8.1.1	HV Substations.....	50
8.1.2	MV Substations	50
8.2	MV and LV Lines.....	51
8.3	Distribution Transformers.....	51
8.4	Switching and Control	52
8.4.1	Intelligent Switching Devices	52
8.4.2	Distribution System Smart Grid.....	57
9.	Investment Plan.....	57
10.	Conclusion	64
11.	Recommendations	65
12.	Annexure.....	67
13.	References.....	67
14.	Assumptions.....	68
15.	Challenges.....	68

List of Tables

Table 1: MV and LV Line Details	7
Table 2: Total Numbers of Transformers, Installed Capacity and Customers	7
Table 3: HV Power Sources	11
Table 4: MV Power Sources.....	13
Table 5: Feeder Wise Peak Power Demand (2015-2019).....	14
Table 6: Thermal loading of ACSR conductor at different voltage levels.....	18
Table 7: Feeder Peak Power Demand Forecast.....	19
Table 8: Feeders with Poor Voltage Profile (2019, 2025 and 2030)	24
Table 9: Feeder Wise Voltage Improvement.....	25
Table 10: Summary of Total Energy Loss (MU).....	26
Table 11: Feeder Wise Energy Loss (in MU) of ESD, Chukha	28
Table 12: Feeder Wise Reliability Indices	32
Table 13: Forecasted Transformer Loading of ESD, Phuentsholing.....	38
Table 14: Proposed Lists of DTs Requiring Up-grading	39
Table 15: List of Outlived Transformers	40
Table 16: LAPs under Chukha Dzongkhag.....	41
Table 17: Proposed Distribution Transformers in LAPs.....	49
Table 18: Existing and Proposed Switching Equipment.....	53
Table 20: Investment Plan (2020-2030).....	59

List of Figures

Figure 1: Block diagram for distribution system planning for thematic studies	3
Figure 2: Electricity Distribution Schematic Network of Chukha Dzongkhag (Phuentsholing, Singyegoan and Malbase substations)	5

Figure 3: Electricity Distribution Schematic Network of Chukha Dzongkhag (Gedu and Watsa Substations and Chukha Switchyard)	6
Figure 4: Overall Plot of Peak Power Demand of ESD, P/Ling & ESSD, Gedu & Tsimasham ..	16
Figure 5: Plot of Feeder Wise Peak Power Demand of ESD, P/Ling & ESSD, Gedu & Tsimasham.....	17
Figure 6:Overall Plot of Forecasted Peak Power Demand of ESD, Phuentsholing (Including ESSDs)	22
Figure 7: Plot of Forecasted Peak Power Demand of ESD, Phuentsholing.....	22
Figure 8: Plot of Forecasted Peak Power Demand of ESSD, Gedu & Lhamoizingkhag.	23
Figure 9: Plot of Total Energy Loss (MU) of ESD, Phuentsholing.....	27
Figure 10: Feeder Wise Energy Losses (MU) of ESD, Phuentsholing.....	31
Figure 11: Feeder Wise SAIFI & SAIDI of ESD, Phuentsholing	33
Figure 12: Root Causes of the Interruptions	34
Figure 13: Ahlay LAP	41
Figure 14: Pekarzhing LAP	42
Figure 15: Pasakha LAP.....	43
Figure 16: Rinchending LAP.....	44
Figure 17:Kharayphu LAP	44
Figure 18: Damdara LAP	45
Figure 19: Amochu LAP	46
Figure 20: Chamkuna LAP.....	46
Figure 21: Toorsatar LAP	47
Figure 22: Proposed Distribution Network under ESD, Phuentsholing	51
Figure 23: Overall Switching Equipment for Distribution Network of Gedu SS	54
Figure 24: Proposed Switching Equipment for Distribution Network of Phuentsholing SS.....	55
Figure 25: Proposed Switching Equipment for Distribution Network of Chukha Switch Yard and Singyegoan GIS SS.....	56

Figure 26: Priority Matrix 57

Abbreviations

BPC: Bhutan Power Corporation Limited

ESD: Electricity Services Division

DSMP: Distribution System Master Plan

GIS: Geographical Information System

SLD: Single Line Diagram

ETAP: Electrical Transient and Analysis Program

IS: Indian Standard on Transformers

IEC: International Electrotechnical Commission

DT: Distribution Transformer

TSA: Time Series Analysis

LRM: Linear Regression Method

USS: Unitized Substation

DMS: Distribution Management System

ADMS: Advanced DMS

SCADA: Supervisory Control and Data Acquisition

DSCADA: Distribution SCAD

MV: Medium voltage (33kV, 11kV and 6.6kV (if it exists))

DDCS: Distribution Design and Construction Standards

kVA: Kilo Volt Ampere

W: Watt

kWh: Kilo Watt Hour

RMU: Ring Main Unit

PHCB: Population and Housing and Census of Bhutan

BDBL: Bhutan Development Bank Limited

BNB: Bhutan National Bank

RSTA: Road Safety and Transport Authority

RICB: Royal Insurance Corporation Limited

BoB: Bank of Bhutan Limited

Definitions

Asset Life: The period of time (or total amount of activity) for which the asset will be economically feasible for use in a business.

Balanced system: A system is said to be balanced when all phase conductors carry approximately the same current. For delta systems, this applies to two-phase conductors, and for three-phase wye systems, this applies to three-phase conductors.

Contingency plan: Power that is needed when regularly used electric generating units are not in service, such as during short-term emergencies or longer unplanned outages, and during periods of scheduled maintenance when the units must be shut down. Short-term backup power is generally called emergency power. Long-range backup power is often provided for in reserve sharing agreements.

Capacity: Also known as the power or capability of an electric generating plant. Facilities and place to serve electric customers. 2) The total amount of electrical energy a power line is able to transport at any given time (Measured in kVA).

Clearance: The clear distance between two objects measured surface to surface. For safety reasons, proper clearance must be maintained between power lines and the ground, buildings, trees, etc.

Critical Value: The value of the random variable at the boundary between the acceptance region and the rejection region in the testing of a hypothesis.

Distribution line: That part of the electrical supply system that distributes electricity at medium voltage (33kV, 11kV & 6.6kV) from a transformer substation to transformers or other step-down devices service customer premises, which finally supply power at the voltage required for customer use.

Distribution loss: Energy losses in the process of supplying electricity to the consumers due to commercial and technical losses.

Distribution system: The portion of the transmission and facilities of an electric system that is dedicated to delivering electric energy to an end-user.

Energy: Delivered power measured in kilowatt-hours (kWh).

Generating station: A plant wherein electric energy is produced by conversion from some other forms of energy.

Grid: A system of high-voltage transmission and power-generating facilities that is interconnected with a number of other bulk power supply agencies on a regional basis. A grid enables power to be transmitted from areas having a surplus to areas experiencing a shortage. A grid also eliminates some duplication of costly facilities in a given region.

Investment: the action or process of investing money for certain activities with return and profit.

Lines (electrical supply) - Those conductors used to transmit or deliver electric energy and their necessary support or containing structures.

Linear Regression Method: In **statistical modeling**, regression analysis is a set of statistical processes for **estimating** the relationships between a **dependent variable** (often called the 'outcome variable') and one or more **independent variables**.

Load: 1) A device, or resistance of a device, to which power is delivered in a circuit. 2) The measure of electrical demand placed on an electric system at any given time.

Load forecasting: The methods used in determining a system's short and long-term growth in peak load and kilowatt-hour sales by consumers.

Load Growth: The increase in the demand of power required over time.

Marginal Value: Just barely adequate or within a lower Limit.

On line - Term generally used to indicate when a generating plant and transmission line is scheduled to be in operation. When an operational plant and line is not on line, it is said to be "down."

Outage - Interruption of service to an electric consumer.

Overload - Operation of equipment in excess of normal, full-load rating, or of a conductor in excess of rated ampacity that, when it persists for a sufficient length of time, would cause

damage or dangerous overheating. A fault, such as a short circuit or ground fault, is not an overload.

Optimization: the action of making the best or most effective use of a situation or resource.

Pad-mounted equipment- General term describing enclosed equipment, the exterior of which enclosure is at ground potential, positioned on a surface-mounted pad. Example: underground transformers and junction boxes.

Peak demand - The maximum amounts of electricity used by a utility customer at any given time during the year. The peak is used to measure the amount of electric transmission, distribution, and generating capacity required to meet that maximum demand, even if it occurs infrequently and only for very short durations.

Peak load - The greatest amount of electricity used during a time period by the consumers in a utility's system.

Power - The time rate of electric energy in a device or circuit, measured in watts.

Power factor - A measurement of efficiency in the use of electricity. For example: a 100% power factor would be like a horse pulling a wagon on rails directly forward with no resistance. If the horse turns and pulls at a right angle to the rails, he may pull just as hard, but his efforts will not move the car. This would be a zero percent power factor. Now, if he pulls at a 45-degree angle to the rails, he will pull the car, but not with as high efficiency as if he were pulling straight down the rails. In the use of electricity, not every kilowatt generated translates into equivalent horsepower efficiency.

Power grid - A network of generation, transmission and distribution system that are interconnected

Power quality - The extent to which a utility system is able to maintain its delivery of electric energy within the tolerable limits of voltage and without outages or other problems with affect a customer's equipment use.

Power supply - Source of current and voltage.

Reliability - A measure of a utility's ability to deliver uninterrupted electric service to its customers.

Substation - An electrical facility containing switches, circuit breakers, buses, and transformers for switching power circuits and transforming power from one voltage to another, or from one system to another.

Time Series Analysis: The statistical techniques used when several years' data are available to forecast the load growth.

1. Executive Summary

Bhutan Power Corporation Limited is mandated to provide affordable, adequate, reliable and quality electricity services to the customers through transmission and distribution networks established across the country. Towards realizing the mission, vision and destination statement of BPC as outlined in the Corporate Strategic Plan (2019-2030), there is a need to carry out comprehensive studies of the distribution system to address the system deficiencies as the ground realities are different triggered by technological advancement and economic growth.

The existing distribution networks are modeled and accordingly, the technical evaluation is carried out adopting the generally accepted load forecasting framework i.e. Time Series Analysis in conjunction to Linear Regression Method, the power requirement for next ten (10) years are forecasted. Subsequently, the network capability and the system gaps are identified with proposed distribution system planning. The investments are proposed (based on the priority matrix) to address the system inadequacies with the intent to improve the Customer Services Excellence, Operational and Resource Optimization Excellence, Innovation and Technology Excellence and Business Growth Excellence.

The single to three-phase distribution network conversion across the country is reproduced in this report based on the studies carried out by BPC “Technical and Financial Proposal on Converting Single Phase to Three-Phase Power Supply in Rural Areas”.

The details on the distribution grid modernization are outlined in Smart Grid Master Plan 2019 including the investment (2020-20230). The identification of the system deficiencies and qualitative remedial measures which would require system automation and remote control as per the existing and projected load are only outlined in this report.

Similarly, the system study beyond the Distribution Transformers had to be captured during the annual rolling investment and budget approval.

The ETAP tool is used to carry out the technical evaluation and validate the system performances. Finally, necessary contingency plans, up gradation and reinforcement plans are proposed as annual investment plans based on the outcome of the simulation result.

2. Introduction

The system study is intended to improve the power distribution system in Bhutan by formulating a comprehensive, national level and district wise DSMP (2020-2030) till 2030 that provides measures for renewing and reinforcing power distribution facilities. BPC's distribution system has grown in size and complexities over the years. While many network additions and alterations carried out so far were as per the recommendations of the Druk Care Consultancy Study Report (2006), the ground realities are evermore different now than anticipated during the study. There is a need to explore opportunities for optimizing the available resources and develop a master plan for future investments.

Some of the prominent driving factors required for the development of the master plan includes but not limited to reliable power supply to the customers, reduction of distribution losses, network capability with the anticipated load growth, optimization of the resources and to develop annual investment plan.

BPC has never carried out comprehensive system studies to improve the distribution system and optimize the available resources. The recurring investment plans (annual) is based on the on-site and field proposals without any technical evaluation being carried out which could have resulted in preventable and excessive investments. Therefore, proper planning is necessary to improve the system for optimal usage of resources.

It is also intended that this master plan is to provide general guidance in preparing long-range system planning. The analysis indicates where up-grades are most likely to be economical and provides insight into the development of a practical transition from the existing system to the proposed long-range system. Based on this analysis, recommendations are made for improving system performance and increasing system capacity for expansion. Periodic reviews of the master plan will be required to examine the applicability of the preferred plan considering actual system developments.

3. Objectives of the Master Plan

The objective(s) of the DSMP (are):

- 3.1 To carry out the system study of the existing distribution network, forecast and come out with the comprehensive ten (10) years strategic distribution plan;
- 3.2 To provide affordable and adequate electricity, reduce losses, improve power quality, reliability, optimize the resources and gear towards excellent customer services; and
- 3.3 To come out with annual investment plans.

4. Scope of the Distribution System Master Plan

Formulation of detailed DSMP (2020-2030) of the Dzongkhag for renewal, reinforcement, and extension of the power distribution system up to DT.

5. Methodology and Approach

In order to better understand the existing distribution system and postulate the credible investment plans; standard framework and procedures had been adopted. However, in the absence of any standardized procedures in BPC for planning of distribution system, the following customized procedures detailed in **Section 5.1** through **Section 5.5** and as shown in **Figure 1** are considered to suit BPC's requirement for developing the DSMP.




Figure 1: Block diagram for distribution system planning for thematic studies

5.1 Data Collection and Validation

In order to carry out the detailed studies with greater accuracy, complete and reliable data for the existing distribution infrastructure is required. Therefore, intensive field investigation was carried out during the months of April and May (2020) to validate the information that was collected. The information required for the studies does not confine to the BPC's internal distribution network but also the developmental activities of the cross-governmental sectors. The power arrangement requirements from these developmental activities were also used to forecast the power demand. The data validation on the distribution system includes the review of all the power sources, medium voltage lines and transformers with that of GIS data of Environment and GIS Division and SLD submitted by respective ESDs which is attached as **Annexure-1**.

5.2 Modeling and Mapping

The feeder wise distribution lines and transformers were modeled and mapped in ETAP tool and the base case was developed for the existing distribution network. The technical parameters for the lines and transformers were considered based on IS 2026, IEC 60076 (Details attached as **Annexure-2**) to develop the base model. Modeling and Mapping detail is attached as **Annexure-1**.

5.3 Analysis and Identification of System Deficiencies

The existing distribution system model was analyzed in the ETAP involving balanced load flow to figure out the network capabilities against the set distribution standards. The load growth was projected using the commonly adopted methodology that is LRM in conjunction to TSA which is based on the historical data and accordingly the behavior of the distribution system was analyzed, and the system deficiencies were identified. The details on load forecast methodology is attached as **Annexure-3**.

5.4 Distribution System Planning

Necessary deterministic and probable distribution system planning methods are proposed to address the system gaps focusing on reduction of losses, improving the reliability and power

quality. Accordingly, any contingency plans, up gradation and reinforcement plans are proposed along with the investment plans incorporating best fit technology.

5.5 Investment Plan

The approved investment plans (from 2020 to 2023) have been validated based on the outcome of the system studies and accordingly, the yearly investment plans are outlined as per the priority matrix as detailed in **Section 9**.

6. Existing Electricity Distribution Network

6.1 Overview of the Power Supply Sources

The power supply to ten (10) Gewogs of Chukha Dzongkhag and industries based in Phuentsholing Gewog is from Phuentsholing, Malbase, Singyegoan, Gedu, Chukha and Watsa HV substations. There are also two MV substations in Phuentsholing and Gurungdangra. The basic electricity distribution network model as seen from the source is illustrated in the schematic diagram is predominantly radial as shown in **Figures 2 & 3**.




Figure 2: Electricity Distribution Schematic Network of Chukha Dzongkhag (Phuentsholing, Singyegoan and Malbase substations)

The customers of Chukha Dzongkhag receive power supply from 66/33kV, 3MVA & 10MVA and 66/11kV, 2x10MVA Phuentsholing substations; 66/11kV, 2x20MVA Malbase substation; 66/11kV, 2x10MVA Singaygoan substation; 66/11kV, 2x5MVA and 66/33kV, 5MVA & 8MVA Gedu substations; 66/11kV, 3x3MVA Chukha substation and 66/33kV, 8MVA Watsa substation.

There are two 33/11kV substations installed at Phuentsholing and Gurungdangra as MV substations.




Figure 3: Electricity Distribution Schematic Network of Chukha Dzongkhag (Gedu and Watsa Substations and Chukha Switchyard)

6.2 Electricity Distribution Lines

The quantity of MV and LV lines operated and maintained by ESD, Phuentsholing is summarized in **Table 1**.

Table 1: MV and LV Line Details

Sl. No.	33 kV		11 kV		Total MV line		LV lines		Total line length
	OH	UG	OH	UG	OH	UG	OH	UG	
ESD, Phuentsholing									
1	111.11	0.98	160.34	13.01	271.46	13.99			923.09
ESSD, Gedu & Lhamoizingkha									
2	219.08	0.13	87.30	5.61	306.38	5.74	625.64	12	312.13
ESSD, Tsimalakha									
3	23.71	0.07	50.46	0.64	74.17	0.71			74.88
Overall Total									
	353.90	1.19	298.11	19.26	652.01	20.45	625.64	12.00	1,310.10

*LV line length is as per Power Data Book 2018.

The total MV line length is 672.46 km and the total LV line length is 637.64km. The ratio of LV to MV line length is 0.95 which reflects an equal proportion of power distribution through MV & LV distribution and is recommended to maintain the ratio. While the ratio of LV to MV line length would vary according to the site conditions, as a general thumb rule, network ratio of 1.2:1 (LV to MV) should be maintained for optimum initial capex and the running and maintenance costs. The majority of the MV distribution network is through 33 kV and 11 kV overhead lines with some network in the town areas being through underground cables.

6.3 Distribution Transformers

The number of distribution transformers operated and maintained by the ESD, Phuentsholing and its ESSDs (Gedu, Tsimasham & Lhamoizingkha) is tabulated in **Table 2**.

Table 2: Total Numbers of Transformers, Installed Capacity and Customers

Sl. No.	Name of Feeder	Voltage Ratio	Number of Transformers	Installed capacity (kVA)	Total number of customers
ESD, Phuentsholing					
1	11 kV Feeder B10 (New Polythyene)	11/0.415kV	9	4933	284

Sl. No.	Name of Feeder	Voltage Ratio	Number of Transformers	Installed capacity (kVA)	Total number of customers
2	11kV Feeder B20 (Karbraytar & Rametey)	11/0.415kV	21	4348	1181
3	11kV Feeder B30 (Tading)	11/0.415kV	91	6475	1034
4	11kV Feeder B40 (BPC Colony)	11/0.415kV	12	5110	544
5	11kV Feeder B220 (Hospital)	11/0.415kV	1	750	23
6	11kV Feeder B230 (Helipad)	11/0.415kV	2	1500	268
9	11kV Feeder B280 (Water Booster)	11/0.415kV	18	9475	1650
10	11kV Feeder B270 (PWD)	11/0.415kV	17	8938	1824
11	11kV Feeder B290 (Yarkay)	11/0.415kV	1	315	10
12	11kV Feeder B300 (Station)	11/0.415kV	1	63	1
13	33kV Feeder B260 (Serina Bosokha)	11/0.415kV	94	2952	1822
14	11kV Feeder B80 (Rangaytrung)	11/0.415kV	15	819	939
15	11kV Feeder B90 (Gurungdangra)	11/0.415kV	3	251	378
16	11kV Feeder B400 (Druk Cement)	11/0.415kV	28	14005	800
17	11kV Feeder B410 (Bhutan Steel)	11/0.415kV	2	3750	1
18	11kV Feeder B420 (Malbase Colony)	11/0.415kV	1	630	31
19	11kV Feeder B460 (Burkey)	11/0.415kV	3	189	152
20	11kV Feeder B50 (BCCL Colony)	11/0.415kV	10	5221	566
21	11kV Feeder B390 (Lower Industrial Estate)	11/0.415kV	17	11686	29
22	11kV Feeder B310 (Upper Industrial Estate)	11/0.415kV	5	6025	10
Total			351.00	87,435.00	11,547.00
ESSD, Gedu & Lhamoizingkha					
1	11 kV Feeder B100 (BBPL)	11/0.415kV	11	4,102.00	465

Sl. No.	Name of Feeder	Voltage Ratio	Number of Transformers	Installed capacity (kVA)	Total number of customers
2	11kV Feeder B110 (Microwave)	11/0.415kV	1	100	1
3	11kV Feeder B120 (THPA II)	11/0.415kV	9	7150	458
4	11kV Feeder B130 (Padechu)	11/0.415kV	10	600	380
5	11kV Feeder B320 (Mirchingchu I)	11/0.415kV	2	275	689
6	11kV Feeder B330 (Geduchu)	11/0.415kV	5	454	84
7	33kV Feeder B160 & C30 (Gurungdangra II)	33/0.415kV	104	10324	2602
8	11kV Feeder B470 (Rinchentse)	11/0.415kV	6	4335	1890
9	11kV Feeder B480 (Mirchingchu II)	11/0.415kV	3	263	175
10	11kV Feeder B500 (Power House)	11/0.415kV	1	100	1
11	11kV Feeder B510 (TRT or BVC)	11/0.415kV	6	750	1
12	11kV Feeder B520 (Surgeshaft)	11/0.415kV	4	2750	1
13	11kV Feeder B530 (Arekha/Sinchekha)	11/0.415kV	5	3510	657
Total			167.00	34,713.00	7,404.00
ESSD, Tsimalakha					
1	11 kV Feeder B170 (BVC)	11/0.415kV	5	1001	153
2	11kV Feeder B200 (Hongkha)	11/0.415kV	3	850	313
3	11kV Feeder B350 (Old Tsimalakha)	11/0.415kV	13	1804	1174
4	11kV Feeder B360 (New Tsimalakha)	11/0.415kV	6	2258	
5	11kV Feeder B440 (CHPC Colony)	11/0.415kV	5	1813	439
6	11kV Feeder B450 (Dzong site)	11/0.415kV	2	500	46
7	33kV Feeder B180 (Shemagangkha)	33/0.415kV	11	517	233
8	33kV Feeder B190 (Chapcha)	33/0.415kV	8	889	259
Total			53.00	9,632.00	2,617.00
Overall Total			571.00	131,780.00	21,568.00

As of June 2019, there were 571 transformers with a total installed capacity of 131,780.00kVA. As evidenced from **Table 2**, the installed capacity of transformer per customer is 6.11kVA per customer. The installed transformers are generally large in capacity and few in number rather than generally small in capacity and more in numbers. The 11kV Tading feeder with a connected installed capacity of 1158kVA (for 53 transformers) which is being operated and maintained by ESSD, Dorokha has its source from 66/11kV Phuentsholing substation. Therefore, this report is inclusive of the above transformers along with the Tading feeder.

7. Analysis of Distribution System

Based on the model developed in ETAP for the existing feeder wise distribution network, analysis of the system was carried out by considering the forecasted load growth from 2020-2030. The quality of power, reliability and energy loss of the existing network were assessed and accordingly the augmentation and reinforcement works are proposed which shall be the integral part of the investment plan. The assessment of MV lines, DTs, power sources, reliability of the power supply and energy & power consumption pattern are presented from **Section 7.1** through **Section 7.4**.

7.1 Assessment of Power Sources

The assessments of the capabilities of the power sources were exclusively done based on the existing (as on 2019) and forecasted load. The source capability assessment had to be carried out to ascertain the adequacy of the installed capacity against the existing load and the forecasted load. The source capability assessment had been carried out bifurcating HV and MV substations as detailed below.

7.1.1 HV Substation

The assessment of 66kV and above substations had to be carried out to ascertain the adequacy of the installed capacity against the existing and the forecasted load.

Table 3: HV Power Sources

Sl.No.	Name of Source	Source Capacity		Forecasted Peak Load (MW)		
		MVA	MW*	2019	2025	2030
1	220/66kV, 50/63MVA Malbase SS (T1)	50.00	42.50	36.00	41.89	44.30
2	220/66kV, 50/63MVA Malbase SS (T2)	50.00	42.50	35.00	40.00	44.00
3	220/66kV, 50/63MVA Malbase SS (T3)	50.00	42.50	38.00	39.30	40.95
	Total	150.00	127.50	109.00	121.19	129.25
4	66/11kV, 20MVA Malbase SS (T1)	20.00	17.00	2.60	4.25	5.36
5	66/11kV, 20MVA Malbase SS (T2)	20.00	17.00	2.60	4.12	5.57
	Total	40.00	34.00	5.20	8.37	10.93
6	220/66kV, 50/63MVA GIS Singigoan (T1)	50.00	42.50	38.23	39.90	42.24
7	220/66kV, 50/63MVA GIS Singhigoan (T2)	50.00	42.50	33.02	40.24	43.45
8	220/66kV, 50/63MVA GIS Singhigoan (T3)	50.00	42.50	33.18	39.42	42.60
	Total	150.00	132.50	104.42	119.56	128.29
9	66/11kV, 10MVA GIS Singhigoan (T1)	10.00	8.50	2.71	4.91	6.69
10	66/11kV, 10MVA GIS Singhigoan (T2)	10.00	8.50	3.02	4.65	5.39
	Total	20.00	17.00	5.73	9.56	12.08
11	66/33kV, 10MVA Pling SS (T1)	10.00	8.50	Kept ideal charge		
12	66/33kV, 10MVA Pling SS (T2)	10.00	8.50	4.80	5.60	6.25
	Total	20.00	17.00	4.80	5.60	6.25
13	66/11kV, 10MVA Pling SS	10.00	8.50	6.71	7.13	7.79
14	66/11kV, 5MVA Pling SS	5.00	4.25	2.95	3.16	3.96
15	66/33kV, 8MVA Gedu SS	8.00	6.80	2.41	3.51	4.42
16	66/33/11kV, 5/2.5/2.5MVA Gedu SS	2.50	2.13	0.90	1.20	1.50
17	66/11kV, 5MVA Gedu SS (T1)	5.00	4.25	1.56	2.33	2.95
18	66/11kV, 5MVA Gedu SS (T2)	5.00	4.25	1.31	1.49	1.66
	Total	10.00	8.50	2.87	3.82	4.61
19	66/11kV, 3x3MVA Chukha Switchyard	9.00	7.65	2.09	2.22	2.40
20	66/33kV, 8MVA Watsa SS	8.00	6.80	1.11	1.45	1.74
	Total	432.50	367.63	248.20	286.76	313.22

*pf of 0.85 was considered for study purpose only.

From the above table it is conclusive that the existing installed HV substation would be adequate to meet the forecasted load till 2030. The total peak power required for the customers of Chukha Dzongkhag as of 2019 is 248.20MW and is expected to reach 286.76MW & 313.22 MW in 2025 & 2030 respectively against the installed capacity of 367.63MW (@0.85x432.50 MVA). The load forecast (power requirement) has been carried out including the load requirement of the LAPs and industries.

The existing peak load of 220/66kV, 3x50/63MVA Malbase substation is 109.00MW as of 2019 and is expected to reach 121.19MW & 129.25MW by 2025 & 2030 respectively against the installed capacity of 127.50/160.65MW (0.85x150/189MVA). Similarly, the existing peak load of 66/11kV, 2x10MVA Malbase substation is 5.73MW and is expected to reach 9.56MW & 12.08MW by 2025 & 2030 respectively against the installed capacity of 17.00MW (0.85x20MVA). Therefore, the installed capacities of both the substations would be adequate to meet the forecasted load growth.

The existing peak load of 220/66kV, 3x50/63MVA Singyegoan GIS substation was 104.42MW and is expected to reach 119.56MW & 128.29MW by 2025 & 2030 respectively against the installed capacity of 127.50MW (150/189MVA). Similarly, the existing peak load of 66/11kV, 2x20MVA Malbase substation is 5.20MW and is expected to reach 8.37MW & 10.93MW by 2025 & 2030 respectively against the installed capacity of 34MW (40MVA). Therefore, the installed capacities of both the substations would be adequate to meet the forecasted load growth.

The existing peak load of 66/33kV, 2x10/63MVA Phuentsholing substation is 4.80MW and is expected to reach 5.60MW & 6.25MW by 2025 & 2030 respectively against the installed capacity of 17.00MW (20MVA). Similarly, the existing peak loads of 66/11kV, 10MVA & 5MVA are 6.71MW & 2.95MW respectively and are expected to reach 7.13MW & 3.16MW and 7.79MW & 3.96MW respectively by 2025 & 2030 respectively against the installed capacity of 8.5MW (10MVA) & 4.25MW (5MVA). Therefore, the installed capacities of both the substations would be adequate to meet the forecasted load growth.

Similarly, the Gedu and Watsa substations and Chukha switch yard would be adequate to cater the load requirement till 2030.

7.1.2 MV Substation

The assessment of 33kV and below substations had to be also carried out to ascertain the adequacy of the installed capacity against the existing load and the forecasted load.

Table 4: MV Power Sources

Sl.No.	Name of Source	Source Capacity		Feeder Load (MW)		
		MVA	MW*	2019	2025	2030
1	33/11kV, 5/6.3 MVA (Pling) Sector I SS	5.00	4.25	2.87	3.39	3.82
2	33/11kV, 5/6.3 MVA (Pling) Sector II SS	5.00	4.25	3.58	4.35	4.98
3	33/11kV, 5/6.3 MVA Gurungdangra I SS (T1)	5.00	4.25	0.95	1.47	1.82
4	33/11kV, 5/6.3 MVA Gurungdangra I SS (T2)	5.00	Ideal charge			
Total		20.00	12.75	7.40	9.21	10.63

Single out assessment of MV substations are carried as follows:

a) 33/11kV, 2x5/6.3MVA (Phuentsholing) Sector I Substation

The FWPL for Sector I (Phuentsholing) substation as on 2019 is 2.87MW and is expected to reach 3.39MW & 3.82MW by 2025 & 2030 respectively which would be adequate. Similarly, the Sector II (Phuentsholing) substation would be adequate enough to meet the increasing power requirement till 2030 as can be inferred from **Table 4**.

b) 33/11kV, 2x5/6.3MVA Gurungdangra Substation

The power supply for the customers of Lhamoizingha and part of Gedu (Phuentsholing) are directly fed from 66/33kV, 8MVA Gedu substation. Therefore, the total FWPL of this feeder is being included in the HV power source assessment. The FWPL for Gurungdangra I substation as on 2019 is 0.95MW and is expected to reach 1.47MW & 1.82MW by 2025 & 2030 respectively. The installed capacity would be adequate to cater the forecasted power demand of Arekha, TRT, Power House, Rinchentse and Mirchingchu II till 2030. Further, the power can be also fed from 33/11kV, Gurungdangra II substation which is currently ideal.

7.2 Assessment of MV Feeders

Feeder wise planning is necessary to ensure that the power delivery capacity, power quality and reliability requirements of the customers are met. In distribution system, capacity assessment of existing MV feeders is important to ensure that feeders are adequate to transmit the peak demand of the load connected to the feeders. Particularly, the capacity assessment of the feeders enables identification of feeders that require reinforcement and reconfiguration works.

The behavior of the MV feeders are assessed based on the existing and forecasted load, feeder wise energy loss, reliability, and single to three-phase line conversions which are outlined vividly in **Section 7.2.1** through **Section 7.2.4**. Further, recognizing that the asset life of the distribution system is thirty years (30), our system should be able to handle the load growth (peak demand) for next 30 years. Therefore, it is equally important to consider the asset life of the system in addition to the assessment of the system in different time horizons.

7.2.1 Assessment of MV Feeder Capacity with Load

The feeder wise peak power consumption was compiled based on the historical data. The array of daily and monthly peak demand was sorted to obtain the annual peak demand. The feeder-wise historical peak demand recorded at the source is presented in **Table 5** and the corresponding feeder-wise annual load curve is presented in **Figures 4** and **5**.

Table 5: Feeder Wise Peak Power Demand (2015-2019)

Sl. No.	Feeder Name	Peak Load Consumption Pattern (MW)				
		2015	2016	2017	2018	2019
ESD, Phuentsholing						
1	11 kV Feeder B10 (New Polythyene)	0.47	0.52	0.53	1.09	1.02
2	11kV Feeder B20 (Karbraytar & Rametey)	0.86	0.84	0.85	0.89	0.90
3	11kV Feeder B30 (Tading)	0.92	0.96	1.12	1.09	1.24
4	11kV Feeder B40 (BPC Colony)	1.86	1.45	1.47	2.22	2.08
5	11kV Feeder B220 (Hospital)	0.14	0.18	0.12	0.15	0.14
6	11kV Feeder B230 (Helipad)	0.50	0.41	0.53	0.41	0.41
7	33kV Feeder B260 (Serina Bosokha)	1.06	1.29	0.80	0.98	1.28
8	11kV Feeder B280 (Water Booster)	2.66	3.20	3.03	3.96	3.58
9	11kV Feeder B270 (PWD)	3.21	1.91	2.56	3.03	2.87

Sl. No.	Feeder Name	Peak Load Consumption Pattern (MW)				
		2015	2016	2017	2018	2019
10	11kV Feeder B290 (Yarkay)	0.17	0.17	0.12	0.16	0.17
11	11kV Feeder B300 (Station)	0.01	0.02	0.02	0.02	0.02
12	11kV Feeder B80 (Rangaytrung)	0.45	0.40	0.50	0.29	0.28
13	11kV Feeder B90 (Gurungdangra)	0.18	0.03	0.02	0.09	0.09
14	11kV Feeder B50 (BCCL Colony)	1.25	1.11	1.03	1.38	1.41
15	11kV Feeder B390 (Lower Industrial Estate)	3.46	3.31	3.31	4.29	4.27
16	11kV Feeder B310 (Upper Industrial Estate)	4.12	3.28	4.40	4.52	3.51
17	11kV Feeder B400 (Druk Cement)	2.09	2.01	2.77	4.19	3.56
18	11kV Feeder B410 (Bhutan Steel)	2.91	2.94	2.89	2.98	2.88
19	11kV Feeder B420 (Malbase Colony)	0.92	0.91	0.87	1.11	1.11
20	11kV Feeder B460 (Burkey)	0.09	0.12	0.10	0.14	0.10
21	33kV Feeder B240 (Sector I)	3.21	1.91	2.56	3.03	2.87
22	33kV Feeder B250 (Sector II)	2.84	2.85	2.80	2.84	2.85
Total		33.39	29.81	32.39	38.86	36.64
ESSD, Gedu & Lhamoizingkha						
1	11 kV Feeder B100 (BBPL)	1.32	1.43	1.43	1.56	1.73
2	11kV Feeder B110 (Microwave)	0.00	0.02	0.01	0.01	0.02
3	11kV Feeder B120 (THPA II)	0.40	0.78	0.50	0.60	0.70
4	11kV Feeder B130 (Padechu/THPA I)	0.15	0.20	0.19	0.17	0.21
5	11kV Feeder B320 (Mirchingchu I)	0.05	0.08	0.09	0.08	0.09
6	11kV Feeder B330 (Geduchu)	0.01	0.01	0.03	0.05	0.09
7	33kV Feeder B160 & C30 (Gurungdangra II)	0.60	0.77	0.95	0.93	0.66
8	11kV Feeder B470 (Rinchentse)	0.20	0.21	0.30	0.20	0.46
9	11kV Feeder B480 (Mirchingchu II)	0.03	0.02	0.01	0.04	0.06
10	11kV Feeder B500 (Power House)	0.01	0.01	0.03	0.02	0.02
11	11kV Feeder B510 (TRT or BVC)	0.09	0.18	0.10	0.13	0.14
12	11kV Feeder B520 (Surgeshaft)	0.04	0.03	0.01	0.08	0.09
13	11kV Feeder B530 (Arekha/ Sinchekha)	0.21	0.30	0.20	0.32	0.44
14	33kV Feeder B140 (Gurungdangra I)	1.20	1.20	1.20	1.20	0.95
Total		4.31	5.24	5.05	5.39	5.66
ESSD, Tsimalakha						
1	11 kV Feeder B170 (BVC)	0.21	0.31	0.16	0.32	0.37
2	11kV Feeder B200 (Hongkha)	0.11	0.20	0.12	0.19	0.20
3	11kV Feeder B350 (Old Tsimalakha)	0.30	0.50	0.48	0.58	0.50

Sl. No.	Feeder Name	Peak Load Consumption Pattern (MW)				
		2015	2016	2017	2018	2019
4	11kV Feeder B360 (New Tsimalakha)					
5	11kV Feeder B440 (CHPC Colony)	0.29	0.49	0.30	0.47	0.55
6	11kV Feeder B450 (Dzong site)	0.21	0.30	0.26	0.22	0.29
7	33kV Feeder B180 (Shemagangkha)	0.13	0.13	0.15	0.13	0.18
8	33kV Feeder B190 (Chapcha)	0.12	0.22	0.17	0.20	0.21
Total		1.37	2.14	1.64	2.10	2.30
Overall Total		39.07	37.19	39.08	46.35	44.59





Figure 4: Overall Plot of Peak Power Demand of ESD, P/Ling & ESSD, Gedu & Tsimasham






Figure 5: Plot of Feeder Wise Peak Power Demand of ESD, P/Ling & ESSD, Gedu & Tsimasham

As evident from **Table 5**, compared to 33kV system, Chukha has more 11kV system and accordingly the 11kV network is more loaded than 33kV system. The 33kV Gurungdangra feeder II which caters power supply to the customers of Lhamoizingkha and part of Gedu has the longest circuit length which is distributed as far as Lhamoizingkha of Dagana Dzongkhag. Apart from the LV customers, Chukha has also MV and HV customers and in fact Chukha has the highest HV & MV customers in the country.

The peak power demand for Chukha Dzongkhag has steadily increased from 39.07MW in 2015 to 44.59MW in 2019. As per the load forecast however, the peak power requirement in 2018 is 46.35MW which is higher than that of 2019. This is attributed due to reduction in power consumption by MV & HV industries.

The assessment of the feeder is carried out based on the following aspects:

- a) System study: Existing load
- b) System study based on forecasted load: 2025 & 2030 scenario

a) System Study (Existing Load)

Based on the peak load (2019-2020) and the thermal capacity of the line, the load flow and accordingly the assessment of the feeder was carried out. The simulation result shows no abnormality and the ampacity capability of the feeders will be within the range with the existing load. The thermal capacity of the different conductor sizes is as shown in **Table 6**.

Table 6: Thermal loading of ACSR conductor at different voltage levels.

Sl. No.	ACSR Conductor Type	Ampacity of Conductor	MVA rating corresponding to the Ampacity
33 kV Voltage Level			
1	RABBIT	193	11.031
2	DOG	300	17.146
3	WOLF	398	22.748
11 kV Voltage Level			
1	RABBIT	193	3.677

Sl. No.	ACSR Conductor Type	Ampacity of Conductor	MVA rating corresponding to the Ampacity
2	DOG	300	5.715
3	WOLF	398	7.582

Ampacity (thermal loading) of the lines have been calculated based on IS 398 (Part-II): 1996 for maximum conductor temperature 85°C for ACSR conductors considering an ambient temperature of 40°C.

The ampacity of all the feeders would be within the permissible range with the existing load however, the 11kV Water Booster feeder would exceed the thermal limit of the conductor as it is forecasted to reach 4.27MW 2030. Due to shorter circuit line length (5.17km only), voltage profile is expected to be within the permissible range and therefore, would pose no technical glitches. However, degree of the feeder loading has to be closely monitored as the accuracy of the forecasted load would deviate more in the distant future.

b) System Study with Forecasted Load (2025 and 2030)

The peak power demand from 2014-2019 has been considered to forecast the peak power demand for the next 10 years (2020-2030) as shown in **Table 7** and **Figures 6, 7 and 8** adopting the commonly practiced methodology of LRM and TSA with the help of ETAP. The detailed load simulation result is attached as **Annexure-4**.

Table 7: Feeder Peak Power Demand Forecast

Sl. No.	Feeder name	Circuit Length (km)	Total Transformer	Connected (kVA)	Total Forecasted Load Growth (MW)		
					2019	2025	2030
	ESD, Phuentsholing						
1	11 kV Feeder B10 (New Polythylene)	1.06	9.00	4,933.00	1.02	1.09	1.32
2	11Kv Feeder B20 (Karbraytar & Rametey)	21.22	21.00	4,348.00	0.90	1.13	1.22
3	11Kv Feeder B30 (Tading)	86.16	91.00	6,475.00	1.24	1.57	1.83

Sl. No.	Feeder name	Circuit Length (km)	Total Transformer	Connected (kVA)	Total Forecasted Load Growth (MW)		
					2019	2025	2030
4	11Kv Feeder B40 (BPC Colony)	1.50	12.00	5,110.00	2.08	2.56	2.96
5	11Kv Feeder B220 (Hospital)	0.14	1.00	750.00	0.14	0.14	0.14
6	11Kv Feeder B230 (Helipad)	1.84	2.00	1,500.00	0.41	0.53	0.63
7	33Kv Feeder B260 (Serina Bosokha)	110.65	94.00	2,952.00	1.28	1.46	1.51
8	11Kv Feeder B280 (Water Booster)	5.17	18.00	9,475.00	3.58	4.35	4.98
9	11Kv Feeder B270 (PWD)	6.36	17.00	8,938.00	2.87	3.39	3.82
1	11Kv Feeder B290 (Yarkay)	0.43	1.00	315.00	0.17	0.21	0.24
11	11Kv Feeder B300 (Station)	0.03	1.00	63.00	0.02	0.02	0.02
12	11Kv Feeder B80 (Rangaytrung)	17.11	15.00	819.00	0.28	0.48	0.50
13	11Kv Feeder B90 (Gurungdangra)	1.36	3.00	251.00	0.09	0.13	0.14
14	11Kv Feeder B50 (BCCL Colony)	3.79	10.00	5,221.00	1.41	1.54	1.65
15	11Kv Feeder B390 (Lower Industrial Estate)	4.49	17.00	11,686.00	4.27	4.51	4.79
16	11Kv Feeder B310 (Upper Industrial Estate)	2.78	5.00	6,025.00	3.51	4.45	4.52
17	11Kv Feeder B400 (Druk Cement)	14.25	28.00	14,005.00	3.56	3.82	4.29
18	11Kv Feeder B410 (Bhutan Steel)	2.42	2.00	3,750.00	2.88	3.02	3.04
19	11Kv Feeder B420 (Malbase Colony)	0.46	1.00	630.00	1.11	1.45	1.74
20	11Kv Feeder B460 (Burkey)	2.77	3.00	189.00	0.10	0.12	0.13
21	33Kv Feeder B240 (Sector I)	0.71	1.00	5,000.00	2.87	3.39	3.82
22	33Kv Feeder B250 (Sector II)	0.73	1.00	5,000.00	2.85	3.93	3.97
Total		283.97	351.00	87,435.00	36.64	43.27	47.28
ESSD, Gedu & Lhamoizingkha							
1	11 kV Feeder B100 (BBPL)	12.54	10.00	4,102.00	1.73	2.26	2.73
2	11Kv Feeder B110 (Microwave)	11.74	1.00	25.00	0.02	0.03	0.04
3	11Kv Feeder B120 (THPA II)	2.96	9.00	7,150.00	0.70	1.00	1.24
4	11Kv Feeder B130 (Padechu)	21.48	10.00	600.00	0.21	0.26	0.30
5	11Kv Feeder B320 (Mirchingchu)	7.72	2.00	275.00	0.09	0.14	0.18

Sl. No.	Feeder name	Circuit Length (km)	Total Transformer	Connected (kVA)	Total Forecasted Load Growth (MW)		
					2019	2025	2030
	I)						
6	11Kv Feeder B330 (Geduchu)	10.30	6.00	1,084.00	0.09	0.20	0.30
7	33Kv Feeder B160 & C30 (Gurungdangra II)	208.83	102.00	4,524.00	0.66	1.01	1.15
8	11Kv Feeder B470 (Rinchentse)	3.71	6.00	4,335.00	0.46	0.68	0.94
9	11Kv Feeder B480 (Mirchingchu II)	4.94	3.00	478.00	0.06	0.10	0.14
10	11Kv Feeder B500 (Power House)	2.48	1.00	100.00	0.02	0.04	0.05
11	11Kv Feeder B510 (TRT or BVC)	7.36	6.00	750.00	0.14	0.17	0.19
12	11Kv Feeder B520 (Surgeshaft)	4.38	5.00	2,100.00	0.09	0.17	0.25
13	11Kv Feeder B530 (Arekha/ Sinchekha)	3.26	5.00	3,510.00	0.44	0.68	0.92
14	33Kv Feeder B140 (Gurungdangra I)	10.38	2.00	10,000.00	0.95	1.47	1.82
Total		312.08	168.00	39,033.00	5.66	8.19	10.24
ESSD, Tsimasham							
1	11 kV Feeder B170 (BVC)	10.35	5.00	1,001.00	0.37	0.54	0.70
2	11kV Feeder B200 (Hongkha)	1.89	3.00	850.00	0.20	0.30	0.39
3	11kV Feeder B350 (Old Tsimalakha)	27.16	13.00	1,804.00	0.50	0.86	1.10
4	11kV Feeder B360 (New Tsimalakha)	8.28	6.00	2,258.00			
5	11kV Feeder B440 (CHPC Colony)	3.29	5.00	1,813.00	0.55	0.82	1.07
6	11kV Feeder B450 (Dzong site)	0.13	2.00	500.00	0.29	0.30	0.34
7	33kV Feeder B180 (Shemagangkha)	13.02	11.00	517.00	0.18	0.22	0.27
8	33kV Feeder B190 (Chapcha)	10.77	8.00	889.00	0.21	0.31	0.39
Total		74.88	53.00	9,632.00	2.30	3.34	4.26
Overall Total		670.93	572.00	136,100.00	44.59	54.81	61.77




Figure 6: Overall Plot of Forecasted Peak Power Demand of ESD, Phuentsholing (Including ESSDs)





Figure 7: Plot of Forecasted Peak Power Demand of ESD, Phuentsholing




Figure 8: Plot of Forecasted Peak Power Demand of ESSD, Gedu & Lhamoizingkhag.

From the above table, it is observed that the highest 33kV feeder peak load as on 2019 is 2.87MW for Sector I Feeder which is expected to grow up to 3.39MW & 3.82MW by 2025 and 2030 respectively followed by 33kV Sector II feeder. In fact, it is forecasted that Sector II feeder would surpass Sector I peak power requirement by 2030. Nonetheless, both the feeders can redistribute the load as and when necessary as they can be operated in parallel mode. Similarly, the highest 11kV feeder peak load is 3.58MW as on 2019 experienced by Water Booster Feeder and is forecasted to reach 4.35MW & 4.98MW by 2025 and 2030 respectively. Therefore, it is conclusive that the existing MV lines would be adequate to evacuate the power to the customers till 2030 without having to do any augmentation works (size of the conductors) as the load carrying capacity of the feeder is within the conductor capacity.

Although it is conclusive that the existing MV lines are adequate to evacuate the power if assessed independently, the voltage profile would go below the standard accepted range of (\pm) 10% should the existing network supply the forecasted load as tabulated in **Table 8**. The load carrying capacity of a feeder is determined by the line length and degree of load connected in addition to other parameters (e.g., ampacity).

Table 8: Feeders with Poor Voltage Profile (2019, 2025 and 2030)

Sl. No.	Name of Feeder	Conductor	Total Circuit Length (km)	End Voltage (kV)	% Variation	Load (MW)		
						2019	2025	2030
A	2019							
1	11kV Tading Feeder(B30)	R/UG	86.16	9.79	11%	1.24	1.57	1.83
2	11kV BBPL Feeder (B100)	D/UG	12.54	9.78	11%	1.72	2.26	2.73
B	2025							
1	11kV Tading Feeder(B30)	R/UG/HV ABC	87.57	9.43	14%	1.24	1.57	1.83
2	11kV BBPL Feeder (B100)	D/UG/HV-ABC	12.54	9.39	15%	1.72	2.26	2.73
C	2030							
1	11kV Tading Feeder(B30)	R/UG	89.07	9.3	15%	1.24	1.57	1.83
2	11kV BBPL Feeder (B100)	D/UG/HV ABC	13.848	9.01	18%	1.72	2.26	2.73

The 11kV feeders which are reflected in the table above would violate the voltage profile with the current loading (as of 2019) and the forecasted load for 2025 & 2030 which are detailed as follows:

a) 11kV Tading Feeder

The Tading feeder has 86.16km constructed on Rabbit and UG conductors. Most of the loads connected to this feeder are rural customer and therefore, the connected loads are static/impedance load (90%) in nature. the voltage profile at the end of the feeder is 11% with the existing load and would decrease with the increased forecasted load. Simulation result shows that it will be 14% & 15% with the 2025 & 2030 forecasted load. As the load considered for carrying out the technical evaluation is based on the peak load, the actual voltage profile would be within the permissible range for the existing load. However, the incremental tap of the PT has to be utilized to improve the voltage regulation for 2025 forecasted load. However, to maintain the voltage regulation within the range with 2030 forecasted load and to improve the reliability, the power supply has to be arranged from Samtse. To address this issue, 1.5km on Rabbit is proposed to be constructed to interconnect

the two feeders (construct from Samtse's Feeder) and the voltage profile would be improved to 9.34% from 15%.

b) 11kV BBPL Feeder

The BBPL Feeder has 13.85km constructed on mixed of conductors (Dog/UG/HV ABC). Most of the loads connected to this feeder are rural customer and therefore, the connected loads are static/impedance load (90%) in nature. the voltage profile at the end of the feeder is 11% with the existing load and would decrease with the increased forecasted load. Simulation result shows that it will be 15% & 18% with the 2025 & 2030 forecasted load respectively. As the load considered for carrying out the technical evaluation is based on the peak load, the actual voltage profile would be within the permissible range for the existing load. However, the incremental tap of the PT has to be utilized to improve the voltage regulation for 2025 forecasted load. However, to maintain the voltage regulation within the range with 2030 forecasted load and to improve the reliability, the power supply has to be arranged from Gurungdangra II feeder and with this arrangement it is expected to improve the voltage regulation from 18% to 7%.

Knowing the degree of significance of quality of power (voltage profile), it is inevitable that voltage regulation be maintained within the permissible range which is required as per the distribution code and the requirement of the end user appliances. Therefore, the feeders whose voltage regulation aren't within the permissible range due to existing or forecasted load would be improved by implementing the corrective measures identified in the foregoing sections. The improvement of voltage profiles after implementing the corrective measures is as detailed in table **Table 9**.

Table 9: Feeder Wise Voltage Improvement

Sl. No.	Name of Feeder	Before		After		Remarks
		Voltage (kV)	% Variation	Voltage (kV)	% Variation	
A	2019					
1	11kV Tading Feeder(B30)	9.79	11%	10.34	5.96%	
2	11kV BBPL Feeder (B100)	9.78	11%	10.32	6.09%	Tap of the PT utilized

Sl. No.	Name of Feeder	Before		After		Remarks
		Voltage (kV)	% Variation	Voltage (kV)	% Variation	
B	2025					
1	11kV Tading Feeder(B30)	9.43	14%	10.10	9.27%	Tap of the PT utilized
2	11kV BBPL Feeder (B100)	9.39	15%	10.00	9.59%	
C	2030					
1	11kV Tading Feeder(B30)	9.3	15%	10.60	9.34%	Re-configuring the source (From Samtse)
2	11kV BBPL Feeder (B100)	9.01	18%	10.24	6.88%	Re-configuring the source (From Gurungdangra)

It is also important for BPC to explore the best fit technology (e.g. installing AVR/voltage boosters) to improve the voltage profile rather than proposing to up-grade the entire conductor size which would be inconvenient to implement as it will involve frequent power interruptions.

7.2.1 Energy Loss Assessment of MV Feeders

Energy losses in the distribution network are inherent as the power transmission and distribution system are associated with the transformers and lines. However, it is crucial to maintain the energy loss at an optimal level by engaging in timely improvement of the distribution infrastructures and not reacting to the localized system deficiencies. The objective of the energy loss assessment is to single out the feeder (s) with maximum loss (es) and put in additional corrective measures to minimize to the acceptable range.

To carry out the assessment, the energy sales, purchase and loss is as tabulated in **Table 10** and as shown in **Figure 9**.

Table 10: Summary of Total Energy Loss (MU)

Sl.No.	Energy	2014	2015	2016	2017	2018	Average
1	Total Energy Requirement (MU)	1,309.38	1,341.48	1,236.39	1,408.94	1,505.47	1,360.33
2	Total Energy Sales (MU)	1,311.75	1,335.01	1,234.38	1,404.69	1,500.25	1,357.22
	Total energy loss (MU)	-2.37	6.46	2.02	4.25	5.22	3.12

Sl.No.	Energy	2014	2015	2016	2017	2018	Average
	Total Loss (%)	-0.18%	0.48%	0.16%	0.30%	0.35%	0.22%





Figure 9: Plot of Total Energy Loss (MU) of ESD, Phuentsholing

Generally, the system loss (MV & LV) is 8.9% and any loss more than this for the distribution network would require in-depth study. An independent study carried out by 19 ESDs for 38 feeders in 2017 (two feeders each in ESD with more loss) showed that average of 6.84% is due to technical loss. The study also showed that loss pattern was never consistent because of variant characteristics of distribution network and loading pattern.

The average energy loss of the entire feeder is 0.22% (3.12 million units on average) from 2014 to 2018. Due to presence of high proportion of HV & MV customers, the average loss is very less compared to the losses of other Dzongkhags. The fluctuating energy loss trend which cannot be able explicitly ascertain may be due to mass rural homes connected to grid through rural electrical projects and anomalous in energy accounting (especially for negative energy loss).

As the feeder wise energy details were not available, the energy loss was redistributed to the feeders based on number of customers connected and circuit line length and accordingly the feeder wise energy loss was worked as shown in **Table 11**. It was computed to single out the problematic feeder with high losses for any remedial and corrective measures that can be arranged to minimize the loss in the future.

Table 11: Feeder Wise Energy Loss (in MU) of ESD, Chukha

Sl. No.	Name of Feeder	Total customer	Circuit Length (km)	2014	2015	2016	2017	2018	Average	%Loss
	ESD, Phuentsholing									
1	11 kV Feeder B10 (New Polythyene)	284	1.06	(0.02)	0.05	0.01	0.03	0.04	0.02	0.00%
2	11kV Feeder B20 (Karbraytar & Rametey)	1,181	21.22	(0.10)	0.28	0.09	0.18	0.23	0.13	0.01%
3	11kV Feeder B30 (Tading)	1,034	86.16	(0.21)	0.57	0.18	0.37	0.46	0.27	0.02%
4	11kV Feeder B40 (BPC Colony)	544	1.50	(0.03)	0.09	0.03	0.06	0.07	0.04	0.00%
5	11kV Feeder B220 (Hospital)	23	0.14	(0.00)	0.00	0.00	0.00	0.00	0.00	0.00%
6	11kV Feeder B230 (Helipad)	268	1.84	(0.02)	0.05	0.02	0.03	0.04	0.02	0.00%
7	33kV Feeder B240 (Sector I)		0.71	(0.00)	0.00	0.00	0.00	0.00	0.00	0.00%
8	33kV Feeder B250 (Sector II)		0.73	(0.00)	0.00	0.00	0.00	0.00	0.00	0.00%
9	33kV Feeder B260 (Serina Bosokha)	1,822	110.65	(0.30)	0.80	0.25	0.53	0.65	0.39	0.03%
10	11kV Feeder B280 (Water Booster)	1,650	5.17	(0.10)	0.27	0.08	0.18	0.22	0.13	0.01%
11	11kV Feeder B270 (PWD)	1,824	6.36	(0.11)	0.30	0.09	0.20	0.25	0.15	0.01%

Sl. No.	Name of Feeder	Total customer	Circuit Length (km)	2014	2015	2016	2017	2018	Average	%Loss
12	11kV Feeder B290 (Yarkay)	10	0.43	(0.00)	0.00	0.00	0.00	0.00	0.00	0.00%
13	11kV Feeder B300 (Station)	1	0.03	(0.00)	0.00	0.00	0.00	0.00	0.00	0.00%
14	11kV Feeder B80 (Rangaytrung)	939	17.11	(0.08)	0.22	0.07	0.15	0.18	0.11	0.01%
15	11kV Feeder B90 (Gurungdangra)	378	1.36	(0.02)	0.06	0.02	0.04	0.05	0.03	0.00%
16	11kV Feeder B50 (BCCL Colony)	566	3.79	(0.04)	0.10	0.03	0.07	0.08	0.05	0.00%
17	11kV Feeder B390 (Lower Industrial Estate)	29	4.49	(0.01)	0.03	0.01	0.02	0.02	0.01	0.00%
18	11kV Feeder B310 (Upper Industrial Estate)	10	2.78	(0.01)	0.01	0.00	0.01	0.01	0.01	0.00%
19	11kV Feeder B400 (Druk Cement)	800	14.25	(0.07)	0.19	0.06	0.12	0.15	0.09	0.01%
20	11kV Feeder B410 (Bhutan Steel)	1	2.42	(0.00)	0.01	0.00	0.01	0.01	0.01	0.00%
21	11kV Feeder B420 (Malbase Colony)	31	0.46	(0.00)	0.01	0.00	0.00	0.01	0.00	0.00%
22	11kV Feeder B460 (Burkey)	152	2.77	(0.01)	0.04	0.01	0.02	0.03	0.02	0.00%
ESSD, Gedu & Lhamoizingkha										
1	11 kV Feeder B100 (BBPL)	465	12.54	(0.05)	0.13	0.04	0.09	0.11	0.06	0.00%
2	11kV Feeder B110 (Microwave)	1	11.74	(0.02)	0.06	0.02	0.04	0.05	0.03	0.00%
3	11kV Feeder B120 (THPA II)	458	2.96	(0.03)	0.08	0.03	0.05	0.07	0.04	0.00%
4	11kV Feeder B130 (Padechu)	380	21.48	(0.06)	0.16	0.05	0.11	0.13	0.08	0.01%
5	11kV Feeder B320 (Mirchingchu I)	689	7.72	(0.05)	0.14	0.04	0.09	0.11	0.07	0.00%
6	11kV Feeder B330 (Geduchu)	84	10.30	(0.02)	0.06	0.02	0.04	0.05	0.03	0.00%
7	33kV Feeder B160 & C30 (Gurungdangra II)	2,602	208.83	(0.51)	1.39	0.44	0.92	1.13	0.67	0.05%
8	33kV Feeder B140		10.38	(0.02)	0.05	0.02	0.03	0.04	0.02	0.00%

Sl. No.	Name of Feeder	Total customer	Circuit Length (km)	2014	2015	2016	2017	2018	Average	%Loss
	(Gurungdangra I)									
9	11kV Feeder B470 (Rinchentse)	1,890	3.71	(0.11)	0.30	0.09	0.20	0.24	0.15	0.01%
10	11kV Feeder B480 (Mirchingchu II)	175	4.94	(0.02)	0.05	0.02	0.03	0.04	0.02	0.00%
11	11kV Feeder B500 (Power House)	1	2.48	(0.00)	0.01	0.00	0.01	0.01	0.01	0.00%
12	11kV Feeder B510 (TRT or BVC)	1	7.36	(0.01)	0.04	0.01	0.02	0.03	0.02	0.00%
13	11kV Feeder B520 (Surgeshaft)	1	4.38	(0.01)	0.02	0.01	0.01	0.02	0.01	0.00%
14	11kV Feeder B530 (Arekha/ Sinchekha)	657	3.26	(0.04)	0.11	0.04	0.08	0.09	0.06	0.00%
ESSD, Tsimalakha										
1	11 kV Feeder B170 (BVC)	153	10.35	(0.03)	0.07	0.02	0.05	0.06	0.04	0.00%
2	11kV Feeder B200 (Hongkha)	313	1.89	(0.02)	0.06	0.02	0.04	0.05	0.03	0.00%
3	11kV Feeder B350 (Old Tsimalakha)	1,174	27.16	(0.11)	0.31	0.10	0.20	0.25	0.15	0.01%
4	11kV Feeder B360 (New Tsimalakha)		8.28	(0.01)	0.04	0.01	0.03	0.03	0.02	0.00%
5	11kV Feeder B440 (CHPC Colony)	439	3.29	(0.03)	0.08	0.03	0.05	0.07	0.04	0.00%
6	11kV Feeder B450 ()	46	0.13	(0.00)	0.01	0.00	0.00	0.01	0.00	0.00%
7	33kV Feeder B180 (Shemagangkha)	233	13.02	(0.04)	0.10	0.03	0.06	0.08	0.05	0.00%
8	33kV Feeder B190 (Chapcha)	259	10.77	(0.03)	0.09	0.03	0.06	0.07	0.04	0.00%
	Overall Total	21,568	672	- 2.37	6.46	2.02	4.25	5.22	3.12	0.22%




Figure 10: Feeder Wise Energy Losses (MU) of ESD, Phuentsholing

The feeder wise energy loss as tabulated in **Table 11** and **Figure 10** indicates that 33kV Gurungdangra II (for Gedu and Lhamoizingha customers) and 11kV Serina Bosokha feeders had contributed the major portion of the energy loss of ESD, Phuentsholing. These feeders have high proportion of circuit length and customers compared to other feeders.

7.2.2 Reliability Assessment of the MV Feeders

Today's emphasis in the power sector has shifted to providing reliable power supply as electricity itself is positioned as one of the essential needs. However, improving reliability comes with its inherent costs as it involves embracing additional preventive and corrective measures leading to substantial up-front capital investment. Any major reliability improvement strategies need to be adopted only after carefully understanding the costs involved and the benefits that will be accrued from implementing such strategies. Failure rate, repair time and restoration time are some important parameters defining reliability. Reducing the values of one or more of the above parameters can improve reliability considerably.

In addition to ensuring that the MV feeders have the required capacity, it is also very important to ensure that the MV feeders are reliable. In order to assess the reliability of the distribution system, the historical data was referred. The yearly (2017-2019) feeder reliability indices summary is compiled as tabulated in **Table 12** and details used to derive such summary is

attached as **Annexure-5**. The interruptions with less than five minutes were omitted from the computation. The actual records (both within and beyond ESDs control) were considered for actual representation to compute the reliability indices. The average reliability indices viz a viz. SAIFI & SAIDI compiled for 2017-2018 are 100.75 & 160.46 respectively which is exceptionally high.

Table 12: Feeder Wise Reliability Indices

Sl.No .	Name of Feeder	2017		2018		Overall Total	
		SAIFI	SAIDI	SAIFI	SAIDI	SAIFI	SAIDI
1	11 KV THPA-Polythene feeder-B010	0.12	0.10	0.43	1.11	0.28	0.61
2	11 KV Karbarey-Ramety Feeder-B020	5.47	4.35	10.17	14.13	7.82	9.24
3	11 KV Tading Rural Feeder-B030	4.01	4.49	14.93	22.02	9.47	13.25
4	11 KV Pepsi BPC Colony Feeder-B40	0.28	0.34	1.60	1.86	0.94	1.10
5	11 KV New Hospital Feeder-B220	0.00	0.01	0.02	0.00	0.01	0.00
6	11 KV Helipad linked feeder-B230	0.57	4.97	1.34	0.84	0.96	2.91
7	33 kV Druk Iron & Steel feeder-B150	0.00	0.02	-	-	0.00	0.01
8	33 kV Sector II-B240	3.48	0.53	6.02	6.13	4.75	3.33
9	33 kV Sector II-B250	7.25	0.42	13.74	9.33	10.49	4.88
10	33 kV Serina Bosokha-B260	17.27	23.69	22.70	53.74	19.99	38.72
11	11 kV Gurungdara rural -B80	0.49	1.41	0.47	0.70	0.48	1.06
12	11 kV TCBL Fdr-B50	0.02	0.04	0.01	0.03	0.02	0.04
13	11 kV Industrial area upper terrace-B310	0.00	0.01	0.00	0.01	0.00	0.01
14	11 kV Industrial area lower terrace-B390	0.02	0.10	0.01	0.04	0.02	0.07
15	11 kV Druk Cement Fdr-B400	0.55	0.73	0.92	2.01	0.73	1.37
16	11 kV Bhutan Steel Fdr	0.00	0.01	0.00	0.00	0.00	0.01
17	11 kV Malbase Colony Fdr	0.01	0.01	0.03	0.07	0.02	0.04
18	11 kV Malbase Burkey Fdr-B460	0.01	0.01	0.05	0.15	0.03	0.08
19	33kV Gurungdara I-B140	0.00	0.00	0.00	0.00	0.00	0.00
20	33kV Gurungdara II-B160&C30	22.43	25.71	20.87	47.15	21.65	36.43
21	33kV Mirchingchu-B320	0.92	0.80	0.70	0.83	0.81	0.81
22	11kV BBPL Fdr-B100	4.36	3.31	3.39	3.99	3.87	3.65
23	11kV M/Wave Fdr-B110	0.77	26.60	0.75	6.19	0.76	16.40
24	11kV THPA-1 Fdr-B120	0.61	1.23	0.80	0.88	0.71	1.06

Sl.No .	Name of Feeder	2017		2018		Overall Total	
		SAIFI	SAIDI	SAIFI	SAIDI	SAIFI	SAIDI
25	11kV Geduchu Fdr-B330	0.00	0.00	0.78	1.30	0.39	0.65
26	11kV Padechu Fdr-B130						
27	11kv Old & new Tsimalakha -B350	7.58	7.74	13.41	8.69	10.50	8.21
28	11kv THPA I- B370	-	-	-	-	-	-
29	11KV BVC Fdr-B170	0.44	0.01	0.68	3.18	0.56	1.60
30	11kV THPA II-B380	-	-	-	-	-	-
31	11kV THPA III-B200	0.06	0.00	-	-	0.03	0.00
32	33kV Shemagangkha-B180	1.22	0.77	3.41	17.88	2.32	9.33
33	33kV Chapcha-B190	0.79	0.20	1.69	8.55	1.24	4.38
34	11kV Chukha Colony-B440	1.67	0.14	2.04	2.06	1.85	1.10
35	11kV colony-B450	0.06	0.22	0.08	0.07	0.07	0.14
Total		80.48	107.97	121.02	212.96	100.75	160.46

The above summary indicates that the 11kV Karbary-Rametey, Tading Rural Feeder, Old Tsimalakha and 33kV Sector-I (B240), Sector-II (B250), Serina Bosokha and Gurungdara II feeders sustained more interruptions compared to other feeders. Generally, power interruptions are due to transient, operation and maintenance, HT fuse replacement, over current/earth fault current, lightning and rainfall which are inter-related to each other for most of the cases.





Figure 11: Feeder Wise SAIFI & SAIDI of ESD, Phuentsholing



Root Causes	Frequency	% Distribution
Transient Fault	352	18.57%
ARCB/G.O/LBS O&M	309	16.30%
HT fuse replacement/Jump	292	15.40%
OC & Earth fault current	274	14.45%
Maintenance (Line & SS)	191	10.07%
Lightning/Thundering/Heavy rainfall	163	8.60%
Right of way	82	4.32%
SMD/ Preventative Maintenance)	77	4.06%
LA Replacement	43	2.27%
Others*	113	2.11%
Total	1896	100%

Figure 12: Root Causes of the Interruptions

*Others: Adhoc works, disc/pin insulator damage, fallen trees and grid failure.

The root causes of the power interruptions are due to transient fault, operation and maintenance of switching equipment, HT fuse replacement, OC & earth fault current, maintenance of lines and substations and lightning, thunder and heavy rainfall had also significantly contributed towards the power interruptions.

There are switching devices (ARCBs and LBS) installed in these feeders for better operation and maintenance flexibility. In order to address the reliability issue of the feeders, following remedial and corrective measures are proposed:

a) 11kV Tading Feeder

The circuit length of this feeder is 86.16km and passes through thick vegetation and rugged terrain and becomes inaccessible due to swelling of Amochu river. The area receives heavy rainfall during the summer seasons and lightning strikes. The feeder recorded SAIFI & SAIDI of 9.47 & 13.25 on average for recent three years. There are 6 LBS and an ARCB installed in this feeder as a switching and control mechanism. In order to further improve the reliability of the feeder, it is proposed to install additional ARCB, Sectionalizer and FPIs.

- Re-configuration of sources

It is proposed to construct interconnecting line from Samtse feeder with that of Tading and arrange the power supply to 53DTs from Samtse. This would enable the power system improvement for customers connected to both the feeders.

- Installation of more and smart switching devices

b) 33kV Serina Bosokha Feeder

The circuit length of this feeder is 110.65km and passes through thick vegetation and rugged terrain and becomes inaccessible. The area receives heavy rainfall and lightning strikes during summer season. The feeder recorded SAIFI & SAIDI of 19.99 & 38.72 on average for recent three years and is one of the worst amongst all the feeders in terms of reliability indices. There are 7 LBS and an ARCB installed in this feeder as a switching and control mechanism. In order to further improve the reliability of the feeder, it is proposed to install additional an ARCB, 3 Sectionalizer, 5 FPIs and 2 LBS.

c) 33kV Gedu-Lhamoizingkha Feeder

The circuit length of this feeder is 208.83km and passes through thick vegetation and rugged terrain. This feeder has the longest circuit length and is extended as far as Lhamoizingkha under Dagana Dzongkhag, thus sustaining more interruptions. The area receives heavy rainfall and lightning strikes during summer season. The feeder recorded SAIFI & SAIDI of 21.65 & 36.43 on average for recent three years and is the worst amongst all the feeders in terms of reliability indices. There are 10 LBS and 4ARCBs installed in this feeder as a switching and control mechanism. In order to further improve the reliability of the feeder, it is proposed to install additional 5 Sectionalizers and 14 FPIs.

d) 11kV Karbatar-Rametay Feeder

The circuit length of this feeder is 21.22km and passes through thick vegetation and rugged terrain. The area receives heavy rainfall and lightning strikes during summer season. The feeder recorded SAIFI & SAIDI of 7.82 & 9.24 on average for recent three years. There are only 5 LBS installed in this feeder as a switching and control mechanism only. In order to further improve the reliability of the feeder, it is proposed to install additional two Sectionalizers, 3 FPIs, 2 Sectionalizers, an ARCB and 2 LBSs.

e) 33kV Sector II Feeder

With the circuit length of 0.73km for this feeder, it is not anticipated to experience many interruptions as in the case of feeder with longer circuit length and more loads connected. However, the record shows that it has recorded 10.49 & 4.88 as an SAIFI & SAIDI in recent years which is exceptionally high. The reason behind this incredible figure is due to faulty incomer breaker. As the area experiences longer humid weather, there is continuous formation of moisture and thus conventional breakers fails to operate as it is intended to. Therefore, it is proposed to install breaker (GIS) similar to those installed in the HV substations (Malbase, Singyegoan etc...). Currently, the breaker is bypassed which is not a good practice.

f) 11kV Old Tsimalakha Feeder

The reliability index of the 11kV Old Tsimalakha is 10.50 & 8.21 on average for recent years. On the contrary, the reliability in reality is half the recorded indices as the data captured is the total of two feeders i.e. 11kV Old and New feeders.

7.2.2 Single Phase to Three-Phase Conversion

BPC during the RE expansion programs considered for low-load remote and rural homes with two of the three-phases of the MV designed with single phase transformers. However, with the adoption of mechanized agricultural machinery, the requirement of three-phase power to cater these loads is gaining an importance even in the rural areas. Therefore, R&DD, BPC in 2017 has carried out the “Technical and Financial Proposal on Converting Single Phase to Three-phase Supply” to come out with the alternatives for providing three-phase power supply where there are single phase power supplies. It was reported that while all the alternatives required the third conductor of the MV system to be extended on the existing poles following three proposals along with the financial impact were proposed:

a) Alternative -I

It was proposed to replace all the single-phase with three-phase transformers and this option as contemplated as not feasible as a replacement by three-phase transformers and distribution boards will lead to idle storage of single phase transformers of BPC.

b) Alternative -II

It was proposed to utilize the existing single-phase transformers to form three-phase transformations along with the additional purchase of three-phase transformers and additional pole structures. Further, single phase transformers of identical make, type, and rating can be only used to make three-phase power available.

c) Alternative -III

Option 3 is found to be a techno-commercially viable alternative as the lines can be easily upgraded to three-phase by constructing third conductor on existing pole structures. The transformer can be upgraded from single phase to three-phase as and when the demand for 3-phase supply comes. The line up-gradation across the country would amount to Nu. 96.67 million (Detail in **Annexure-6**) excluding the cost of three-phase transformers which have to be procured on need-basis, rather than one-time conversion in general.

The total single-phase line length required to be converted to three-phase in the Dzongkhag is 99.84 km and the estimate for such conversion would require Nu. 12.21 Million.

As the single phase to three network conversions is a demand-driven planning, conversions works shall be carried out based on the demand from the customers which would be more techno-commercially viable alternatives. Therefore, considering the anticipatory conversion requirement, the conversion of networks is proposed in the later stage of the DSMP.

7.3 Assessment of the Distribution Transformers

The number of distribution transformers operated and maintained by the ESD is tabulated in **Table 2.**

7.3.1 Distribution Transformer Loading

The DTs are one of the most critical equipment of the distribution network and assessment of loading pattern along with the remaining asset life are crucial to ascertain the adequacy and performance of the transformer. The capability evaluation is based on historical peak load loading pattern and forecasted peak load growth of the feeder.

As per the peak loading pattern, some of the existing transformer capacities would not be adequate to cater the forecasted load growth for next ten (10) years. Accordingly, the capacities of the transformers need to be up-graded and such proposal is tabulated in **Table 13**. The individual DT loading details used to derive the summary is attached as **Annexure-7**.

Table 13: Forecasted Transformer Loading of ESD, Phuentsholing

Sl.No .	Name of substation location	Capacity (kVA)	Peak Load (kVA)	% Loading	Peak Load(kVA)	% Loading	Peak Load(kVA)	% Loading
2019	2025	2030						
1	Damdara DT	125	90.89	72.71%	114.28	91.42%	133.78	107.02%
2	Sector II DT (33/11kV)	5000	3.40	68.00%	4.39	87.76%	5.15	103.02%
3	Lower Market USS	750	525.05	70.01%	680.84	90.78%	780.97	104.13%
4	Upper Market DT	1000	789.68	78.97%	921.12	92.11%	1037.62	103.76%
5	Tinkilo DT	125	100.89	80.71%	117.68	94.15%	132.57	106.05%
6	Rangaytrung DT	125	89.56	71.65%	155.88	124.71%	162.38	129.90%
7	Barsa DT	63	44.67	70.90%	61.54	97.68%	67.84	107.68%
8	Bmobile DT	63	58.99	93.63%	64.92	103.05%	69.56	110.41%
9	Bmobile DT (Balujora)	500	428.56	85.71%	466.21	93.24%	524.79	104.96%
10	Toribari DT	250	220.90	88.36%	240.31	96.12%	270.50	108.20%
11	Malbase Village DT	63	44.90	71.27%	66.24	105.15%	73.97	117.42%
Total Distribution Transformers		11						

Assuming that the load growth of the rural homes is not expected to grow similar to that of urban dwellings, it is strongly recommended to closely monitor the actual load growth and accordingly plan remedial measures for those transformers although some of the transformers would get overloaded as per the forecasted load. Nevertheless, considering the actual site-specific growth rate and judgment of the field offices, it is recommended that arrangements be made for the up-gradation of 11 transformers. However, cross-swapping the existing transformers prior to procurement of new transformers would mean that, only eight (8) transformers have to be procured as tabulated in **Table 14**.

In addition to above, 2x750 kVA & 500kV transformers would be required to cater the power requirement of the Toribari town plan.

Table 14: Proposed Lists of DTs Requiring Up-grading

Sl.No.	Name of Feeder	Capacity (kVA)	Peak Load (kVA)	% Loading	Proposed kVA	Adjustment/New	Remarks
List of Transformers for 2019-2025							
1	Lower Market USS	750	525.05	70.00%	1000	New	Need 750kVA also and new is for lower and upper markets
2	Tinkilo DT	125	117.68	94.15%	125	New	Additional 125kVA required
3	Rangaytrung DT	125	155.88	124.71%	500	New	125kVA not required
4	Bmobile DT	63	64.92	103.05%	125	Adjustment-Rangaytrung DT	63kVA not required
5	Malbase Village DT	63	66.24	105.15%	125	New	63kVA not required
List of Transformers for 2025-2030							
1	Damdara DT	125	133.78	107.02%	500	New	125kVA not required
2	Barsa DT	63	67.84	107.68%	125	Adjustment-Damdara DT	63kVA not required
3	Bmobile DT (Balujora)	500	524.79	104.96%	1000	New	Need the 500kVA also
4	Toribari DT	250	270.50	108.20%	3x750	New	3 nos of 750kVA required
5	Toribari DT				500	New	
Total number of transformers required to up-grade						10	
Extra Transformers			63	2	2019-2025	Can cross check with the nearest ESDs for adjustment	
			63	1	2025-2030		
			125	1	2025-2030		
Total extra				4			

7.3.2 Asset life of Distribution Transformers

The DTs are one of the most critical equipment of the distribution network. Therefore, assessment of existing loading pattern together with the remaining asset life is crucial to

ascertain its capabilities to cater the projected load growth. The life cycle of transformer and its mapping provides the clear information for its optimal utilization and development of an asset replacement framework.

The record was generated from the SAP-ERP system on December 9, 2019 and compiled for those DTs which have been put to use for 25 years and more.

Table 15: List of Outlived Transformers

Sl. No.	Asset	Name of Location	Unit	Qty	Cap. Date	No. of Years put to Use	Sl. No.
1	1502205	250 KVA, Stanelce Pvt Ltd. Yer of mfg: 1989, Gedu	NO	1	1-Jul-89	30.44	820123
2	1502212	125 KVA, Stanelec Pvt. Ltd. Yer of Mfg. 1989	NO	1	1-Jul-89	30.44	S/4160
3	1502232	63 KVA, Kirloskar Electric. Yer of Mfg: 1988	NO	1	1-Aug-89	30.35	86AD-125/3
4	1502237	400 KVA,11/400, Winpower make,at	NO	1	1-Jul-89	30.44	SL # 132489
5	1502243	500 KVA, uttam Bharat,11/400, at L. Market	NO	1	1-Jul-89	30.44	SL # 17645
6	1502244	500 KVA, Winpower,11/400 at ECE Ind Estate	NO	1	1-Jul-82	37.44	SL# 132989
Total Transformers				6			

7.3.3 Replacement of Single Phase Transformers

As discussed in the “Single Phase to Three-phase Conversion” of the distribution network it will be more economical and technically feasible to convert the single to three-phase transformers on need basis. Total of Nu. 283.00 million is estimated for replacing all single-phase transformers including the distribution board. The detailed work out is produced as **Annexure-8**.

There are 48 single phase transformers in the Dzongkhag and the estimate for up-grading all the single to three-phase transformers would require Nu. 9.38 Million. As the conversion from single to three-phase transformer is demand base, the plan has been distributed in ten year-span.

7.4 Power Requirement for Urban Areas by 2030

Phuentsholing is one of the Thromdes located in south-western foothills of the country bordering the Indian state of Bengal. It is the commercial hub for western Dzongkhags and is the gateway of the country India. It has been envisioned to uniformly develop the Thromde and as a result it has planned and demarcated the LAPs. Under the Phuentsholing Thromde jurisdiction, there are 9 LAPs identified so far as tabulated in **Table 16**.

Table 16: LAPs under Chukha Dzongkhag

Sl. No.	Name of LAP	Approximate Number of Plots	Approximate Power Demand (MW)
1	Ahlay LAP	124	7.055
2	Pekarzhing Lap	150	10.160
3	Pasakha Lap	117	7.26
4	Rinchending LAP	195	9.596
5	Kharayphu LAP	35	1.93
6	DamdaraKarbray LAP	134	7.635
7	Ammochu Lap	58	3.160
8	Chamkuna LAP	17	0.970
9	Toorsatar Lap	63	3.685
Total		893	51.451

a) Ahlay LAP




Figure 13: Ahlay LAP

The Ahlay LAP has fewer numbers of customers at present and major portion of the load is being drawn by Yuenten Kunjung Private School. However, the LAP has been already earmarked to be developed and accordingly the power requirement would increase. Therefore, total power requirement for the LAP is forecasted to be 7.055 MW and to meet the demand load, 2x750KVA USS is proposed along with proposal to up-grade the existing 63kVA Ahaly transformer to 500kVA substation.

b) Pekarzhing LAP

Currently, there are two MV customers in this LAP (M/s. Zimdra Foods Pvt. Ltd and M/s. Neetshel Pvt. Ltd. and are fed from existing 25kVA Khogla transformer. There is a plan that there will be mixture of small scale industries, MV customers, LV bulk customers and residential cum commercial buildings which would require a load of 10.16MW. Therefore, to meet the increasing power demand, it is proposed to install 3x750kVA USS along with proposal to up-grade the existing 25kVA to 500kVA pad substation.




Figure 14: Pekarzhing LAP

c) Pasakha LAP

The Pasakha LAP includes Malbase, Gurungdangra, Chengamri (Balujora) and other non-pollutant industries in Pasakha area.




Figure 15: Pasakha LAP

The total forecasted load for this LAP is 7.26MW by 2030 and therefore, 750kVA USS at Malbase, 1000kVA package SS at Bhalujora and 750kVA at Gurungdara (up-grade from existing 63kVA). The existing 500kVA at Bhalujora would be still required to meet the power requirement with the proposed 1000kVA.

d) Rinchending LAP

Rinchending LAP is the biggest identified LAP covering maximum area starting from Tinkilo and the highest power consumer of this LAP is the College of Science and Technology. However, most of the areas are geographically unstable for developmental activities to be initiated. The developmental activities in this area have really picked up and the existing distribution network may not be adequate to meet the increasing power requirement. It is forecasted that the power requirement would reach 9.60 MW by 2030. The existing 125kVA transformer of Tinkilo is 94.15 % loaded and might get overloaded by next year and similar trend is expected with the Rinchending 500kVA transformer. Therefore, it is proposed to install additional 125kVA in Tinkilo and up-grade the 500kVA to 1000kVA (USS) for Rinchending transformer.

Recently, BPC has installed 250kVA transformer on cost sharing basis with Thromde at Lower Rinchending which may not be adequate to meet the power requirement. Therefore,

additional 750kVA USS is proposed at Lower Rinchending. The existing 500kVA substation above Kharbandi Goenpa will feed to Middle Rinchending LAP. As there is no source for the LAP below Goenpa, 500kVA Pad substation is proposed.



Figure 16: Rinchending LAP

e) Kharayphu LAP

Kharayphu LAP is located opposite to Karbraytar and this LAP is still developing. BPC has recently installed 500kVA Pad substation to cater the demand load for construction.



Figure 17: Kharayphu LAP

The forecasted demand load of the LAP till 2030 is 1.93MW and to cater the forecast demand load, 2x750kVA USS is proposed.

f) Damdara LAP

Damdara Karbray LAP is one of the rapid developing LAPs and it consists of two different areas called Damdara and Karbraytar. The total forecasted demand load for the LAP for Damdara and Karbraytar is 3.670 MW and 3.965MW respectively till 2030. The existing 1000kVA USS has lengthy LT network and the customers of Karbraytar top have been expressing the grievances of erratic power supply lately. The quality of power is anticipated to worsen with the increase in power requirement. Therefore, it is proposed install additional 125kVA transformer to address the issue. Similarly, the existing 125kVA transformer at Damdara is 72.71% loaded and is forecasted to be overloaded by 2030. Therefore, it is proposed to up-grade the existing 125kVA to 500kVA and install additional 500kVA Pad SS. Addition to this, Thromde also suggested BPC to convert the overhead line to UG network especially at Damdara LAP.




Figure 18: Damdara LAP

g) Amochu LAP

The Thromde has demarcated the LAP area without including the Amochu Land Reclamation Township Project (ALRT). The total forecasted demand load for the LAP is 3.161MW. The ALRT is under full swing and Thromde is also scheduling to execute the

development of the LAP simultaneously with the project. Therefore, to meet the demand load, 750kVA USS and 500kVA Pad SS is proposed for the LAP.



Figure 19: Amochu LAP

h) Chamkuna LAP

Chamkuna LAP is located alongside the Amochu river bank and on the way to Samtse high way. With the steep slope and unstable area in the proposed LAP, the Thromde has planned only few infrastructures in this LAP and the forecasted demand load for this LAP is only 0.96MW. However, since there is no electrical infrastructure in this proposed area, 125kVA pole mounted SS is proposed for the LAP.



Figure 20: Chamkuna LAP

i) Toorsatar LAP

With the space constraint in the Phuentsholing, Thromde has demarcated the Toorsatar area as one of the Thromdes LAP and further, the ALRT project will also cover till Toorsatar base. The forecasted demand load for this lap is 3.685MW. Currently, Toorsatar area has 25kVA substation which is adequate to cater the load to this area.



Figure 21: Toorsatar LAP

However, if the Thromde initiates the Toorsatar LAP development, the existing power supply arrangement may be adequate to meet the demand. Therefore, the existing 25kVA is proposed to up-graded to 750kVA package SS and another additional 750kVA package SS is proposed in this LAP.

7.4.1 MV & LV lines for LAPs

The LV & MV lines have to be proposed for distribution of power to the identified LAPs which are detailed as follows:

- a) The extension of 11kV HV ABC (95sqmm) from BPC Colony to Bangay (Amochu) as an alternative source is proposed mainly to improve the reliability to the customers who reside at Amochu. With the Thromde's LAP development strategies, reliable power source is must

and further, these customers fall under Thromde's jurisdiction. Currently, customers of Amochu are fed from Tading feeder which is susceptible to interruptions compared to other feeders. Therefore, it is proposed to extend the 11kV line from BPC colony.

- b) The re-alignment of 33 kV double circuit feeder from Phuentsholing 66 kV substation to 33/11 kV Sector 2 Substation by 33kV 3Cx150sqmm UG XLPE cable (0.38km) & 33kV HV ABC 1cx95sqmm (0.69km) is proposed due to new NPPF colony which would directly fall under the line. Although, proposal was approved in 2017, the work was not executed due to non-availability of clearances which should have been arranged by By-Pass Road, SASEC project. However, the work is kept as spill over and it will be executed by mid of 2020, as the project is in the verge of completion.
- c) As per the result of ETAP, the additional line needs to be extended from 33/11kV Gurungdangra SS in order to improve the voltage profile of BBPL feeder.
- d) The conversion of ASCR conductor to HV ABC 1cx95sqmm cable (1.5km) line within the Tsimasham town area is proposed for better safety and to resolve the right of way issue with private land owners.
- e) As a contingency plan (in case of any breakdown or any O&M works to be carried out at 66kV Phuentsholing substation) the power supply to Phuentsholing has to be fed from 400KV Malbase substation through Druk Cement feeder. Therefore, the re-sizing of ACSR Dog conductor to wolf conductor is proposed.
- f) The study carried out for HT network in the core town of Phuentsholing shows normal, but, all the LT cable under core town get overloaded and need to be resized with proportional to load forecast.
- g) 33kV Gedu-Lhamoizingkha feeder being a worst feeder in reliability front and if Wangchu project gets materialized, the proposal for extending additional back up source from Gamana (Point of 66/33kV substation by Wangchu project) and connect the existing 33kV line feeding towards Lhamoizingkha need to be incorporated, so that the reliability indices of Lhamoizingkha will be improved.

- h) By the proposal of upcoming LAP by Thromde, the conversion of bare conductor to UG cable has to be incorporated in order to resolve the Right of way issues with public, aesthetic view of Thromde LAP and to improve the safety of the general public. Addition to this, the bare conductors passing nearby the school and colonies also have to convert to insulated conductor.

7.4.2 Distribution Transformers

Currently, there are nine (9) identified LAPs under Phuentsholing Thromde which would get materialized sooner or later. Therefore, to arrange the power supply, existing installed transformers may not be adequate to meet the forecasted power demand; it is therefore, proposed to up-grade and install additional transformers in various LAPs as tabulated in **Table 17**.

Table 17: Proposed Distribution Transformers in LAPs

Sl.No.	Name of LAP	Capacity (kVA)	Qty	Unit	Remarks
1	Ahaley LAP	750	2	No	Package SS
		500	1	No	OD SS
2	Pekarzhing LAP	750	3	No	Package SS
		500	2	No	OD SS
3	Pasakha LAP	1000	1	No	Package SS
		750	2	No	Package SS
4	Rinchending LAP	1000	1	No	Package SS
		750	1	No	Package SS
		500	1	No	OD SS
		125	1	No	OD SS
5	Kharayphu LAP	750	2	No	Package SS
6	Damdara & Karbray LAP	500	2	No	OD SS
		125	1	No	OD SS
7	Amochu LAP	750	1	No	Package SS
		500	1	No	OD SS
		125	1	No	OD SS
8	Chamkuna LAP	125	1	No	OD SS
9	Toorsatar LAP	750	2	No	Package SS

8. Distribution System Planning

The distribution network of the Dzongkhag has a radial topology with significant risk of high interruptions (fault in one location would mean that the entire customer in the network would experience the outage). Having alternate routes, sources or any contingency plan would significantly improve the reliability and power quality. In order to have robust and hard-lined distribution network, there is a need for good contingency plans with adequate sources to reduce the downtime. However, any provision to improve the power system would incur additional capital cost in addition to recurring additional preventive and corrective costs.

Therefore, to meet the system shortfalls against the set standard and to keep abreast with the forecasted load growth, proper distribution system planning is required which are detailed from **Section 8.1** through **Section 8.4**.

8.1 Power Supply Sources

8.1.1 HV Substations

As detailed in **Section 7.1.1**, the installed HV substation capacities would be adequate to cater the forecasted load of the customers of Chukha Dzongkhag. Therefore, neither the existing substation capacities would be required to be up-graded nor construction of additional substations.

8.1.2 MV Substations

As detailed in **Section 7.1.2**, the installed MV substation capacities would be adequate to cater the forecasted load of the customers of Chukha Dzongkhag. Therefore, neither the existing substation capacities would be required to be up-graded nor construction of additional substations.

8.2 MV and LV Lines




Figure 22: Proposed Distribution Network under ESD, Phuentsholing

As detailed in **Section 7.4.1** of this report, it is proposed to extend, construct MV and LV lines to in various locations to arrange power supply according to the load forecast, developmental activities, to improve reliability, reduce loss and improve the power quality. **Figure 22** shows the proposed distribution network.

8.3 Distribution Transformers

As listed in **Section 7.3.1**, these transformers need to be up-graded either by procuring or by cross-swapping the required capacities. Out of 11 listed transformers, procurement of only 8 DTs would be required which has been worked out based on the likelihood of load growth of the areas and inculcating the fair judgment of the field personnel. Similarly, twenty-six (26) DTs would be required to cater the power supplies to nine (9) identified LAPs under Phuentsholing Thromde which would be executed over the period of time.

8.4 Switching and Control

Switching and control system is required to take care of the system during faulty situations which ultimately is going to take care of the failure rate, repair and restoration time. This in turn would improve the reliability, safety of the equipment and online staff, optimizes the resource usage and more importantly the revenue generation will be enhanced. Similarly, in order to capture the real time data and information, it is inevitable to have automated and smart distribution system. The feeders which are more susceptible to faults are identified with proposed restorative measures through the studies. With the exception of tripping of breakers in the sending end substations, existing distribution network is neither automated nor smart to detect the faults and respond in real-time manner. The automation and smart grid components are detailed in Smart Grid Master Plan 2019.

8.4.1 Intelligent Switching Devices

As reflected in **Section 7.2.3**, 11kV Karbary-Rametey, Tading Feeder, Old Tsimalakha and 33kV Sector-I (B240), Sector-II (B250), Serina Bosokha and Gurungdara II feeders sustained more interruptions compared to other feeders. Therefore, additional preventive and corrective measure for these feeders need to be put in place. In order to improve reliability and power quality of these feeders, it is proposed to have technology in place to respond to fault and clear it accordingly rather than through ex post facto approach. Therefore, it is proposed to enhance the existing switching and control system by having latest suitable and user-friendly technology (automatic). The coordinated arrangement of Intelligent Switching Devices (ISD) like ARCBs, Sectionalizers and FPIs would significantly improve the control and operation mechanism of the network. **Table 18** and **Figures 23, 24 & 25** shows the proposed switching devices and RMUs for the distribution network for easing operation and maintenance and for improving the reliability of the power supply of the Dzongkhag.

Reliability of the lines and substations can also be enhanced through training of line staff. They need to be equipped with the knowledge, skills, and the confidence to operate and maintain the distribution infrastructure. For instance, the linemen of the ESDs need to develop the confidence to change DO fuses online using hot sticks instead of the usual practice of taking shut down of the whole feeder. However, having the right tools, equipment, and especially spares (of

appropriate specifications) is a prerequisite. Although it is not possible to quantify the reliability indices that can be achieved with preventive and corrective measures in place, the proposed contingency plans would significantly improve the power quality.

However, the quantum and location of the devices to be installed shall be based on the Smart Grid Master Plan 2019.

Table 18: Existing and Proposed Switching Equipment

Sl. No.	Feeder Name	ARCBs		Sectionalizers		FPIs		LBS	
		Exist	Prop	Exist	Prop	Exist	Prop	Exist	Prop
1	11kV Feeder B30 (Tading)	1	2		1		5	6	
2	11kV Karbraytar & Rametey	1			2		2		1
3	11 kV Feeder B10 (New Polythyene)						1		
4	11kV Feeder B40 (BPC Colony)						1		
5	11kV Feeder B230 (Helipad)				1		2		
6	33kV Feeder B260 (Serina Bosokha)	1	1		3		5		
7	11kV Feeder B350 (Old Tsimalakha)				2		3	1	
8	11kV Feeder B360 (New Tsimalakha)				2		3	1	
9	11kV Feeder B80 (Rangaytrung)						2	1	
10	33kV Feeder B160 & C30 (Gurungdangra-II)	2			5		14		1
	Overall Total	5	3	0	16	0	38	9	2




Figure 23: Overall Switching Equipment for Distribution Network of Gedu SS

66/33/11kV PHUENTSHOLING SUBSTATION




Figure 24: Proposed Switching Equipment for Distribution Network of Phuentsholing SS




Figure 25: Proposed Switching Equipment for Distribution Network of Chhukha Switch Yard and Singyegoan GIS SS.

8.4.2 Distribution System Smart Grid

The distribution grid modernization is outlined in Smart Grid Road Map 2019 including the investment (2020-2027). The DMS, ADMS, DSCADA features along with their components and functionalities, the timeline for the programs and the cost estimates of the smart grid are lucidly reflected. Therefore, this report exclusively entails the identification of the system deficiencies and qualitative remedial measures which would require system augmentation and reinforcement as per the existing and projected load.

9. Investment Plan

In accordance to the above mentioned contingency plans targeted to improve the power quality, reduce losses and improve reliability indices of the Dzongkhag, investment proposal is developed. The investment plan has been confined to power supply sources, MV lines, DTs, switching and control equipment and RoW. The proposed/approved (2020-2024) investment plan and any new investment plans have been validated and synced with the system studies carried out. The annual investment plan (2020-2030) has been worked out based on the priority parameters set out as shown in **Figure 26**.

The matrix gives us the basis on the prioritization of the investments to be made in the ten-year schedule as every activity cannot be carried out at a time. The activities which have to be carried out due to load growth, developmental activities and retrofitting of obsolete/defective switchgears and equipment will have the highest level of importance and urgency. These activities have to be prioritized and invested in the initial years which are grouped in the first quadrant (Do First).

How important is the task?	Highly Important	Action: Do First I	Action: Do Next II
	Important	Action: Do Later III	No Action: Don't Do IV
	How urgent is the task?		
	<i>Figure 26: Priority Matrix</i>		

Similarly, there are certain activities although might be very important but not so urgent can be planned in the later stage of the year (Do Next). These activities can be but not limited to

improving the reliability, reducing losses and reconfiguration of lines and substations to reduce the losses and improving the power quality. The activities which are not so important but are highly urgent have to be also planned in later stage of the period.

According to the investment prioritization matrix framework, the yearly investment plan along with the cost estimation is derived and is consolidated in **Table 19** as an investment plan. The cost estimates have been worked out based on the BPC ESR-2015 and annual inflation is cumulatively applied to arrive the actual investment cost for the following years.

In the span of next 10 years (2020-2030), the total projected investment required to adequately deliver the power to the customers of Chukha Dzongkhag is Nu. 189.45 million (Nu. 18.95 million per year).

Table 19: Investment Plan (2020-2030)

Sl. No	Activities	Investment Plan (Nu. In Million)						Total				
		2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030
1	Construction of composite 11kV, 3cx95sqmm HV ABC (2.5 km) line from Gurungdara s/s to BBPL feeder.							3.58				3.58
2	Realignment of 33 KV overhead double circuit feeder from P/lng 66 KV substation to 33/11 KV Sector 2 Substation (RCO Building) (Laying of 33kV, 3cx150sqmm XLPE (0.750km) and paying of overhead AAC-100sqmm (.15km) over Dotikhola river).											2.57
3	Extension of power supply and construction of substation to new proposed site of Land User Right Certificate (LURC) under Chukha Dzongkhag							2.24		2.24		8.96
4	Extension of 11kV, 3cx150sqmm XLPE (0.3km) UG cable and construction of 11/0.415kV, 1MVA USS substation at Integrated checkpost, Rinchending											4.36
5	Extension of 11 kV, 3cx95sqmm HV ABC (1.2km) from CHPC colony to Bangay alternatives to construction Separate feeder											2.77
6	Extension of 11kV, 3cx50sqmm (0.120km) &							1.28				1.28

Distribution System Master Plan (2020-2030) | 2019

Sl. No	Activities	Investment Plan (Nu. In Million)					
		2020	2021	2022	2023	2024	2025
	construction of 11/0.415kV, 125kVA substation at Tinkilo, Batomuni						
7	Extension of 11kV, 3cx150sqmm XLPE (0.3km) UG cable, Installation of 1MVA Packaged Substation and Upgradation of LT UG line from 4cx70sqmm to 4cx150sqmm (1.5km) in Phuntsholing core town.			5.25			5.25
8	Extension of 4cx95sqmm (0.7 km) LV ABC line at near Gedu Zero.		0.47				0.47
9	Installation of Shield wire (5km) on 33kV Gurungdara Feeder II (Gedu-Lhamoizingkha)		0.71				0.71
10	Upgradation of 33KV panels & breakers for Sector II & Gurungdangra substation		8.13				8.13
11	RE-Fill in works	2	10.7	2	2	2	2
12	Conversion of ACSR-Squirrel/ Rabbit conductor (2km) to 4c x 95 sq.mm LV ABC at old Dzong site, Chukha Colony.		0.79				0.79
13	Conversion of overhead ACSR conductor to 3cx240sqmm XLPE UG Cable (Damdara Karbray, Amochu, Toorsatar, Town & Kharayphu LAP-2.5km, Pasakha, Ahalay, Pekarzhing & Rinchending LAP-3.5km) under Thromde LAP for aesthetic view of town.		2.71	2.71	2.71	2.71	10.84

Sl. No	Activities	Investment Plan (Nu. In Million)									
		2020	2021	2022	2023	2024	2025	2026	2027	2028	Total
14	Conversion of ACSR-Squirrel/Rabbit conductor (1.5km) to 4c x 50 sq.mm LV ABC at Junior School, Tsiamalakha.				0.69						0.69
15	Up-rating of 125kVA Rangaytrung substation to 500kVA Pad mounted substation				1.11						1.11
16	Up-grading of 63kVA Pasakha Bmobile substation to 125kVA pole mounted substation			0.43							0.43
17	Construction of 4cx400sqmm UG Cable LT ring system between Packaged Substation in Phuentsholing City Core Area (Direct Burial Method) (2km) for load sharing.				1.89	1.89					3.78
18	Extension of 11kV, 3cx240sqmm XLPE (0.92km) and construction of 2x750kVA USS and 500kVA Pad substation at Ahaly LAP.			2.68			2.68			2.68	8.04
19	Extension of 11kV, 3cx240sqmm XLPE (0.45km) UG cable and construction of 750kVA USS and 500KVA Pad substation at Rinchending LAP.				1.53			1.53		1.53	4.59
20	Extension of 11kV, 3cx240sqmm XLPE (0.40km) UG Cable and construction of 750kVA USS, 500kVA Pad substation and 125kVA pol mounted substation at Amochu LAP.					1.66			1.66		4.98
21	Conversion of HV ABC 3cx95sqmm cable (1.5km) line within the Tsimasham town area for better						2				2

Sl. No	Activities	Investment Plan (Nu. In Million)				
		2020	2021	2022	2023	2024
	safety and lesser ROW requirement.					2029
22	Re-sizing of 11kV, ACSR-Dog to Wolf conductor (6.3km) in Druk cement feeder and re-sizing of 3cx95sqmm HV ABC to 3cx120sqmm HV ABC (1.5km) between Goenpa and Pemaling as back up supply from 400kV Malbase substation to whole Phuentsholing town.				2028	6.36
23	Extension of 11kV, 3cx150sqmm XLPE (0.3km) UG cable, extension of 3cx95sqmm HV ABC cable (0.29km) and construction of 2x500kVA Pad substation and 125kVA pole mounted substation at Damdara & Karbraytar LAP.			2.12	2.12	2.12
24	Up-grading of 63kVA Malbase village substation to 125kVA pole mounted substation			2.01		2.01
25	Extension of 11kV, 3cx240sqmm XLPE (1.2km) UG cable and construction of 2x750kVA USS and 2x500kVA Pad substation at Pekarzhing LAP.			3.2	3.2	3.2
26	Extension of 11kV, 3cx50sqmm HV ABC Cable (0.35km) and construction of 125kVA pole mounted substation at Chamkuna LAP.		2.41			0
27	Up-grading of 63kVA Balsa substation to 125kVA pole mounted substation				0.45	0.45
28	Construction of 33kV line ACSR Dog conductor				1.67	1.67
						5.01

Sl. No	Activities	Investment Plan (Nu. In Million)											
		2020	2021	2022	2023	2024	2025	2026	2027	2028	Total		
	(7km) from Gamana (Point of 6/6/33kV substation by Wangchu project) to connect to the existing 33kV line feeding towards Lhamoizingkha.												
29	Extension of 11kV, 3cx240sqmm XLPE (0.63km) UG Cable and construction of 2x750kVA USS and 1000kVA USS at Pasakha LAP.												
30	Extension of 11kV, 3cx240sqmm XLPE (0.26km) UG Cable and construction of 2x750kVA USS at Toorsatar LAP.												
31	Extension of 11kV, 3cx240sqmm XLPE (0.55km) UG cable and construction of 2x750kVA USS at Kharayphu LAP.												
32	Re-alignment of Existing HT and LT networks, Uprating and installation of new substation for new township of Lhamoizingkha.												
33	Conversion of single to three-phase line	1.36	1.36	1.36	1.36	1.36	1.36	1.36	1.36	1.36	12.24		
34	Replacement of single phase by three phase transformers	1.83	1.83	1.83	1.83	1.83	1.83	1.83	1.83	1.83	16.47		
Total		20.47	20.01	5.98	12.37	12.95	16.37	21.12	19.48	22.43	15.02	23.25	189.45

10. Conclusion

Based on the inputs from Divisional office, validated data, assessment of the existing distribution network, and the reliability analysis, recommendations are made for system modifications and improvements. Costs associated with each recommendation are presented in several phases so that work may continue at a pace that is determined by fund availability and the capacity of the office to execute the work. An attempt is made to prioritize the recommendations; however, there will undoubtedly be adjustments in the order and priority by which the investments will be actually implemented.

The third option which would be the least-cost alternatives for converting the single to three-phase distribution network where all the MV lines will have to be converted to three-phase and replacing the single phase to three-phase transformers on need basis.

Although the report entails the identification of system deficiencies and reinforcement required, for automation and smart operation of the distribution network, the smart grid infrastructure development with functionalities are detailed in “Smart Grid Master Plan 2019”. Therefore, the DSMP-Smart Grid Master Plan-Hybrid is necessary which can be amalgamated during the rolling out of annual investment and budget approvals.

Proportion of LV is higher in comparison to MV line length; accordingly, the independent study carried out by BPC in 2017 showed that large portion of loss is due to LV and DT. Therefore, similar system study beyond DT has to be carried out in order to capture the entire network and strategize to develop the blue print.

11. Recommendations

Sl. No.	Parameters	Recommendations
A. Power Supply Sources		
1	HV Substations	As detailed in Sections 7 & 8 of this report, there is no up-grading or requirement of new HV substations required under Chukha Dzongkhag.
2	MV Substations	As detailed in Sections 7 & 8 of this report, there is no up-grading or requirement of new MV substations required under Chukha Dzongkhag.
B. MV and LV Lines		
1	MV & LV lines	As detailed in Sections 7 & 8 of this report, realignment, re-sizing of the conductors, construction of new MV & LV lines for LAPs and conversion of overhead to UG system are proposed.
2	ACSR to ABC (LV)	In order to minimize the safety of the inhabitants and to address the RoW issues, it is proposed to convert LV ACSR to LV ABC in and around the town.
C. Distribution Transformers		
1	Distribution Transformer	<p>As reflected in Section 7.3.1 of this report, it is proposed to regularly monitor the loading pattern especially of the urban transformers. It is desired to load the transformers less than 85% so as to ensure that transformer is operated at maximum efficiency.</p> <p>As the system study is restricted to DTs, the loads need to be uniformly distributed amongst the LV feeders to balance the load.</p>
2	Single to Three Phase Transformers	As reported in the “Technical and Financial Proposal on Converting Single Phase Power Supply to Three Phase in Rural Areas”, it is recommended to replace the single to three phase transformers on need basis.
D. Switching and Control Equipment		
1	Switching and Control Equipment	<p>It is recommended to install Intelligent Switching Devices (ISD) like ARCBs, Sectionalizers and FPIs as proposed which would reduce the downtime for clearing faults.</p> <ol style="list-style-type: none"> 1) Install FPI, Sectionalizes and ARCBs at various identified locations. 2) Installation of 11kV& 33kV RMUs at various identified locations.
E. others		
1	Investment Plan	As reflected in Section 9 of this report, overall investment plan as proposed is recommended.
2	Review of the	Practically the projections will hold only true in the nearest future therefor, it is

Sl. No.	Parameters	Recommendations
	DSMP	strongly recommended to review the DSMP in 2025 (after five years) or if need be as and when situation demands.
3	System Studies beyond DT	It is observed that distribution of electricity is more through LV than MV & HV and the scope of DSMP terminates at DT. However, it is equally important to carry out similar system studies for LV networks till meter point. Due to time constraint and non-availability of required LV data, it is recommended to carry out the studies on LV network including the DTs. Nevertheless, with the entire distribution network captured in the GIS and ISU, the system studies should be carried out including the LV network in the future.
4	Customer Mapping	One of the important parameters required especially for reaffirming the capability of the DTs is by examining customer growth patterns. Therefore, it is recommended to consistently update the customers via customer mapping process carried out annually.
5	Right of Way	RoW should be maintained as per the DDCS 2016. However, increased frequency of RoW clearing in the problematic sections of the line and in fast growth sub-tropical forest is recommended.
6	Asset life of DTs	The asset life of DTs need to be gathered to enable development of asset replacement framework. However, it is recommended to regularly monitor the health of the transformers which have already outlived their lives.
7	Overloading of DTs	As per the load forecast, some of the rural DTs might overload. While the probability of realizing such an event is quite low. It is, however, recommended that the DTs that have already exhausted its statutory life (25 years and above) be regularly monitored.
8	New extension through 33kV network	The power carrying capacity of 33kV system is almost 3-fold compared to that of 11kV system. Therefore, any new extension of lines may be done through 33kV system (based on fund availability and practical convenience).
9	Reliability	<p>In order to improve the reliability of the feeder/network, it is recommended that fault should be located within short period of time thereby reducing the restoration time and the number of customers affected. In this regard, the following initiatives are recommended:</p> <ol style="list-style-type: none"> 1) To install ISDs (communicable FPIs, Sectionalizers & ARCBs); 2) To explore with construction of feeders with customized 11kV & 33kV towers; and 3) To increase the frequency of Row clearing in a year.

Sl. No.	Parameters	Recommendations
10	Conversion Works	As the joint survey for laying the UG had not been done, the investment has been worked out based on assumptions of likely scenarios. Therefore, actual activities should be incorporated during the rolling out of the investment plans.
11	Lightning Protection	The top root cause of the power interruption is due to lightning and storm. Therefore, more focus should be placed on how to control and safeguard the equipment from lightning and storm (especially for the southern foothills).

12. Annexure

Annexure-1: MV Line Details and Single Line Diagram

Annexure-2: IS 2026, IEC 60076 (Technical parameters for Distribution Lines and Transformers)

Annexure-3: The details on load forecast methodology

Annexure-4: Detailed Simulation Results

Annexure 5: Feeder Wise Reliability Indices

Annexure-6: Material Cost for Upgrading single phase (11 kV and 33 kV) Lines to three-phase

Annexure 7: Distribution Transformer loading

Annexure-8: Material Cost of three phase (3Φ) Transformers

13. References

1. The FWPL and CPL from TD, BPC as of 2018.
2. BPC Power Data Book 2018.
3. BPC Distribution Design and Construction Standards (DDCS)-2016.
4. BPC Smart Grid Master Plan (2019-2027).
5. BPC National Transmission Grid Master Plan (2020 & 2030).
6. BPC Operation and Maintenance Manual for Distribution System (2012).
7. BPC Corporate Strategic Plan (2019-2030).
8. Population and Housing Census of Bhutan 2019.
9. The Structural Plan (2004-2027) for every Dzongkhag.
10. Industrial Parks (Department of Industry).
11. BPC Electrical Schedule of Rates 2015.

14. Assumptions

1. All the distribution network was considered as Balanced System (Restriction with the existing ETAP Key);
2. All DTs considered as lump load and depending upon the type of load connected to the feeder, ratio of 80% (static load) to 20% (industrial feeders) were assumed;
3. The voltage level of $\pm 10\%$ is given as critical value which is indicated by red color while simulating and voltage level of $\pm 5\%$ is given as marginal value which is indicated by pink color while simulating.
4. The typical inbuilt value of X/R ratio of ETAP tool was considered for all the transformers;
5. Dimensions and parameters of some cables/UG cables are customized in the library as per the requirement;
6. The technical parameters which are required for analysis of the distribution network have been considered as per the set standard of DDCS.

15. Challenges



Sl. No.	Parameters	Challenges	Opportunities/Proposals
1	Software Tool (ETAP)	<p>a) Only one key & offline Key</p> <p>a) Balanced Load Flow</p> <p>b) Limitations of No. of buses (1000)</p>	<p>a) Can opt for on line key with fewer more modules specially to carry out the technical evaluation of unbalanced load flow system. This would be more applicable and accrue good result for LV networks.</p>
2	Data	<p>a) No recorded data (reliability & energy) on the out-going feeders of MV SS</p> <p>b) Peak Load data of DTs which were recorded</p>	<p>a) Feeder Meters could be install for outgoing feeders of MV substations to record actual data (reliability & energy)</p> <p>b) In order to get the accurate Transformer Load Management</p>

Sl. No.	Parameters	Challenges	Opportunities/Proposals
		manually may be inaccurate due to timing and number of DTs.	(TLM)/loading, it is proposed to install DT meters which could also have additional features to capture other required information.
		c) No proper feeder and DT wise Customer Mapping recorded	c) Customer Information System (CIS) of the feeder/DT would enable to have proper TLM and replacement framework.
3	Manpower	a) Resource gap in terms of trained (ETAP) and adequate engineers (numbers)	a) Due to lesser number of trained engineers in the relevant fields (software), engineers from other areas were involved.


12. Annexures


Annexure-1: MV Line Details and Single Line Diagram


DISTRIBUTION NETWORK - ESSD, TSIMAKHA





2 OF 2











33/11 kV Gurungdara Substation





Legends:


	33 kV Line (OH)
	33 & 11 kV U/G cable
	11 kV Line (OH)
	LBS/Line GO (33 & 11 kV)
	ARCB (33 & 11 kV)
	BFC Transformers
	Private Transformers

3 OF 3









3 OF 3

MV line details of Chuukha Dzongkhag

S#	Asset Code	Feeder Name	Line Description	Source Substation like TD or 33kV substation		Sh	Line(Section 1) details						Remarks	
				Voltage level(kV)	U/G Overhead or Mixed		Line	Asset Code	Asset description on	Cable/Conductor sizes/mm ²	First GPS code	Final GPS code	Line length (KM)	
1	B180-Shemangkha	33kV, ACSR-Wolf Overhead line	66/33kV, Wasa substation	33	Overhead	Trunk Line	No	B180H75	B180H75	3.74	Wasa's/s	Upper Shemangkha's/s	1996-97	
1	Not applicable	B180-Shemangkha	33kV, ACSR-Wolf Overhead line	66/33kV, Wasa substation	33	Overhead	Spur line	No	B180H36	B180H36	0.07	Gangthik's/s	Gangthik's/s	1996-97
2	1600349.00	B180-Guroena	33kV, ACSR-Wolf Overhead line	66/33kV, Wasa substation	33	Overhead	Spur line	No	B180H44	B180H49	0.26	Gangthik's/s	Lower Gangthik's/s	1996-97
3	1600100.00	B180-Wasa-Jomshi	33kV, ACSR-Rabbit Overhead line	66/33kV, Wasa substation	33	Overhead	Trunk Line	1600349	1600H68	B180H161	4.02	Wasa's/s	Lower Shemangkha	2011
4	Not applicable	B190-Chaplin	33kV, ACSR-Wolf Overhead line	66/33kV, Wasa substation	33	Overhead	Trunk Line	1600100	1600H76	B180H172	4.08	Wasa's/s	Jomshi's/s	2007
5	1600925	B190-Juba-Jemo	33kV, ACSR-Dog Overhead line	66/33kV, Wasa substation	33	Overhead	Spur line	No	B190H111	B190H136	5.73	Wasa's/s	Chuphin GRrif's/s	2005
6	1600542.00	B190-L-haba-Lomzhi Menda	33kV, ACSR-Rabbit Overhead line	66/33kV, Wasa substation	33	Overhead	Spur line	1600925	1600H95	B190H155	0.45	Wasa's/s	Doklae Grempa's/s	1997-98
7	17040.00	Gate Chamber, Chuukha	11kV, ACSR-Rabbit and Dog Overhead	Chukha Switchyard	11	Overhead	Trunk	17040	17040	B190H156	1.08	Lhaha	Lomzhi Menda	2014
8	17041.00	B200-Wangkha (GREF-TPHA Colony)	11kV, ACSR-Dog/Rabbit Overhead line	Chukha Switchyard	11	Mixed	Trunk line	100/50	B200H11	B200H33	1.72	Chukha Switchyard gantry	Chuphin GRrif's/s	2016
9	1700317.00	B240-CHPC Colony	11kV, ACSR-Dog/Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	1700317	1700317	B200H118	0.03	THPA T-off	THPA's/s	2016
10	1700587.00	B240-Tie-Line (CHPC Colony)	11kV, ACSR-Dog Overhead Tie-line	Chukha Switchyard	11	Overhead	Spur line	100	B200H20	B200H003	0.41	Wangkha GREF T-off	Wangkha colony	2011
11	1700312.00	B170-Tashiangshab-Jabchho	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Mixed	Spur line	50	B200H008	B200H17	2.23	Chukha Switchyard gantry	CHPC Lower terrace	2002
12	1700900.00	B170-Tashiangshab-Jabchho	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	1700587	1700587	B200H120	0.16	OLDDSD T-off (CHPC colony)	OLDDSD's/s (CHPC colony)	2011
13	Not applicable	B170-Tashigatsheh-Tokgom	11kV, ACSR-Dog Overhead line	Chukha Switchyard	11	Overhead	Spur line	50	B200H132	B200H132	1.235	Near Wangkha school	Near Wangkha school	2003
14	1700560.00	B170-Tie-Line (Tashigatsheh-Babcho)	11kV, ACSR-Rabbit Overhead Tie-line	Chukha Switchyard	11	Overhead	Tie-Line	1700650	1700650	B170H1	2.83	Chukha Switchyard gantry	Tashingatsheh T-off	2002
15	17000.00	B170-Tie-Line (Tashigatsheh-Babcho)	11kV, ACSR-Rabbit Overhead Tie-line	Chukha Switchyard	11	Overhead	Tie-Line	17090	17090	B170H11	0.17	Tasingatsheh T-off	Tasingatsheh T-off	2011
16	17089.00	B170-Lower Jabchho	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Spur line	17089	17089	B170H117	0.39	Toktogn T-off	Toktogn T-off	2011
17	1700114.00	B360-New Tsimalkha	11kV, ACSR-Dog Overhead line	Chukha Switchyard	11	Overhead	Tunk Line	100	B360H111	B360H93	6.37	Chukha Switchyard gantry	Chukha Switchyard T-off	2008
18	1700651.00	B360-New Tsimalkha	11kV, ACSR-Dog Overhead line	Chukha Switchyard	11	Overhead	Spur line	100	B360H74	B360H75	0.03	Tsimalkha Hospital T-off	Tsimalkha Hospital	2012
19	1700105.00	B350-Old Tsimalkha	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	700/103	700/103	B360H110	0.12	Tsimalkha village tapings	New Zone's/s	2003
20	1700100.00	B350-Tsimalkha -Tsimsham	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	50	B360H107	B360H107	0.25	Lower Tsimalkha	Lower Tsimalkha	2003
21	1700101.00	B350-Tsimsham- Lohnkha	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	1700101	1700101	B350H196	1.65	Tsimsham Police camp	Pole No.B350H108 (On the way to Bumagu)	2003
22	Not applicable	B350-Tsimsham- Lohnkha	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Trunk Line	No	B350H108	B350H140	3.68	Bumagu T-off	Bumagu T-off	2003
23	17008.00	B350-Tsimsham- Lohnkha	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Spur line	No	B350H140	B350H176	3.38	Bumagu T-off	Lohnkha's/s	2016
24	1700603.00	B350-Chilouney	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Trunk Line	170088	170088	B350H135	0.196	Bumagu T-off	Bumagu	Chilouney's/s
25	1700775.00	B350-Chilouney	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B350H140	B350H204	2.12	Bumagu	Budangar	Chilouney B2/s
26	Not applicable	B350-Sannadangra	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B350H149	B350H158	0.42	Sannadangra T-off	Sannadangra's/s	2011
27	B30-Toorsar	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B350H111	B350H186	0.58	Toorsar T-off	Toorsar's/s	2016	
28	B30-Sorchen	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B20H130	B20H138	1.32	Sorchen T-off	Sorchen's/s	2014	
29	B20-Kamji	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B20H167	B20H167	0.263	Chilouney B1 Upper	Chilouney B1 Upper	Chilouney B1 Upper's/s	
30	B20-Simolakha	11kV, ACSR-Rabbit Overhead line	66/33kV Phuentsholing substation	11	Overhead	Spur line	50	B350H63	B350H171	0.212	Chilouney B1 Lower T-off	Chilouney B1 Lower T-off	Chilouney B1 Lower's/s	
31	B30-Gelzing	11kV, ACSR-Rabbit Overhead line	Chukha Switchyard	11	Overhead	Spur line	50	B350H204	B350H204	7.36	Geling rooppa's/s	Geling rooppa's/s	2014	

MV line details of Chukha Dzongkhag															
Sl#	Asset Code	Federer Name	Line Description	Federer Details			S#	Line (Section 1) details				Termination point	Year of construction	Remarks	
				Voltage level(kV)	UG/Overhead or Mixed	Line		Asset Code	Cable/Conductor size(mm ²)	First GPS code	Final GPS code				
26	1700313.00	B350-Chukha Switchyard Old Tsimalakha Fdr.	11kV, 150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	I700313	150	B350H1	0.131	66kV s/s switchyard	Chukha Switchyard gauntry		
Not applicable	B350-Chukha Switchyard (New Tsimalakha Fdr)	11kV, 150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	Not applicable	150	B360H1	0.125	66kV s/s switchyard	Chukha Switchyard gauntry	2002		
Not applicable	B350-Chukha Switchyard (BVC Edt)	11kV, 150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	Not applicable	150	B370H1	0.135	66kV s/s switchyard	Chukha Switchyard gauntry			
27	1700314.00	B200-Chukha Switchyard (Hankuk Fdr)	11kV, 150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	I700314	150	B200H1	0.065	66kV s/s switchyard	Chukha Switchyard gauntry	2002	
28	1700315.00	B450-Chukha Switchyard (Dzousie Fdr)	11kV, 2x150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	I700315	2x150	B450H1	0.242	66kV s/s switchyard	Chukha Switchyard gauntry	2002	
29	1700316.00	B440-Chukha Switchyard (Colby Fdr)	11kV, 150sqmm XLPE UG cable line	Chukha Switchyard	11	UG	Trunk Line	I700316	150	B440H1	0.062	66kV s/s switchyard	Chukha Switchyard gauntry	2002	
30	1700751.00	B360-TIPA Tsimlakha (Above ESSD Office)	11kV, ACSR-Dog Overhead line	Chukha Switchyard	11	Overhead	Spur Line	I700751	100	B360H188	0.139	Old Tsimalakha s/s	TIPA s/s	2014	
31	1600097.00	B130-Pedelchu-Chumkha (A)	11kV, ACSR-Dog Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Trunk Line	I600097	100/50	B130H125	10.688	Gedu switchyard entry	Pedelchu T-off		
32	1700586.00	B130-Pedelchu-Chumkha (B)	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I600097	50	B130H125	0.175	Spur Line	Pedelchu T-off	2007	
33	170016.00	B130-Geddu new town	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I700116	50	B130H160	0.074	Chumkha T-off	Upper Chumkha s/s		
34	1700112.00	B130-Toekha & Ben	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I700112	100	B130H168	1.829	Chumkha T-off	Lower Chumkha s/s	2007	
35	1700365.00	B10-Mekongave	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Trunk Line	I700365	50	B130H168	1.92	Chumkha T-off	Chumkha T-off	1998	
36	Not applicable	B10-Geddu	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I700367	50	B130H168	4.65	Padelchu tap off	Bangtangap off	2011	
37	1700133.00	B10-Geddu	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I700133	50	B130H174	0.116	Gedu new town T-off	Gedu new town s/s	2008	
38	1700366.00	B10-BBPL (Till)	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Spur Line	I700366	50	B130H201	2.08	Spur Line	Tonkha s/s	2007	
39	1700367.00	RNR-BBPL (Lapsakha-RNR s/s)	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Trunk Line	I700367	100/50	B10H116	6.88	Gedu switchyard entry	Pakshikha T-off		
40	1700368.00	B10-Lamu	11kV, BBPL (RNR T-off)	66/33/11kV Gedu substation	11	Overhead	Trunk Line	I700368	100	B10H141	0.589	No	Gedu switchyard entry	Allexkha T-off	1999
41	1700753.00	Gedu College U/G Network	11kV, 3x300sqmm XLPE UG cable	66/33/11kV Gedu substation	11	UG	Trunk Line	I700753	240	GPS not done	3.975	Gedu switchyard entry	Lenuj T-off	2010	
42	17034.00	B320-Geddu-Mirchingebu	11kV, ACSR-Rabbit Overhead line	66/33/11kV Gedu substation	11	Overhead	Trunk Line	I7034	100	B200H111	5.4	Gedu switchyard entry	Mirching Add T-off	2014	
43	17035.00	Gungdama-Mirchingebu Adm	11kV, 3x300sqmm & ACSR-Dog Overhead line	66/33/11kV Gedu substation	11	Mixed	Trunk Line	I7035	300/100	B200H114	0.03	Gedu switchyard entry	Lhaphakha T-off	2016	
44	17036.00	Sinchkha-Arckha	11kV, 3x300sqmm & ACSR-Dog Overhead line	33/11kV Gurungdara substation	11	Mixed	Trunk Line	I7036	300/100	B200H115	4.83	33/11kV Gurungdara switchyard	Mirching Adm	2016	
45	Not applicable	Rinchense	11kV, 3x300sqmm XLPE UG	33/11kV Gurungdara substation	11	Overhead	Spur Line	I7037	300	B200H116	2.5	33/11kV Gurungdara switchyard	Upper Arckha s/s		
46	17037.00	Gungdama-Sung shaft	11kV, ACSR-Dog Overhead line	33/11kV Gurungdara substation	11	Overhead	Spur Line	I7037	100	B200H117	0.65	O&M office, THPA T-off	Rinchense	2016	
47	17038.00	Gungdama-Sung shaft	11kV, ACSR-Dog Overhead line	33/11kV Gurungdara substation	11	Overhead	Trunk Line	I7038	100	B200H118	1.67	Rinchense Water Tank T-off	Rinchense Water Tank	2016	
48	17039.00	Gungdama-Sung shaft	11kV, ACSR-Dog Overhead line	33/11kV Gurungdara substation	11	Overhead	Spur Line	I7039	100	B200H119	2.83	33/11kV Gurungdara switchyard	Port Head I s/s		
									100	B200H120	0.31	THPA Surge Shift (EL.145)-T-off	THPA Surge Shift (EL.145)-s/s		
									100	B200H121	0.59	Switch yard II (EL.125)-T-off	Switch yard II (EL.125)-s/s		
									100	B200H122	0.64	Port Head I T-off	Port Head I s/s		
									100	B200H123	2.42	33/11kV Gurungdara switchyard	Power House s/s	2016	
									100	B200H124	6.63	33/11kV Gurungdara switchyard	THP Tail Race Outfall II s/s		
									100	B200H125	0.34	Tai Race I	Tai Race I (EL.145)-T-off	2016	

Asset taken over from DGPC

Asset taken over from DGPC

Mv line details of Chittua Dzongkha														
Sl#	Asset Code	Feeder Name	Line Description	Source Substation like TD or 33kV substation		Feder Details		S#		Line (Section 1) details		Remarks		
				Voltage level(kV)	Mixed	Line	Asset Code	Cable / conductor mm ²	First GPS route	Final GPS code	Line length (KM)			
48	16036.00	B140-Gurungdara -J	33kV, AC/CSR-Dog Overhead Line	33kV, Gurungdara substation	11	Overhead	Spur Line	100	GPS not done	0.18	Draunge Galaxy THP Colony T-off	Drangue Galaxy THP Colony S.S		
49	16036.00	B140-Gurungdara -J	33kV, AC/CSR-Dog Overhead Line	33kV, Gurungdara substation	11	Overhead	Spur Line	100	GPS not done	0.24	THP Tuni Route Outfall T-off	THP Tuni Route Outfall T-off		
50	16039.00	B160-Gurungdara-II	33kV, AC/CSR-Dog Overhead Line	66/33/11kV Gedu substation	33	Overhead	Trunk Line	16038	100	B140H1	160H132	10.54	Gedu switchyard gantry	
51	1600092.00	B160-Beech Tala	33kV, AC/CSR-Dog Overhead Line	66/33/11kV Gedu substation	33	Overhead	Trunk Line	1600092	100	B160H100	B160H112	10.9	Gedu switchyard gantry	
52	1600099.00	B160-Gedu-Bakunza	33kV, AC/CSR-Dog Overhead Line	66/33/11kV Gedu substation	33	Overhead	Trunk Line	1600099	100	B160H142	B160H595	20.01	Gurungdara switchyard	
53	1600099.00	B160-Gedu-Bakunza	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600099	50	B160H161	B160H396	1.17	Talayek T-off	
54	1600093.00	B160-Marchim-Bouso	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600093	50	B160H193	B160H657	1.15	Ganau T-off	
55	1600526.00	B160-Penithang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600526	50	B160H220	B160H384	1.25	Lower Yacon T-off	
56	1600537.00	B160-Gelukha	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600537	50	B160H252	B160H668	2.01	Rullang T-off	
57	1600554.00	B160-Getena	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600554	50	B160H411	B160H437	1.11	Sileky T-off	
58	Not applicable	B160-Phasuma	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	Not applicable	No	50	B160H445	B160H53	0.35	Stichukha T-off
59	1600010.00	B160-Pening	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600010	150	B160H187	B160H884	2.878	Pakshina s.s	
60	1600356.00	C301-Armancan	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600356	50	B160H222	B160H346	9.667	Gunungdara	
61	1600367.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1600367	50	B160H526	B160H639	4.07	Marishim	
62	16175.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	16175	50	B160H147	B160H479	1.23	Ganana T-off	
63	16176.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	16176	50	B160H193	B160H543	0.32	Kezan T-off	
64	16181.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	16181	50	B160H250	B160H561	0.31	Domaniey T-off	
65	16182.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	16182	50	B160H251	B160H562	0.31	Zomisa s.s	
66	16047.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	16047	50	B160H252	B160H563	0.31	Under ESSD, Gedu	
67	1700117.00	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	1700117	50	B160H266	B160H565	0.399	LZhingka BPC colony	
68	Not available	C301-Kamling-Odahhang	33kV, AC/CSR-Rabbit Overhead Line	66/33/11kV Gedu substation	33	Overhead	Spur Line	Not available	No	100	C301H260	C301H656	0.399	Under R&B Distribution services

<< Not available >>

My line details of Chukha Dzongkhag

Sl#	Asset Code	Feeder Name	Line Description	Feeder Details		Line (Section 1) details				Termination point	Year of construction	Remarks		
				Voltage level(kV)	U/G/Overhead or Mixed	Line	Asset Code	Cable / conductor sizes/mm ²	First GPS code	Final GPS code	Line length (KM)	Location		
68	C30-Lhamo/zinkhu Town	33kV, AC/CSR/Rabbit Overhead line	Source Substation like TD or 33/11kV substation	66/33/11kV Gedu substation	33	Overhead	Spur Line	No	C30H1229	C30H1247	1.198	BHU T-off	Majeyan/s/s	
69	Not applicable C30-Lhamo/zinkhu Trunk line	33kV, AC/CSR/Wolf Overhead line	66/33/11kV Gedu substation	66/33/11kV Gedu substation	33	Overhead	Trunk line	No	B160H171	C30H1267	20.216	Pening T-off	DG Maniar T-off	
70	1600509.00	B160-Pakchima-Dumena	33kV, AC/CSR/Rabbit Overhead line	66/33/11kV Gedu substation	33	Overhead	Spur Line	No	B160H1085	B160H1149	8.598	Maniar T-off	House/hamozamka Lower Dumena/s/s	
70	B160-Pakchima-Dumena	33kV, AC/CSR/Rabbit Overhead line	66/33/11kV Gedu substation	66/33/11kV Gedu substation	33	Overhead	Spur Line	No	B160H1107	B160H1110	0.173	Yeshidukha T-off	Yeshidukha T-off	
71	1700124.00	B80-Sungye	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Trunk line	1600509	B160H126	B160H1129	0.621	Pakchima Lower T-off	Pakchima Lower T-off	
72	1700125.00	B80-Rangaytung	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Trunk line	1700124	B80H146	B80H146	1.374	Singhagon Ganty	Singhagon Ganty	
73	1700126.00	B80-Rangaytung Drashang	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700125	B80H170	B80H170	2.24	Singye Village s/s	Rangaytung Village s/s	
74	B80-Teeling	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700126	B80H69	B80H181	1.5	Rangaytung	Rangaytung s/s		
74	1700757.00	B30-Ardangra	66/33/11kV Phuentsholing	66/33/11kV Phuentsholing	11	Overhead	Spur Line	1700757	B80H77	B80H193	0.796	Teeling T-off	Teeling s/s	
75	1700602.00	B80-Pana-Kortline	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700602	B30H171	B30H192	1.152	Chikoney B1 Lower T-off	Chikoney B1 Lower T-off	
75	B80-Pana-Kortline	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700602	B80H70	B80H188	3.853	Rangaytung Village s/s	Rangaytung Village s/s		
75	B80-Pana-Kortline	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700602	B80H154	B80H162	0.822	Pana A Upper T-off	Pana A Upper T-off		
75	B80-Pana-Kortline	11kV, AC/CSR/Rabbit Overhead line	220/66/11kV Singhagon	11	Overhead	Spur Line	1700602	B80H175	B80H176	0.052	Pana B Lower T-off	Pana B Lower T-off		
76	17111.00	B70-V-Singhagon-Mahuse Tie line	11kV, AC/CSR/Dog Overhead line	220/66/11kV Singhagon	11	Overhead	Trunk line	17111	B70H11	B70H117	1.7	Singhagon Ganty	Singhagon Ganty	
77	1700113.00	B390-Pasikha Industrial Estate Lower & Upper	11kV, AC/CSR/Wolf Overhead line	220/66/11kV Singhagon	11	Overhead	Trunk line (Lower)	1700113	B390H11	B390H191	4.34	Singhagon Ganty	Korlinge s/s	
78	1700120.00	B390-Pasikha Industrial Estate Lower & Upper	11kV, AC/CSR/Wolf Overhead line	220/66/11kV Singhagon	11	Overhead	Trunk line (Upper)	1700120	B390H11	B390H191	3.68	Singhagon Ganty	Dargang s/s	
78	1700120.00	B390-Pasikha Industrial Estate Lower & Upper	11kV, DC/ACSR-XLPE	220/66/11kV Singhagon	11	U/G	Trunk line	1700120	B390H30	B390H31	0.15	Above Road, Singhi Store	Mahbase Ganty	
79	1700115.00	B400-DC Druk Cement/ Bhutan Steel	11kV, DC/ACSR-Wolf Overhead line	400/22/66/11, Mahbase substation	11	Overhead	Trunk line	1700115	B40H111	B40H132	2.216	Mahbase gantry	Below Road, Singhi Store	
80	1700119.00	B400-DC Druk Cement/ Bhutan Steel	11kV, AC/CSR-Dog Overhead line	400/22/66/11, Mahbase substation	11	Overhead	Trunk line	1700119	B40H75	B40H1128	0.42	Alay Khogla T-off	Alay Khogla T-off	
81	1700118.00	B370-Initika-Satillo (Water Oxhead)	11kV, HV ABC Overhead line	66/33/11kV Phuentsholing Substation	11	Overhead	Trunk Line	1700118	B270H17	B270H178	1.09	Above Penaling (Tin Kilo T-off)	Above Penaling (Tin Kilo T-off)	
82	17042.00	B30-Gangjaka	11kV, AC/CSR/Rabbit Overhead line	66/33/11kV Phuentsholing Substation	11	Overhead	Trunk Line	17042	B20H167	B20H200	4.046	Sakliko (Water Gangjaka)s/s	Sakliko (Water Gangjaka)s/s	
83	Not applicable B30-Hauey	11kV, AC/CSR/Rabbit Overhead line	66/33/11kV Phuentsholing Substation	66/33/11kV Phuentsholing Substation	11	Overhead	Spur Line	No applicable	No	L160H82	L160H168	2.837	Haurey T-off	Hauey s/s
84	1700649.00	B30-Kopshay	11kV, AC/CSR/Rabbit Overhead line	66/33/11kV Phuentsholing Substation	11	Mixed	Trunk Line	1700649	L160H71	L160H149	0.44	Kopchey T-off	Kopchey s/s	
85	1700659.00	B30-Tirring	11kV, AC/CSR/Rabbit Overhead line	66/33/11kV Phuentsholing Substation	11	Overhead	Spur Line	1700649	L160H57	L160H143	3.313	Triuring T-off	Triuring T-off	
86	1600338.00	B36-Ganty to above Sonmang school	33kV, 3x30.95kpm XLPE Underground	66/33/11kV Phuentsholing Substation	33	U/G	Trunk Line	1600338	B260H1	B260H3	0.33	Near Sonmang school gate	Above Sonmang school	
87	1600098.00	B36-Serma-Bosokha	33kV, AC/CSR/Dog Overhead	66/33/11kV Phuentsholing Substation	33	Overhead	Trunk line	1600098	B260H13	B260H90	8.979	Above Sonmang school	Bosokha/s/s	
87	B36-Serma-Bosokha	33kV, AC/CSR/Dog Overhead	66/33/11kV Phuentsholing Substation	66/33/11kV Phuentsholing Substation	33	Overhead	Spur Line	1600098	B260H70	B260H74	0.669	Top Serma T-Off	Top Serma s/s	
88	1600436.00	B36-Serma-Bosokha	33kV, AC/CSR/Dog Overhead	66/33/11kV Phuentsholing Substation	33	Overhead	Spur Line	1600098	B260H80	B260H81	0.05	Upper Serma T-off	Upper Serma s/s	
88	B36-Serma-Bosokha	33kV, AC/CSR/Rabbit & Dog Overhead	66/33/11kV Phuentsholing Substation	66/33/11kV Phuentsholing Substation	33	Overhead	Trunk line	1600436	B260H90	B260H705	1.1922	Bosokha/s/s	Upper Lalidha/s/s	
88	B36-Serma-Bosokha	33kV, AC/CSR/Dog Overhead	66/33/11kV Phuentsholing Substation	66/33/11kV Phuentsholing Substation	33	Overhead	Spur Line	1600436	B260H67	B260H1612	0.684	Lower Tashidingha T-off	Lower tashidingha/s/s	
88	B36-Serma-Bosokha	33kV, AC/CSR/Rabbit Overhead	66/33/11kV Phuentsholing Substation	66/33/11kV Phuentsholing Substation	33	Overhead	Spur Line	1600436	B260H695	B260H698	0.568	Lower Lalidha T-off	Lower Lalidha/s/s	

Sl#	Asset Code	Feeder Name	Line Description	Source Substation like TD or 33kV substation		Feder Details	Sl#	MV line details of Chittua Dzongkha						Remarks	
				Voltage level(kV)	Line			Asset Code	Cable / conductor size(mm ²)	First GPS route	Final GPS code	Line length (KM)	Location	Termination point	
	B260-Lingden, Lalkha & Chumna	33kV, ACSR-Rabbit & Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100/50	B260H714	5.704	Chimna T-off	Dorlakha s/s		
	B260-Lingden, Lalkha & Chumna	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100	B260H591	B260H592	0.172	Chimna Lower T-off	Chimna Upper s/s	
	B260-Lingden, Lalkha & Chumna	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H597	B260H600	0.35	Chimna Upper T-off	Chimna Upper s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit & Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line			100/50	B260H54	B260H149	6.712	Sadhamudi Top	Panji A s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H112	B260H118	0.77	Iedolka T-off	Iedolka C s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H140	B260H168	2.738	Chomchey T-off	Chomchey Top s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H148	B260H151	0.21	Panji B T-off	Panji B s/s	
89	1600435.00	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk line	1600435		100/50	B260H137	B260H189	2.033	Amalay	Dopham D Top s/s	2013
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H178	B260H183	0.69	Dopham	Dagechen s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H184	B260H185	0.146	Dopham B T-off	Dopham B s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line			100	B260H175	B260H227	4.521	Dopham	Dolpshen B/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H194	B260H196	0.334	Dubeni A T-off	Dubeni A s/s	
	B260-Lokhina-Dolephen	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H194	B260H198	0.237	Dubeni C T-off	Dubeni C s/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line			100	B260H227	B260H297	7.998	Dopham	Chungyikha school s/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100	B260H1267	B260H272	0.524	Dopham	Dophalakha Upper s/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100	B260H1295	B260H307	0.59	Chungyikha Upper s/s	Chungyikha Lower	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1267	B260H336	4.487	Dophulakha Lower	Resi s/s	
90	1600434.00	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line	1600434		50	B260H131	B260H335	1.786	Kungkha	Sinoley s/s	2013
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line			100/50	B260H1247	B260H398	4.798	Bjabchu	Damehkhun B/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1378	B260H581	0.483	Chadohka A T-off	Chadohka A s/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1395	B260H401	0.484	Damehkhun C T-off	Damehkhun C s/s	
	B260-Bjachu-Danchehkhun & Kunderha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100/50	B260H1387	B260H510	12.932	Farmgoan T-off	Mongokha B/s	
	B260-Dungna-Metakha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100	B260H1415	B260H417	0.195	Yuje T-off	Yuje s/s	
	B260-Dungna-Metakha	33kV, ACSR-Dog Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			100	B260H1433	B260H435	0.395	Rudingka Lower T-off	Rudingka Lower s/s	
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1473	B260H475	0.182	Pangu B T-off	Pangu B/s	
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Trunk Line	1600484		50	B260H1455	B260H545	6.448	Dungna	Meab Pang B/s	2014
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1464	B260H465	0.103	Ngalaslong T-off	Ngalaslong s/s	
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1523	B260H524	0.231	Meangopa A T-off	Metangopa A s/s	
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1525	B260H557	1.88	Menyal	Gumena s/s	
	B260-Dungna-Metakha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1526	B260H527	0.139	Meangopa B T-off	Metangopa B/s	
	B260-Omechu-Tshundugang-Dip	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H1297	B260H819	10.018	Chungyikha	Tshundugang s/s	
	B260-Omechu-Tshundugang-Dip	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H760	B260H769	1.185	Pasenka	Sedenka s/s	
	B260-Bjobjikha	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H527	B260H837	3.095	Metangopa B	Bjobjikha s/s	2014
	B260-Japin-Lassap/Neridhu-Lerima	33kV, ACSR-Rabbit Overhead	66/33/1 kV Phensholing Substation	33	Overhead	Spur Line			50	B260H715	B260H743	4.324	Dopham	Lhasap/Neridhu	
	B260-Japin-Lassap/Neridhu-Lerima	33kV, 3ex300sqmm XLPE	66/33/1 kV Phensholing Substation	33	UG	Trunk Line	1600102		150	B260H598	B260H714	1.7	Chimna	Dolakha s/s	
	93	1600102.00	Section I(K) RCO Building Office	33kV, 3ex300sqmm XLPE	33kV, 3ex300sqmm XLPE	Trunk Line			150	B250H010A	B250H010A	0.2	66kV s/s control panel	Gantry	2007
		Section II(K) RCO Building Office	33kV, 3ex300sqmm XLPE	33kV, 3ex300sqmm XLPE	Trunk Line					B240H010A	Panned		66kV s/s control panel	Gantry	

My line details of Chithra Dongking

Sl#	Asset Code	Feeder Name	Line Description	Source Substation like TD or 33/11kV substation		Siphon		Line (Section 1) details				Remarks		
				Voltage level(kV)	U/G/Overhead or Mixed	Line	Asset Code	Asset description on	Cable / Conductor size/mm ²	First GPS code	Final GPS code	Line length (KM)		
94	1600103.00	Sector I&II (RCO Building Office)	33kV DC, ACSR-Dog Overhead	66.33/11kV Phenesholing Substation	33	Overhead	Trunk Line	1600103	300	B240H0A	B240H2	0.5	Gantry	
		Sector I&II (RCO Building Office)	33kV DC , ACSR-Dog Overhead	66.33/11kV Phenesholing Substation	33	Overhead	Trunk_line		300	B240H0A	B240H2	0.5	Gantry	
95	17246.00	B30-Amochha B, NHDCL Colony	11kV, AC/CSR-Rabbit Overhead line	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B30H125	B30H210	0.8	Crematorium s/s	
		B30-Amochha A, NHDCL Colony	11kV, AC/CSR-Rabbit Overhead line	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B30H119	B30H198	0.238	NHDCL Amochha A T-off	
96	17247.00	B30-NHDCL Colony, near Rubin Workshop	11kV, 3cx9sqmm XLPE	66.33/11kV Phenesholing Substation	11	UG	Spur Line		150	B230H133	GPS not done	0.501	Helpad RMU	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		95	B400H92	GPS not done	0.5	NHDCL Colony Torbari T-off	
97	17248.00	B400-NHDCL Colony, Torbari	11kV, 3cx9sqmm HV ABC	400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		100	B400H145	B400H143	3.86	Torbari s/s	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		100	B400H145	B400H143	3.86	Torbari s/s	
98	1700105.00	B400-Tie Line between Torbari - Balupur (Bhimbote s/s)	11kV, AC/CSR-Dog Overhead	220/66/11, Singhagom substation	11	Overhead	Trunk Line		1700105				Balupur Mobile T-off	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		50	B50H19	B390H100	2.22	BCCL colony T-off	
99	1700106.00	B50-BCCCL Colony to New Industrial Estate (Kanewire Pasubhan)	11kV, AC/CSR-Rabbit Overhead	400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		1700106				Ratten Wrie T-off (Pasubhan)	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		100	B270H39	B400H145	2.44	Kharbandi Gocupas s/s	
100	1700108.00	B400-Kharbandi Gocupas-Torbari	11kV, AC/CSR-Dog Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		1700108				Torbari s/s	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		100	B400H108	B400H110	0.06	Kharbandi Checkpost T-off	
101	1700104.00	B30-Baludanga	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B30H77	B30H193	0.85	Baldangara T-off	
				66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B30H45	B30H154	1.16	Sathumudu T-off	
102	1700107.00	B30-Sadumadhu	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		1700107				Sadumudu s/s	
				66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line		50	B30H111	L160H22	2.07	Toorsarar Borboye T-off	
103	1700109.00	B30-Tading (T rerouting)	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		1700109				Toorsarar	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B30H110	B30H125	0.342	Crematorium T-off	
104	1700110.00	B30-Crematorium Fdr	11kV, AC/CSR-Rabbit Overhead	400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		1700110				Crematorium s/s	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		100	B400H64	B400H166	0.18	Ahaley T-off (Pasakha)	
105	1700111.00	B400-Ahaley	11kV, AC/CSR-Dog Overhead	400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		100	B460H111	B460H136	1.54	Mahbase gantry	
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B460H115	B460H117	1.1	Burkey T-off	
106	1700122.00	B280-H&K (Below Mini Dry Port)	11kV, AC/CSR-Rabbit Overhead	220/66/11, Singhagom substation	11	Overhead	Trunk_line			100	B80H11	B80H134	1.77	Singhigam Gantry
				220/66/11, Singhagom substation	11	Overhead	Trunk Line			100	B80H2	B80H181	0.43	Gurungdangra T-off
107	1700123.00	B280-Pekasy	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		1700111				Pekasy T-off	
				66.33/11kV Phenesholing Substation	11	Overhead	Spur Line		50	B20H68	B20H183	1.03	Ganguri Ahaley T-off	
108	1700127.00	B400-Torbari V-tar	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line			50	B20H71	B20H119	0.72	Modina T-off
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line			100	B40H196	B400H197	0.14	Reidhi Ahaley T-off
109	1700128.00	B30-Ganguri Lhakhang	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line			50	B280H112	B280H3	0.065	Reidhi Ahaley s/s
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line			100	B230H11	B230H133	1.708	66kV substation gantry
110	1700130.00	B270-Penaling-Kharbandi Goepa	11kV, 3cx9sqmm HV ABC	66.33/11kV Phenesholing Substation	11	Overhead	Spur Line			50	B20H127	B400H138	0.55	Torbari V-tar T-off
				400/220/66/11, Mabbase substation & 66.33/11kV Phenesholing Substation	11	Overhead	Spur Line			50	B20H117	B20H122	0.23	Ganguri Lhakhang T-off
111	1700132.00	B240-Mahbase colony	11kV, AC/CSR-Dog Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line			50	B270H17	B270H39	1.396	Penaling s/s
				66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line			100	B420H11	B420H3	0.537	Mahbase gantry
112	1700132.00	B20-Ramsey	11kV, AC/CSR-Rabbit Overhead	66.33/11kV Phenesholing Substation	11	Overhead	Trunk Line			50	B20H115	B20H15	0.808	66kV Ping Gantry
													Karbayir s/s	

Comments

Sl#	Asset Code	Feeder Name	Line Description	My line details of Chukha Dzongkhag							Remarks					
				Feeder Details		Site		Line								
				Voltage level(kV)	U/G/Overhead or Mixed	Asset Code	Cable / conductor size/mm ²	Asset description on	First GPS code	Final GPS code	Line length (KM)	Location	Termination point	Year of construction		
113	170353.00	B20-Ramtey	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700533	50	B20H15	B20H134	1.962	Karbyatay s/s	1989		
114	170354.00	B20-Ramtey	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700534	50	B20H134	B20H136	0.225	Lower Ramtey s/s	Upper Ramtey T-off	1990	
115	170355.00	B20-Ramtey	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700535	50	B20H136	B20H151	0.681	Ramtey	Bhutan Battery s/s	1991	
116	170356.00	B20-Ramtey	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Spur Line	1700535	50	B20H139	B20H144	0.325	Ramtey RBA T-off	Ramtey RBA T-off		
117	170357.00	B20-Ramtey	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700536	50	B20H151	B20H152	0.091	Bhutan Battery s/s	Ramtey pole no.B20H152	1996	
118	170358.00	B30-Dandara	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700537	50	B20H152	B20H171	0.86	Upper Ramtey T-off	Upper Ramtey T-off	1999	
119	170359.00	B30-Budangtar	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700539	50	B30H11	B30H11	0.31	66kV Ping Ganty	Dandara s/s	1983	
120	170360.00	B30-Darjeygan	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700540	50	B30H129	B30H141	0.98	Budangtar s/s	Darjeygan s/s	1991	
121	170361.00	B30-Pachu	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700541	50	B30H42	B30H79	2.46	Pachu T-off	Upper Pachu s/s	1995	
122	170362.00	L160-Tading	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	1700542	50	B30H77	L160H40	3.562	Pachu T-off	Jenchu s/s	1989	
123	170363.00	L160-Tading	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Spur Line	1700543	50	L160H30	L160H28	0.59	Borbotey T-off	Borbotey s/s	1996	
124	170369.00	B400-Druk Cement (B3P)	11kV, ACSR- Dog Overhead	400/220/66/11, Mabuse substation & 66/33/11kV Phenanthsholing Substation	11	Overhead	Trunk Line	1700369	100	B400H123	B400H139	0.524	Bhutan Steel T-off	Upper Tading Tadding s/s	1997	
125	170584.00	B30-Tading	11kV, 3x240.9mm XLPE U/G cable	66/33/11kV Phenanthsholing	11	UG	Trunk Line	1700584	240	B30H12	B30H3	0.25	66kV Ping Ganty	Above Sonamgang school	Due to Sonamgang school construction	2011
126	170585.00	L160-Lower Tading	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	11	Overhead	Spur Line	1700585	50	L160H74	L160H74	0.017	Lower Tading T-off	Lower Tading T-off	RL-fil work (Constructed s/s on line and capitalised the conductor length in the year 2011)	2011
127	Not applicable	B10-Polythene	11kV, 3x240.9mm XLPE U/G cable	66/33/11kV Phenanthsholing	11	UG	Trunk Line	No applicable	No	B10H1	B10H2	0.214	66kV Ping Ganty	PWD s/s	1988	
128	Not applicable	B10-Polythene	11kV, ACSR- Dog Overhead	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	No applicable	No	B10H2	B10H11	0.35	PWD s/s	Polythene s/s		
129	Not applicable	B280-Water Booster	11kV, 3x240.9mm XLPE U/G ABC	66/33/11kV Phenanthsholing	11	Overhead	Trunk Line	No applicable	No	B400H100	B400H130	1.023	Dringebu s/s	BPC Colony s/s	2006-7	
130	Not applicable	B280-Water Booster	11kV, 3x306.9mm XLPE U/G cable	33/11kV Sector & II Substation	11	UG	Trunk	No applicable	No	B280P31	B280P31	2.186	33/11kV Sector I&II breaker	Heipat RMU	2006-7	
131	16046	B260-Zekentha (Metdaha)	11kV, ACSR- Rabbit Overhead	66/33/11kV Phenanthsholing	33	Overhead	Spur Line	No applicable	No	B280P15	B280P32	0.28	Dringebu RMU	Dringebu RMU	2006-7	
132	B270-PWD-Pemaling	11kV, 3x306.9mm XLPE U/G cable	33/11kV Sector & II Substation	33/11kV Sector & II Substation	11	UG	Trunk Line	No applicable	No	B270P26	B270P26	0.675	PWD USS	Pemaling s/s	2006-7	
133	B270-PWD-Pemaling	11kV, 3x306.9mm XLPE U/G cable	33/11kV Sector & II Substation	66/33/11kV Phenanthsholing	33	Overhead	Spur Line	16046	50	B260H838	Zekentha T-off	0.041	Zekentha s/s	Zekentha s/s	2010-6	


Annexure-2: IS 2026, IEC 60076 (Technical parameters for Distribution Lines and Transformers)

Sl. No.	Parameter	Requirement
1	Applicable standard	IS 2026, IEC 60076
2	Type	Oil filled ¹ / two winding
3	Winding material	Copper
4	Core Material	CRGO silicon steel/Amorphous Metal
5	Cooling	Oil natural air natural (ONAN)
6	Terminations	
	· Primary	Outdoor Bushing or cable box ²
	· Secondary	Outdoor Bushing or Cable box
7	Rated no load voltage	
	· Primary	33 kV or 11 kV
	· Secondary	415/240 V
8	% Impedance	
	10 kVA-24 kVA (1phase/3phase)	3%
	25 kVA-630 kVA	4%
	631 kVA-1250 kVA	5%
9	Vector group	Dyn11
10	Tap changer	
	· Type	Off load
	· Range	+5% to -5%
	· Step value	2.50%
11	Insulation Class (IEC-76)	A
12	Permissible Temperature rise	
	· Maximum winding temperature	55°C
	· Max. Top oil temperature	50°C
13	Insulation levels	
	· Primary	170 kVp-70 kV/75 kVp-28 kV
	· Secondary	7500 Vp-3000 V


Annexure-3: Load Forecast adopting LRM & TSA


Load forecast for Chukha Dzongkhag

Sl. No.	Feeder Name	Peak Load Consumption Pattern (MW)						Forecasted Peak Load Consumption Pattern (MW)									
		2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030
ESD, Phuentsholing																	
1	11kV New Polythene	0.47	0.52	0.53	1.09	1.02	0.87	0.91	0.96	1.00	1.05	1.09	1.14	1.18	1.23	1.27	1.32
2	11kV Karbraytar & Rametey	0.86	0.84	0.85	0.89	0.90	1.04	1.06	1.07	1.09	1.11	1.13	1.14	1.16	1.18	1.20	1.22
3	11kV (Tading)	0.92	0.96	1.12	1.09	1.24	1.30	1.35	1.40	1.46	1.51	1.57	1.62	1.67	1.73	1.78	1.83
4	11kV/BPC Colony	1.86	1.45	1.47	2.22	2.08	2.16	2.24	2.32	2.40	2.48	2.56	2.64	2.72	2.80	2.88	2.96
5	11kV Hospital	0.14	0.18	0.12	0.15	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14
6	11kV Helpad	0.50	0.41	0.53	0.41	0.41	0.43	0.45	0.47	0.49	0.51	0.53	0.55	0.57	0.59	0.61	0.63
7	33kV Senina Bosokha	1.06	1.29	0.80	0.98	1.28	1.21	1.28	1.34	1.42	1.31	1.46	1.39	1.57	1.52	1.51	1.51
8	11kV Water Booster	2.66	3.20	3.03	3.96	3.58	3.71	3.83	3.96	4.09	4.22	4.35	4.47	4.60	4.73	4.86	4.98
9	11kV PWD	3.21	1.91	2.56	3.03	2.87	2.96	3.04	3.13	3.22	3.30	3.39	3.48	3.56	3.65	3.74	3.82
10	11kV Yarkay	0.17	0.17	0.12	0.16	0.17	0.18	0.18	0.19	0.19	0.20	0.21	0.21	0.22	0.23	0.23	0.24
11	11kV Station	0.01	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02	0.02
12	11kV Rangaytrung	0.45	0.40	0.50	0.29	0.28	0.46	0.46	0.47	0.47	0.48	0.48	0.48	0.49	0.49	0.50	0.50
13	11kV/Gurangdangra	0.18	0.03	0.02	0.09	0.09	0.11	0.12	0.12	0.12	0.13	0.13	0.13	0.14	0.14	0.14	0.14
14	11kV BCCL Colony	1.25	1.11	1.03	1.38	1.41	1.43	1.45	1.47	1.50	1.52	1.54	1.56	1.58	1.61	1.63	1.65
15	11kV Lower Industrial Estate	3.46	3.31	3.21	4.29	4.27	4.23	4.28	4.34	4.40	4.45	4.51	4.57	4.62	4.68	4.74	4.79
16	11kV Upper Industrial Estate	4.12	3.28	4.40	4.52	3.51	4.39	4.40	4.41	4.43	4.44	4.45	4.47	4.48	4.49	4.51	4.52
17	11kV Druk Cement	2.09	2.01	2.77	4.19	3.56	3.34	3.43	3.53	3.62	3.72	3.82	3.91	4.01	4.10	4.20	4.29
18	11kV Bhutan Steel	2.91	2.94	2.89	2.98	2.88	2.90	3.00	2.93	2.93	2.88	3.02	3.03	2.94	2.89	3.02	3.04
19	11kV/Malbase Colony	0.92	0.91	0.87	1.11	1.11	1.16	1.22	1.27	1.33	1.39	1.45	1.51	1.57	1.63	1.68	1.74
20	11kV Burkay	0.09	0.12	0.10	0.14	0.10	0.10	0.11	0.11	0.11	0.12	0.12	0.12	0.13	0.13	0.13	0.13
21	33kV Sector I	3.21	1.91	2.56	3.03	2.87	2.96	3.04	3.13	3.22	3.30	3.39	3.48	3.56	3.65	3.74	3.82
22	33kV Sector II	2.84	2.85	2.80	2.84	2.85	3.90	3.91	3.92	3.93	3.93	3.94	3.95	3.95	3.96	3.97	
Total	33.39	29.81	32.39	38.86	36.64	38.97	39.93	40.71	41.57	42.20	43.27	44.00	44.87	45.57	46.48	47.28	



Sl. No	Feeder Name	Peak Load Consumption Pattern (MW)					Forecasted Peak Load Consumption Pattern (MW)										
		2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030
ESSD, Gedu & Lhamozingkha																	
1	11kV BBPL	1.32	1.43	1.43	1.56	1.73	1.78	1.88	1.97	2.07	2.16	2.26	2.35	2.44	2.54	2.63	2.73
2	11kV/Microwave	0.00	0.02	0.01	0.01	0.02	0.02	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.03	0.04
3	11kV/THPA II	0.40	0.78	0.50	0.60	0.70	0.76	0.81	0.86	0.90	0.95	1.00	1.05	1.10	1.14	1.19	1.24
4	11kV/Padechu/THPA I	0.15	0.20	0.19	0.17	0.21	0.21	0.22	0.23	0.24	0.25	0.26	0.26	0.27	0.28	0.29	0.30
5	11kV Mirchingchu I	0.05	0.08	0.09	0.08	0.09	0.10	0.11	0.12	0.13	0.13	0.14	0.15	0.16	0.17	0.17	0.18
6	11kV Geduchu	0.01	0.01	0.03	0.05	0.09	0.10	0.12	0.14	0.16	0.18	0.20	0.22	0.24	0.26	0.28	0.30
7	33kV Gunungdangra II	0.60	0.77	0.95	0.93	0.66	0.87	0.89	0.92	0.95	0.98	1.01	1.03	1.06	1.09	1.12	1.15
8	11kV Rinchenise	0.20	0.21	0.30	0.20	0.46	0.43	0.48	0.53	0.58	0.63	0.68	0.74	0.79	0.84	0.89	0.94
9	11kV Mirchingchu II	0.03	0.02	0.01	0.04	0.06	0.06	0.06	0.07	0.08	0.09	0.10	0.10	0.11	0.12	0.13	0.14
10	11kV Power House	0.01	0.01	0.03	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.04	0.04	0.04	0.05	0.05	0.05
11	11kV TRT or BVC	0.09	0.18	0.10	0.13	0.14	0.14	0.15	0.15	0.16	0.16	0.17	0.17	0.18	0.18	0.19	0.19
12	11kV Surge shaft	0.04	0.03	0.01	0.08	0.09	0.09	0.11	0.13	0.14	0.16	0.17	0.19	0.20	0.22	0.23	0.25
13	11kV Arekha/Sinchehka	0.21	0.30	0.20	0.32	0.44	0.44	0.49	0.53	0.58	0.63	0.68	0.73	0.77	0.82	0.87	0.92
14	33kV Gunungdangra I	1.20	1.20	1.20	0.95	1.12	1.19	1.26	1.33	1.40	1.47	1.54	1.61	1.68	1.75	1.82	
Total	4.31	5.24	5.05	5.39	5.66	6.14	6.55	6.96	7.37	7.78	8.19	8.60	9.01	9.42	9.83	10.24	





Load forecast methodology

1. Load Forecast

1.1 Type of Load Forecast and Power System Planning

One of the power system planning element is the load forecast. Although, there are no documented standards specifying the type of planning however, the power system planning can be short-term planning (STP) (less than one year), medium-term planning (MTP) (1-3 years) and long-term planning (LTP) (3-10 years and even higher). It is necessary to predict the power requirement for a specified time-horizon which is referred to as load (power) forecasting based on the historical consumption pattern for better planning and optimizing the available resources. Analogy to power system planning, the load forecast can be also short-term load forecasting (STLF), medium-term load forecasting (MTLF) and long-term load forecasting (LTLF) and accordingly the distribution network expansion programs are proposed¹ for distributing the electricity.

There are number of driving factors which are listed below affecting the forecasted load.

- a) Time
 - Hours of the day (day or night)
 - Day of the week (weekdays or weekend)
 - Time of the year (winter or summer season)
- b) Weather conditions (temperature and humidity)
- c) Type of customers (residential, commercial, industries etc.)
- d) Population
- e) Economic indicators (per capita income, Gross Domestic Product (GDP) etc.)
- f) Prices of the electricity

As the DSMP is being developed for 10-year period, the load forecast has to be done for same time horizon. Therefore, some of the driving factors as listed above which affects the LTLF may not impact the accuracy as daily, weekly and monthly time factors and weather conditions will have minimum contribution to the load variance.

1.2 Methods of Load (LTLF) Forecast

The LTLF methods are generally the trend analysis or time series analysis, economic modelling, end-use analysis and hybrid analysis. As the DSMP is for 10-year period, the methods of LTFL is being outlined for forecasting the load¹.

1.2.1 Trend Analysis

In the trend analysis, the historical data (power) is used to forecast the load. The details on load forecast adopting power consumption trend is reflected in **Section 1.3**. Typical load forecast is as shown in **Figure 1**.




Figure 1: Typical trend curve¹

1.2.2 Economic Modelling

In this method, the relationship between the load and the driving parameters are established and accordingly the future values of the driving factors are projected. Although, this approach is widely being used, as most of the data for driving factors are not available and for simplicity the trend analysis is adopted to forecast the load.

1.2.3 End-use Analysis

This approach is exclusively used for residential loads which is forecasted in terms of energy and therefore, it requires some methods to convert the predicted energy consumption to load (power demand). There is uncertainty in the accuracy of the predicted load and is also confined to residential customers. Therefore, end-use analysis approach is not adopted to predict the load.

1.2.4 Hybrid Analysis

Although, the end-use and econometric methods may be simultaneously used to forecast the load, it is not widely used as it has advantages and disadvantages of both the approaches.

1.3 Trend Line Analysis

The LTLF is carried out using the trend analysis approach and accordingly for planning the distribution system network. In order to forecast the load, the peak power demand prior to 2020 was considered and the power requirement trend is obtained. Load requirement is then predicted for next ten-year period (2020-2030) by extrapolating the trend line considering the load of 2019 as a base data. The case study of Punakha Dzongkhag is chosen to get insight of actual load forecast.




Figure 2: Flow diagram for load forecast

1.3.1 Normalizing the Data

Some of the distribution network do have ring feeders and multiple sources for better reliability and contingency. This in turn has resulted in abnormality in the power consumption data (recordings). Further, in the absence of meters or malfunctioning of the reading equipment or

recorded data, some of the feeders have unreliable data for some of the years. Therefore, data is normalized by omitting the outliers or by taking the average of the past data (or average of preceding and future load if a year's data is missing). Such exercise is carried out for all the feeders and substation loads.

Table 1: Actual power data of Punakha Dzongkhag

Sl.No.	Name of Feeder	Consumption Pattern (MW)						
		2013	2014	2015	2016	2017	2018	2019
1	Feeder A	1.85	2.01	0.90	0.22	2.45	2.64	2.63
2	Feeder B	0.48	0.51	4.86	0.50	0.49	0.74	0.72
3	Feeder C	1.35	1.60	1.60	1.80	2.10	1.76	2.40
4	Feeder D	0.96	1.02	1.47	1.48	1.80	2.24	1.89
Total		4.64	5.14	8.83	4.00	6.84	7.37	7.64




Figure 3: Actual data of Punakha Dzongkhag

$$x = \left(\frac{x_1 + x_2}{2} \right)$$

Where:

x is the normalized data

x_1 and x_2 is the data for two years

Table 2: Normalized power data of Punakha Dzongkhag

Sl.No.	Name of Feeder	Consumption Pattern (MW)						
		2013	2014	2015	2016	2017	2018	2019
1	Feeder A	1.85	2.01	1.93	1.97	2.45	2.64	2.63
2	Feeder B	0.48	0.51	0.49	0.50	0.49	0.74	0.72
3	Feeder C	1.35	1.60	1.60	1.80	2.10	1.76	2.40
4	Feeder D	0.96	1.02	1.47	1.48	1.80	2.24	1.89
Total		4.64	5.14	8.83	4.00	6.84	7.37	7.64

1.3.2 Trend Line and Load Forecast

Based on the power data, the trend line is added to portray the power consumption pattern which gets generated as per the linear regression equation¹. The trend line added is then extrapolated to forecast the load for next ten years which is as shown in **Figure 4**.




Figure 4: Trend line and load forecast for Punakha Dzongkhag

The trend line equation is given by²:

$$y = ax + b$$

Where:

y is the dependent variable or forecasted load

a is the slope which is the average change in *y* for every increment of *x* (increase in year).

It also gives *x* is the independent variable or time in year

b is the intercept which is the predicted value of *y* when *x* is zero (time is zero)

The Pearson correlation coefficient '*r*', which can take values between -1 & 1 corresponds to the linear relationship between variables *x* & *y*. If the *r* value is either -1 or 1, dependent variable can be perfectly explained by a linear function of the other.

□

Feeder A (LRM/TSA) Feeder A (Average)




Figure 5: Forecasted load (trend line with red shows the linear regression and one with blue shows the forecast with average method)

2. Electrical Transient Analyser Program (ETAP) –Modelling and Load Flow Analysis

2.1 ETAP Software

“**ETAP** is an analytical engineering solution tool specializing in the simulation, design, monitoring, control, operator training, optimizing, and automating power systems³. ETAP’s integrated digital platform offers the best comprehensive suite of enterprise solutions.”

ETAP software is used in DSMP for modelling/designing, network simulation and to carry out the technical evaluation for distribution power system. The modelled network is fed with the essential data (such as specifications, constraints and parameters for network components) and the simulation results are assessed and analysed. Conclusively, different measures are considered and performed in ETAP for improving the efficiency of a system.

2.2 Load Flow Analysis (ETAP)

Load Flow Analysis (LFA) is a major tool to study and analyse the operation of a power system and determines voltage drops and power flow throughout the electrical system. Using network parameters (Input) for power sources, lines, transformers and connected loads, LFA provides voltages magnitude, real/reactive power, currents, and power losses as a result from the load flow simulation. The study also allows for swing, voltage regulated, and unregulated power sources with multiple power grids and generator connections and the analysis can be performed on both radial and loop systems.

Numerical analysis method such as Adaptive Newton-Raphson, Newton-Raphson, Fast Decoupled, & Accelerated Gauss Seidel methods are accessible in ETAP and can be used for solving the load flow analysis problems.

In this analysis, Adaptive Newton-Raphson method is used for load flow study of distribution networks and the study is carried out under 3-time horizon: present (2019), 2025 and 2030 (forecast load). The results (total generation, loading, system losses, and critical report of load flow) obtained under the scenarios are analysed and corresponding corrective measures are proposed.

2.2.1 Creating the Library

Although, the electrical parameters and specifications are inbuilt, to suit the requirements of the study, the missing electrical parameters are customized by creating a library. The units are

set to metric system and accordingly the network is modelled and the relative data for network components such as transformers, line types, power sources and load details are fed in which are detailed as follows:

a) Transmission Cable

- Library-Transmission Line-Phase Conductor-Add-Transmission line library
- In transmission line library: change unit system into Metric, conductor type into ACSR and frequency into 50HZ, and Source name as BPC.
- Click BPC and click edit properties.
- In edit properties add the required conductor parameter by referring the Excel sheet (technical parameters.)
- For AAC use the source name “Pirelli” and select the required size.

b) UG cable (Since 33kV AI UG Cable is not available):

- Library- Cable- Add-change the source name to BPC and make the necessary changes especially type of conductor to Aluminium and installation into non-magnetic.
- Change insulation type to XLPE.
- Select BPC from the Cable library table and click edit properties
- In edit properties add the required UG cable parameters referring the Excel sheet as shown in Pictures below.

c) Set Loading and Generation Categories.

- Go to Project- Settings- Loading and generation categories
- In Generation Category, set 3 categories as Maximum, Normal and Minimum.
- In AC Load, set 3 categories as 2019, 2025 and 2030.
- Keep the DC Load Empty.

2.2.2 Network Modelling and Load Flow Analysis

- a) Draw Distribution Network (SLD).
- b) Enter the height=8 and spacing =1.25 in the Transmission line table.
- c) Enter the electrical parameters (kW, kVA, kV, etc.) ratings for power sources, transformers, line type, bus kV and loading details.

- d) Under the Lump Load, in “Nameplate” edit and enter DT % loading and forecasted % loading details for 2019,2025,2030. Set the load type (80% as constant impedance and 20% as constant KVA) as most of the loads are impedance load.
- e) Make sure to run the load flow for each composite network before you continue with other network. This is to avoid numerous errors at the end.
- f) After completing the SLD, study case for different load scenarios needs to be created.
- g) Switch to “Load Flow Analysis” mode in Mode Toolbar. Go to “Study Case,” select present Case 1 as 2019 and select “Prompt” in “Output Report”
- h) Edit the “Load Flow Study Case [Brief Case Symbol].” Go to “Loading” and set to “2019” under Loading Category and set “Normal” under Generation Category. Check the Margins set under Alerts and set “Marginal ($\pm 5\%$ for Over and Under Voltage Category)” and set “Critical ($\pm 10\%$ for Over and Under Voltage Category)”
- i) Close “Load Flow Study Case” and run “Run Load Flow” and save the result as 2019.
- j) Similarly, follow step b), c) and d) for 2025 and 2030.
- k) To generate the report (SLD drawings) in PDF, go to print preview- set up- change the printer name “Microsoft print to PDF”.

2.3 Consideration/Assumptions made while simulating in ETAP software

- a) All Network is considered as balanced system as there is limitation of unbalanced system in ETAP Key.
- b) The voltage level of $\pm 10\%$ is given as critical value which is indicated by red colour while simulating and voltage level of $\pm 5\%$ is given as marginal value which is indicated by pink colour while simulating.
- c) The typical value of X/R ratio from ETAP inbuilt system is taken for all the power transformers for the simulation.
- d) Some of the types of transmission cables /underground cables used in BPC are not available in ETAP library therefore, a new source is created in ETAP library by inserting all the parameters of those unavailable cables/transmission lines.
- e) There are three cases created in ETAP simulation depending on the load forecast namely the 2019, 2025 and 2030 where the forecasted loads are given respectively and simulated/analysed accordingly.




Figure 6: Flow Chart for Network Modelling & Load Flow Analysis (ETAP)


¹Electric Power System Planning Issues, Algorithms and Solutions by Hossein Seifi Mohammad Sadegh Sepasian

²<http://sites.utexas.edu/sos/guided/inferential/numeric/bivariate/cor/>: dated September 29, 2020

³<http://www.powerqualityworld.com/2011/05/etap-tutorials-load-flow-analysis.html> dated September 30, 2020


Annexure 4: The Simulation Results

One-Line Diagram - ESD Pling=>B30 (Load Flow Analysis)




Simulation results for feeders with voltage profile issues


One-Line Diagram - ESD Pling=>B30 (Load Flow Analysis)




One-Line Diagram - ESD Pling=>B30 (Load Flow Analysis)




One-Line Diagram - ESD Pling=>B30 (Load Flow Analysis)




One-Line Diagram - ESSD Gedu=>B100 (Load Flow Analysis)




One-Line Diagram - ESSD Gedu=>B100 (Load Flow Analysis)



One-Line Diagram - ESSD Gedu=>B100 (Load Flow Analysis)




One-Line Diagram - ESSD Gedu=>B100 (Load Flow Analysis)



11kV BBPL Feeder Improved (Reconfiguring the source from Gurungdangra)-2030

One-Line Diagram - ESD Pling (Load Flow Analysis)



Project:	ETAP	Page:	1
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus Loading Summary Report

Bus	Directly Connected Load								Total Bus Load					
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar			
Bus1		66.000										23.289	82.3	203.7
Bus2		11.000										11.387	85.4	620.4
Bus3		11.000										1.894	85.3	103.2
Bus4		11.000										1.884	85.3	103.2
Bus5		11.000		0.007	0.004	0.072	0.045					0.093	85.0	5.1
Bus6		11.000										1.781	85.3	98.1
Bus7		11.000		0.014	0.009	0.106	0.066					0.142	85.0	7.8
Bus8		11.000		0.054	0.034	0.197	0.122					1.605	85.3	88.6
Bus9		11.000		0.001	0.001	0.016	0.010					0.815	85.4	45.6
Bus10		11.000										0.792	85.4	44.5
Bus11		11.000		0.004	0.002	0.062	0.038					0.077	85.0	4.3
Bus12		11.000		0.001	0.001	0.016	0.010					0.714	85.4	40.1
Bus13		11.000		0.007	0.004	0.120	0.074					0.694	85.4	39.0
Bus14		11.000		0.001	0.001	0.014	0.009					0.018	85.0	1.0
Bus15		11.000										0.544	85.5	30.6
Bus16		11.000		0.001	0.000	0.013	0.008					0.016	85.0	0.9
Bus17		11.000										0.525	85.5	29.6
Bus18		11.000		0.004	0.003	0.066	0.041					0.509	85.5	28.7
Bus19		11.000		0.001	0.001	0.014	0.008					0.017	85.0	1.0
Bus20		11.000										0.425	85.6	24.1
Bus21		11.000		0.001	0.000	0.012	0.008					0.015	85.0	0.9
Bus22		11.000										0.406	85.5	23.1
Bus23		11.000		0.001	0.001	0.019	0.012					0.023	85.0	1.3
Bus24		11.000										0.391	85.5	22.3
Bus25		11.000		0.001	0.000	0.011	0.007					0.014	85.0	0.8
Bus26		11.000										0.367	85.5	21.0
Bus27		11.000		0.233	0.144	0.010	0.006					0.286	85.0	16.5
Bus28		11.000										0.351	85.3	20.2
Bus29		11.000		0.002	0.001	0.032	0.020					0.040	85.0	2.3
Bus30		11.000										0.065	86.2	3.7
Bus31		11.000		0.000	0.000	0.013	0.008					0.025	87.2	1.5
Bus35		11.000										1.525	85.1	83.1
Bus36		11.000		0.224	0.139	0.069	0.043					0.345	85.0	18.8
Bus37		11.000		0.011	0.007	0.049	0.030					1.180	85.1	64.3
Bus38		11.000		0.080	0.049	0.008	0.005					0.103	85.0	5.6
Bus39		11.000		0.018	0.011	0.122	0.076					1.005	85.1	54.9
Bus40		11.000		0.143	0.089	0.015	0.009					0.186	85.0	10.2
Bus41		11.000		0.064	0.039	0.208	0.129					0.654	85.1	35.7
Bus42		11.000		0.188	0.116	0.078	0.048					0.312	85.0	17.1

Project:	ETAP	Page:	2
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus43		11.000		0.003	0.002	0.017	0.010			0.023	85.0	1.3			
Bus44		33.000				0.011	0.007			0.013	85.0	0.2			
Bus45		11.000		0.025	0.016	0.107	0.066			0.155	85.0	8.5			
Bus46		11.000		0.225	0.139	0.103	0.064			4.100	85.6	223.5			
Bus47		11.000		0.324	0.201	0.090	0.056			3.713	85.7	202.5			
Bus48		11.000		0.091	0.056	0.042	0.026			3.225	85.8	175.9			
Bus49		11.000								3.055	85.6	167.5			
Bus50		11.000		0.011	0.007	0.113	0.070			0.559	85.2	30.7			
Bus51		11.000		0.179	0.111	0.010	0.006			0.415	85.0	22.8			
Bus52		11.000		0.108	0.067	0.056	0.034			0.192	85.0	10.6			
Bus53		11.000								2.490	85.6	136.9			
Bus54		11.000		0.163	0.101	0.099	0.061			0.309	85.0	17.0			
Bus55		11.000		0.300	0.186	0.116	0.072			2.174	85.5	120.0			
Bus56		11.000		0.083	0.051	0.391	0.242			1.683	85.6	93.1			
Bus57		11.000		0.111	0.069	0.010	0.006			0.143	85.0	7.9			
Bus58		11.000								2.028	86.0	110.6			
Bus59		11.000		0.103	0.064	0.011	0.007			2.016	85.9	110.6			
Bus60		11.000								1.864	85.9	103.3			
Bus61		11.000		0.010	0.006	0.078	0.049			0.104	85.0	5.8			
Bus62		11.000								0.399	85.1	22.3			
Bus63		11.000		0.003	0.002	0.113	0.070			0.136	85.0	7.6			
Bus64		11.000								0.982	85.0	54.8			
Bus65		11.000		0.042	0.026	0.117	0.073			0.187	85.0	10.4			
Bus66		11.000		0.011	0.007	0.088	0.054			0.116	85.0	6.5			
Bus67		11.000		0.000	0.000	0.038	0.024			0.295	85.0	16.5			
Bus68		11.000								1.710	85.9	95.9			
Bus69		11.000				0.004	0.002			0.021	87.2	1.2			
Bus70		11.000								0.023	88.1	1.3			
Bus71		11.000								0.017	87.5	1.0			
Bus72		11.000				0.004	0.002			0.004	85.0	0.2			
Bus73		11.000								0.013	88.0	0.7			
Bus74		11.000				0.004	0.002			0.010	86.6	0.6			
Bus75		11.000				0.005	0.003			0.006	85.0	0.4			
Bus78		11.000				0.006	0.003			1.683	85.9	94.6			
Bus79		11.000								1.651	85.8	94.2			
Bus80		11.000				0.004	0.003			0.012	87.0	0.7			
Bus81		11.000				0.003	0.002			0.003	85.0	0.2			
Bus82		11.000								0.007	87.1	0.4			
Bus83		11.000				0.003	0.002			0.004	85.0	0.2			
Bus84		11.000				0.010	0.006			1.604	85.6	93.5			
Bus85		11.000				0.009	0.006			0.011	85.0	0.6			
Bus86		11.000								1.561	85.6	92.2			

Project:	ETAP	Page:	3
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus87		11.000				0.004	0.002					0.005	85.0	0.3	
Bus88		11.000		0.066	0.041	0.002	0.001					0.079	85.0	4.8	
Bus89		11.000										1.496	85.3	91.3	
Bus90		11.000										1.414	85.3	86.5	
Bus91		11.000	0.115	0.071	0.009	0.006						0.146	85.0	8.9	
Bus92		11.000										0.419	85.0	25.6	
Bus93		11.000	0.031	0.019	0.034	0.021						0.076	85.0	4.6	
Bus94		11.000				0.014	0.009					0.990	85.4	60.8	
Bus95		11.000	0.043	0.027	0.126	0.078						0.970	85.4	59.8	
Bus96		11.000				0.005	0.003					0.006	85.0	0.4	
Bus97		11.000										0.764	85.4	47.5	
Bus98		11.000				0.009	0.005					0.010	85.0	0.6	
Bus99		11.000										0.754	85.4	47.2	
Bus100		11.000										0.734	85.3	46.6	
Bus101		11.000	0.124	0.077	0.003	0.002						0.149	85.0	9.4	
Bus102		11.000										0.172	85.3	10.9	
Bus103		11.000				0.004	0.002					0.004	85.0	0.3	
Bus104		11.000										0.023	86.7	1.5	
Bus105		11.000				0.004	0.003					0.005	85.0	0.3	
Bus106		11.000										0.019	86.6	1.2	
Bus107		11.000				0.003	0.002					0.014	86.3	0.9	
Bus108		11.000				0.005	0.003					0.010	86.2	0.6	
Bus109		11.000				0.003	0.002					0.004	85.0	0.3	
Bus110		11.000	0.105	0.065	0.005	0.003						0.129	85.0	8.3	
Bus111		11.000										0.559	85.2	35.7	
Bus112		11.000				0.003	0.002					0.004	85.0	0.3	
Bus113		11.000										0.429	85.2	27.4	
Bus114		11.000				0.011	0.007					0.424	85.2	27.2	
Bus115		11.000	0.101	0.063	0.002	0.001						0.122	85.0	7.8	
Bus116		11.000										0.411	85.2	26.4	
Bus117		11.000	0.000	0.000	0.005	0.003						0.006	85.0	0.4	
Bus118		11.000										0.289	85.2	18.6	
Bus119		11.000	0.233	0.145	0.003	0.002						0.278	85.0	18.0	
Bus120		11.000										0.282	85.1	18.2	
Bus122		33.000			0.000							11.144	83.9	200.7	
Bus123		33.000										1.455	94.1	26.2	
Bus124		33.000										1.455	93.8	26.3	
Bus125		33.000										0.640	90.6	11.6	
Bus126		33.000	0.313	0.194	0.029	0.018						0.403	85.0	7.3	
Bus127		33.000	0.000	0.000	0.030	0.018						0.247	96.4	4.5	
Bus128		33.000				0.017	0.010					0.020	85.0	0.4	
Bus129		33.000										0.214	97.3	3.9	

Project:	ETAP	Page:	4
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load					
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar			
Bus130		33.000				0.031	0.019					0.036	85.0	0.7
Bus131		33.000										0.196	97.7	3.5
Bus132		33.000				0.017	0.011					0.163	98.5	2.9
Bus133		33.000										0.145	99.2	2.6
Bus134		33.000				0.004	0.003					0.052	97.7	0.9
Bus135		33.000												-
Bus136		33.000										0.050	92.6	0.9
Bus137		33.000				0.017	0.010					0.051	91.4	0.9
Bus138		33.000										0.032	93.3	0.6
Bus139		33.000				0.012	0.008					0.014	85.0	0.3
Bus140		33.000				0.014	0.009					0.020	89.2	0.4
Bus142		33.000				0.013	0.008					0.016	85.0	0.3
Bus143		33.000										0.094	98.8	1.7
Bus144		33.000				0.012	0.007					0.081	98.9	1.5
Bus145		33.000				0.011	0.007					0.069	99.2	1.2
Bus146		33.000				0.014	0.009					0.058	98.8	1.0
Bus147		33.000				0.011	0.007					0.044	98.1	0.8
Bus148		33.000				0.010	0.006					0.034	93.0	0.6
Bus149		33.000				0.010	0.006					0.024	92.4	0.4
Bus150		33.000				0.002	0.001					0.013	96.2	0.2
Bus151		33.000				0.008	0.005					0.010	85.0	0.2
Bus152		33.000										0.011	99.8	0.2
Bus154		33.000				0.011	0.007					0.820	95.6	14.8
Bus155		33.000				0.008	0.005					0.809	95.6	14.6
Bus156		33.000										0.800	95.7	14.5
Bus157		33.000				0.008	0.005					0.014	87.8	0.2
Bus159		33.000				0.011	0.007					0.788	95.6	14.3
Bus160		33.000				0.010	0.006					0.776	95.6	14.1
Bus161		33.000										0.765	95.7	13.9
Bus162		33.000										0.075	91.9	1.3
Bus163		33.000				0.014	0.009					0.050	88.3	0.9
Bus167		33.000				0.003	0.002					0.027	90.1	0.5
Bus168		33.000										0.024	87.6	0.4
Bus169		33.000				0.010	0.006					0.012	85.0	0.2
Bus170		33.000				0.011	0.007					0.013	85.0	0.2
Bus171		33.000										0.692	95.9	12.5
Bus172		33.000										0.051	97.6	0.9
Bus175		33.000				0.014	0.009					0.017	85.0	0.3
Bus176		33.000										0.042	98.0	0.8
Bus177		33.000										0.027	97.6	0.5
Bus178		33.000				0.003	0.002					0.015	97.1	0.3
Bus179		33.000				0.010	0.006					0.011	85.0	0.2

Project:	ETAP	Page:	5
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus			Directly Connected Load				Total Bus Load				Percent			
ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Loading
Bus180	33.000			0.002	0.001						0.012	94.5	0.2	
Bus181	33.000			0.012	0.007						0.014	85.0	0.3	
Bus182	33.000			0.018	0.011						0.642	95.7	11.6	
Bus183	33.000										0.623	95.8	11.3	
Bus184	33.000			0.014	0.009						0.017	85.0	0.3	
Bus185	33.000												-	
Bus186	33.000			0.012	0.007						0.607	96.0	11.0	
Bus187	33.000			0.003	0.002						0.595	95.9	10.8	
Bus188	33.000			0.013	0.008						0.592	95.7	10.7	
Bus189	33.000			0.014	0.009						0.578	95.8	10.5	
Bus190	33.000			0.015	0.009						0.564	95.7	10.2	
Bus191	33.000										0.547	95.9	9.9	
Bus192	33.000			0.013	0.008						0.253	95.6	4.6	
Bus193	33.000			0.029	0.018						0.239	95.5	4.3	
Bus194	33.000										0.207	96.6	3.8	
Bus195	33.000			0.017	0.010						0.121	97.5	2.2	
Bus196	33.000												-	
Bus197	33.000										0.104	98.3	1.9	
Bus198	33.000			0.026	0.016						0.031	85.0	0.6	
Bus199	33.000										0.104	97.8	1.9	
Bus200	33.000			0.014	0.009						0.088	92.1	1.6	
Bus201	33.000			0.031	0.019						0.073	91.5	1.3	
Bus202	33.000			0.035	0.022						0.042	85.9	0.8	
Bus206	33.000			0.033	0.021						0.078	96.5	1.4	
Bus207	33.000										0.043	98.0	0.8	
Bus208	33.000			0.008	0.005						0.030	94.3	0.5	
Bus209	33.000			0.008	0.005						0.021	97.0	0.4	
Bus210	33.000			0.012	0.007						0.014	85.0	0.3	
Bus211	33.000			0.005	0.003						0.015	92.9	0.3	
Bus212	33.000			0.009	0.006						0.011	85.0	0.2	
Bus213	33.000			0.004	0.003						0.295	96.0	5.3	
Bus214	33.000			0.018	0.011						0.291	95.8	5.3	
Bus215	33.000			0.013	0.008						0.271	96.2	4.9	
Bus216	33.000			0.011	0.007						0.013	85.0	0.2	
Bus217	33.000										0.256	96.5	4.7	
Bus218	33.000			0.011	0.007						0.245	96.6	4.5	
Bus219	33.000										0.232	97.0	4.2	
Bus220	33.000			0.004	0.002						0.041	89.4	0.8	
Bus221	33.000			0.012	0.007						0.038	87.5	0.7	
Bus222	33.000										0.024	88.4	0.4	
Bus223	33.000			0.011	0.007						0.013	85.0	0.2	
Bus224	11.000	0.073	0.046	0.024	0.015						4.232	85.0	240.7	

Project:	ETAP	Page:	6
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus225		33.000								0.193	97.6	3.5
Bus227		33.000			0.011	0.007				0.013	85.0	0.2
Bus228		33.000			0.007	0.005				0.192	97.1	3.5
Bus229		33.000			0.015	0.009				0.180	97.2	3.3
Bus230		33.000			0.014	0.009				0.173	96.9	3.1
Bus231		33.000			0.009	0.005				0.017	85.0	0.3
Bus232		33.000			0.010	0.006				0.157	97.4	2.8
Bus233		33.000			0.013	0.008				0.088	97.7	1.6
Bus234		33.000			0.011	0.007				0.011	85.0	0.2
Bus235		33.000			0.008	0.005				0.079	98.0	1.4
Bus236		33.000			0.010	0.006				0.016	85.0	0.3
Bus237		33.000			0.012	0.007				0.069	97.3	1.3
Bus238		33.000			0.014	0.009				0.055	98.6	1.0
Bus239		33.000			0.011	0.007				0.023	92.8	0.4
Bus240		33.000			0.008	0.005				0.012	85.0	0.2
Bus241		33.000			0.005	0.003				0.033	99.4	0.6
Bus242		33.000			0.008	0.005				0.015	89.0	0.3
Bus243		33.000			0.008	0.005				0.006	85.0	0.1
Bus244		33.000			0.007	0.004				0.021	96.2	0.4
Bus245		33.000			0.014	0.009				0.013	93.7	0.2
Bus247		33.000			0.012	0.007				0.054	98.3	1.0
Bus248		33.000			0.009	0.005				0.039	98.2	0.7
Bus249		33.000			0.010	0.006				0.010	85.0	0.2
Bus250		33.000			0.008	0.005				0.028	95.9	0.5
Bus251		33.000			0.011	0.007				0.019	93.2	0.3
Bus252		33.000			0.010	0.006				0.012	85.0	0.2
Bus253		33.000			0.013	0.009				4.869	81.8	87.8
Bus254		33.000			0.014	0.009				4.865	81.8	87.8
Bus255		33.000			0.015	0.009				4.863	81.8	87.8
Bus256		33.000			0.016	0.009				4.847	81.9	87.4
Bus257		33.000			0.017	0.009				4.843	81.9	87.5
Bus258		33.000			0.018	0.009				4.841	81.9	87.5
Bus259		11.000			0.019	0.009				9.250	85.2	525.9
Bus260		11.000			0.020	0.010				3.608	85.0	205.7
Bus261		11.000			0.021	0.010				0.143	85.0	8.1
Bus262		11.000			0.022	0.010				3.120	85.0	178.2
Bus263		11.000			0.023	0.010				2.637	85.0	150.7
Bus264		11.000			0.024	0.010				1.022	85.0	58.4
Bus265		11.000			0.025	0.010				0.241	85.0	13.8
Bus266		11.000			0.026	0.010				0.475	85.0	27.2
Bus267		11.000			0.027	0.010				0.244	85.0	13.9
Bus268		11.000			0.028	0.010						

Project:	ETAP	Page:	7
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus269		11.000		0.037	0.023	0.318	0.197					0.926	85.0	53.0	
Bus270		11.000		0.118	0.073	0.314	0.195					0.508	85.0	29.1	
Bus271		11.000										1.680	84.8	91.5	
Bus272		11.000		0.045	0.028	0.188	0.116					1.674	84.9	91.5	
Bus273		11.000		0.066	0.041	0.177	0.110					5.381	85.4	306.7	
Bus274		11.000		0.090	0.056	0.242	0.150					2.466	85.0	140.7	
Bus275		11.000										0.256	85.0	14.6	
Bus276		11.000		0.029	0.018	0.076	0.047					0.124	85.0	7.1	
Bus277		11.000		0.031	0.019	0.082	0.051					0.132	85.0	7.6	
Bus278		11.000		0.076	0.047	0.205	0.127					1.818	85.0	103.8	
Bus279		11.000		0.031	0.019	0.083	0.052					0.346	85.0	19.8	
Bus280		11.000		0.049	0.030	0.131	0.081					0.212	85.0	12.1	
Bus281		11.000		0.053	0.033	0.701	0.434					0.887	85.0	50.7	
Bus282		11.000										1.397	85.0	76.6	
Bus283		11.000										1.397	85.0	76.6	
Bus284		11.000										1.394	85.0	76.6	
Bus285		11.000		0.047	0.029	0.312	0.194					0.422	85.0	23.2	
Bus286		11.000		0.009	0.006	0.206	0.127					0.524	85.0	28.8	
Bus287		11.000		0.020	0.012	0.211	0.130					0.271	85.0	14.9	
Bus288		11.000		0.009	0.006	0.108	0.067					0.447	85.1	24.6	
Bus289		11.000		0.003	0.002	0.125	0.078					0.151	85.0	8.3	
Bus290		11.000		0.001	0.001	0.056	0.035					0.159	85.0	8.7	
Bus291		11.000		0.004	0.003	0.074	0.046					0.092	85.0	5.0	
Bus292		11.000										2.624	85.7	149.7	
Bus293		11.000		0.013	0.008	0.169	0.105					0.214	85.0	12.2	
Bus294		11.000		0.013	0.008	0.169	0.105					0.214	85.0	12.2	
Bus295		11.000		0.024	0.015	0.205	0.127					2.192	85.9	125.3	
Bus296		11.000										1.913	85.7	110.0	
Bus297		11.000		0.020	0.012	0.161	0.100					1.447	85.0	84.1	
Bus298		11.000		0.010	0.006	0.085	0.053					0.317	85.7	18.3	
Bus299		11.000		0.012	0.007	0.100	0.062					0.131	85.0	7.5	
Bus300		11.000		0.004	0.003	0.011	0.007					0.018	85.0	1.0	
Bus301		11.000										0.239	85.0	13.6	
Bus302		11.000		0.002	0.001	0.201	0.124					0.239	85.0	13.6	
Bus303		66.000										10.894	85.8	95.3	
Bus304		11.000										10.734	86.9	571.8	
Bus305		11.000										0.152	85.3	8.1	
Bus306		11.000										0.152	85.3	8.1	
Bus307		11.000			0.032	0.020						0.038	85.0	2.0	
Bus308		11.000			0.061	0.038						0.114	85.1	6.1	
Bus309		11.000			0.036	0.023						0.043	85.0	2.3	
Bus310		11.000		0.012	0.007	0.362	0.225					0.440	85.0	23.5	

Project:	ETAP	Page:	8
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus311		11.000								0.440	85.0	23.5
Bus312		11.000								6.270	88.5	334.6
Bus313		11.000								6.252	86.7	344.3
Bus314		11.000								0.575	76.8	31.7
Bus315		11.000	0.211	0.131	0.077	0.048				0.339	85.0	18.8
Bus316		11.000								5.821	84.8	323.4
Bus317		11.000	0.071	0.044	0.031	0.019				0.121	85.0	6.7
Bus318		11.000	0.063	0.039	0.027	0.017				5.341	84.8	297.9
Bus319		11.000	0.038	0.024	0.017	0.010				5.214	84.9	292.0
Bus320		11.000	0.045	0.028	0.351	0.217				0.465	85.0	26.1
Bus321		11.000								4.751	84.9	266.8
Bus322		11.000	0.404	0.250	0.133	0.082				4.107	85.0	234.2
Bus323		11.000	0.029	0.018	0.026	0.016				3.465	85.0	198.1
Bus324		11.000				0.016	0.010			3.384	85.0	194.5
Bus325		11.000				0.059	0.037			0.086	87.3	4.9
Bus326		11.000	0.000	0.000	0.015	0.010				0.018	85.0	1.1
Bus327		11.000								3.238	85.1	188.5
Bus328		11.000				0.138	0.085			0.489	85.0	28.5
Bus329		11.000	0.084	0.052	0.025	0.016				0.128	85.0	7.5
Bus330		11.000	0.013	0.008	0.001	0.001				0.017	85.0	1.0
Bus331		11.000								2.732	85.1	160.0
Bus332		11.000								2.712	85.1	159.0
Bus333		11.000				0.015	0.009			0.058	85.0	3.4
Bus334		11.000	0.026	0.016	0.008	0.005				0.041	85.0	2.4
Bus335		11.000	0.135	0.084	0.048	0.030				0.215	85.0	12.7
Bus336		11.000	0.016	0.010	0.168	0.104				2.305	85.2	136.2
Bus337		11.000	0.405	0.251	0.150	0.093				0.653	85.0	38.6
Bus338		11.000				0.135	0.084			0.159	85.0	9.4
Bus339		11.000								0.939	85.5	55.6
Bus340		11.000				0.200	0.124			0.235	85.0	13.9
Bus341		11.000								0.604	85.0	35.8
Bus342		11.000	0.004	0.003	0.160	0.099				0.193	85.0	11.4
Bus343		11.000								0.193	85.0	11.4
Bus344		11.000								0.982	85.0	57.3
Bus345		11.000								0.641	85.0	37.4
Bus346		11.000	0.268	0.166	0.024	0.015				0.343	85.0	20.0
Bus347		11.000	0.006	0.004	0.246	0.153				0.297	85.0	17.3
Bus348		11.000	0.004	0.002	0.286	0.177				0.341	85.0	19.9
Bus349		11.000	0.030	0.019	0.024	0.015				0.249	85.0	14.5
Bus350		11.000								1.233	85.0	71.8
Bus351		11.000								3.565	84.5	190.2
Bus352		11.000	1.744	1.081	1.211	0.751				3.477	85.0	190.2

Project:	ETAP	Page:	9
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus353		66.000										13.579	79.3	118.8	
Bus354		11.000										13.055	82.1	712.7	
Bus355		11.000										1.779	65.0	97.2	
Bus356		11.000										1.769	64.8	97.2	
Bus357		11.000		0.007	0.004	0.026	0.016					0.732	17.5	40.3	
Bus358		11.000										0.881	60.8	48.5	
Bus359		11.000		0.318	0.197	0.218	0.135					0.630	85.0	34.7	
Bus360		11.000		0.002	0.001	0.087	0.054					1.191	85.1	65.5	
Bus361		11.000										1.078	85.0	59.8	
Bus362		11.000		0.002	0.001	0.051	0.032					0.539	85.0	29.9	
Bus363		11.000		0.266	0.165	0.140	0.087					0.477	85.0	26.4	
Bus364		11.000		0.052	0.032	0.045	0.028					0.538	85.0	29.9	
Bus365		11.000		0.056	0.035	0.035	0.022					0.424	85.0	23.6	
Bus366		11.000		0.047	0.029	0.037	0.023					0.317	85.0	17.6	
Bus367		11.000										0.217	85.0	12.1	
Bus368		11.000		0.054	0.033	0.033	0.021					0.217	85.0	12.1	
Bus369		11.000		0.062	0.038	0.035	0.022					0.115	85.0	6.4	
Bus370		11.000										4.726	84.8	258.2	
Bus371		11.000		0.001	0.000	0.019	0.012					4.609	85.4	258.2	
Bus372		11.000										4.576	85.4	256.9	
Bus373		11.000		0.003	0.002	0.005	0.003					0.009	85.0	0.5	
Bus374		11.000		0.068	0.042	0.138	0.085					0.241	85.0	13.6	
Bus375		11.000										4.563	85.5	256.4	
Bus376		11.000		0.013	0.008	0.026	0.016					4.314	85.5	242.8	
Bus377		11.000		0.026	0.016	0.052	0.032					4.263	85.6	240.3	
Bus378		11.000		0.017	0.011	0.022	0.014					4.158	85.6	235.2	
Bus379		11.000		0.383	0.237	0.766	0.475					1.351	85.0	76.5	
Bus380		11.000										4.105	85.7	232.5	
Bus381		11.000				1.966	1.219					2.736	86.1	156.0	
Bus382		11.000										5.657	83.6	309.1	
Bus383		11.000		0.964	0.598	0.527	0.326					5.443	84.4	309.1	
Bus384		11.000		0.210	0.130	0.114	0.071					3.683	84.1	209.5	
Bus385		11.000										3.293	84.1	187.8	
Bus386		11.000		0.677	0.419	0.366	0.227					1.227	85.0	70.0	
Bus387		11.000		0.881	0.546	0.477	0.296					2.065	83.5	117.8	
Bus388		11.000				0.016	0.010					0.469	78.1	26.8	
Bus389		11.000		0.210	0.130	0.114	0.070					0.381	85.0	21.7	
Bus390		11.000										0.451	77.7	25.7	
Bus391		11.000		0.176	0.109	0.058	0.036					0.275	85.0	15.7	
Bus392		11.000		0.012	0.007	0.000	-					0.230	95.4	13.1	
Bus393		11.000		0.017	0.010	0.005	0.003					0.255	94.6	14.6	
Bus394		11.000		0.079	0.049	0.043	0.026					0.143	85.0	8.2	

Project:	ETAP	Page:	10
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus395		11.000										0.425	91.3	24.3	
Bus396		11.000		0.024	0.015	0.001	0.001					0.030	85.0	1.7	
Bus397		11.000										0.419	85.0	22.9	
Bus398		11.000										0.419	85.0	22.9	
Bus399		11.000		0.173	0.107	0.075	0.047					0.293	85.0	16.0	
Bus400		11.000		0.001	0.000	0.053	0.033					0.126	85.0	6.9	
Bus401		11.000		0.026	0.016	0.028	0.017					0.064	85.0	3.5	
Bus402		11.000										0.533	85.5	29.1	
Bus403		11.000				0.042	0.026					0.531	85.5	29.1	
Bus404		11.000										0.480	85.5	26.4	
Bus405		11.000										0.039	86.5	2.1	
Bus406		11.000										-			
Bus407		11.000				0.021	0.013					0.025	85.0	1.4	
Bus408		11.000										0.039	86.0	2.2	
Bus409		11.000				0.006	0.004					0.015	86.6	0.8	
Bus410		11.000				0.006	0.004					0.007	85.0	0.4	
Bus411		11.000										0.441	85.3	24.3	
Bus412		11.000	0.025	0.016	0.012	0.008						0.044	85.0	2.4	
Bus413		11.000										0.396	85.3	21.9	
Bus415		11.000										0.208	85.2	11.5	
Bus416		11.000				0.024	0.015					0.204	85.1	11.3	
Bus417		11.000	0.101	0.062	0.049	0.030						0.176	85.0	9.8	
Bus418		11.000				0.125	0.077					0.187	85.3	10.4	
Bus420		11.000				0.004	0.002					0.041	85.9	2.3	
Bus421		11.000				0.010	0.006					0.037	85.9	2.0	
Bus423		11.000										0.026	85.9	1.4	
Bus424		11.000				0.007	0.004					0.018	85.8	1.0	
Bus425		11.000				0.009	0.005					0.010	85.0	0.6	
Bus426		11.000				0.002	0.001					0.002	85.0	0.1	
Bus427		11.000				0.002	0.001					0.003	85.0	0.1	
Bus428		11.000				0.003	0.002					0.004	85.0	0.2	
Bus429		11.000										0.010	88.8	0.6	
Bus430		11.000				0.004	0.002					0.004	85.0	0.2	
Bus431		11.000				0.005	0.003					0.006	85.0	0.4	
Bus432		33.000				0.003	0.002					0.004	85.0	0.1	
Bus433		33.000				0.004	0.002					0.004	85.0	0.1	
Bus434		33.000				0.005	0.003					0.009	91.3	0.2	
Bus435		33.000				0.003	0.002					0.004	85.0	0.1	
Bus438		33.000				0.013	0.008					0.034	88.5	0.6	
Bus439		33.000				0.012	0.007					0.019	87.4	0.4	
Bus440		33.000				0.005	0.003					0.006	85.0	0.1	
Bus441		33.000										0.007	18.5	0.1	

Project:	ETAP	Page:	11
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			Percent Loading
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus442		33.000			0.001	0.001			0.002	85.0	-	
Bus443		33.000			0.003	0.002			0.003	85.0	0.1	
Bus444		33.000			0.002	0.001			0.003	85.0	0.1	
Bus445		33.000			0.005	0.003			0.005	85.0	0.1	
Bus446		33.000			0.004	0.002			0.005	85.0	0.3	
Bus447		11.000			0.007	0.004			0.008	85.0	0.4	
Bus448		11.000			0.150	0.093			0.176	85.0	10.5	
Bus449		11.000		0.013	0.008	0.140	0.087		0.180	85.0	10.7	
Bus450		11.000		0.173	0.107	0.064	0.040		0.280	85.0	16.5	
Bus451		11.000		0.103	0.064	0.009	0.006		0.132	85.0	7.8	
Bus452		11.000		0.155	0.096	0.014	0.009		0.198	85.0	11.6	
Bus453		11.000		0.155	0.096	0.014	0.009		0.199	85.0	11.6	
Bus454		11.000		0.231	0.143	0.096	0.059		0.384	85.0	21.5	
Bus455		11.000		0.087	0.054	0.034	0.021		0.142	85.0	8.2	
Bus456		11.000		0.173	0.107	0.079	0.049		0.297	85.0	15.8	
Bus457		11.000		0.072	0.045	0.031	0.019		0.303	85.0	16.7	
Bus458		11.000		0.013	0.008	0.144	0.089		0.185	85.0	10.8	
Bus459		11.000		0.036	0.022	0.014	0.009		0.059	85.0	3.4	
Bus460		11.000		0.108	0.067	0.046	0.029		0.182	85.0	10.0	
Bus461		11.000		0.108	0.067	0.046	0.029		0.182	85.0	10.0	
Bus462		11.000		0.018	0.011	0.008	0.005		0.030	85.0	1.7	
Bus463		11.000		0.103	0.064	0.010	0.006		0.134	85.0	7.4	
Bus464		11.000		0.103	0.064	0.010	0.006		0.133	85.0	7.5	
Bus465		11.000		0.201	0.124	0.020	0.012		0.259	85.0	14.5	
Bus466		11.000		0.010	0.006	0.001	0.001		0.012	85.0	0.7	
Bus467		11.000		0.155	0.096	0.013	0.008		0.197	85.0	12.1	
Bus468		11.000		0.215	0.133				0.253	85.0	14.5	
RMU Helipad		11.000							1.394	85.0	76.6	
RMU MBC		11.000							1.140	85.0	65.1	
RMU Near Bridge		11.000							1.022	85.0	58.4	
Telecom RMU		11.000							2.624	85.7	149.7	

* Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:	ETAP	Page:	12
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Branch Loading Summary Report

CKT / Branch	Cable & Reactor			Transformer						
	ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input)	Loading (output)		
							MVA	%	MVA	%
Cable1		Cable	301.98	103.22	34.18					
Cable2		Cable	301.98	83.13	27.53					
Cable3		Cable	301.98	64.34	21.31					
Cable4		Cable	301.98	5.63	1.86					
Cable5		Cable	301.98	10.16	3.36					
Cable6		Cable	338.03	8.46	2.50					
Cable7		Cable	301.98	223.48	74.01					
Cable8		Cable	301.98	202.47	67.05					
Cable9		Cable	301.98	175.93	58.26					
Cable10		Cable	301.98	110.60	36.63					
Cable11		Cable	265.92	26.21	9.85					
Cable12		Cable	274.79	87.82	31.96					
Cable13		Cable	274.79	87.84	31.97					
Cable14		Cable	274.79	87.44	31.82					
Cable15		Cable	274.79	87.45	31.82					
Cable16		Cable	338.03	205.67	60.84					
Cable17		Cable	338.03	8.14	2.41					
Cable18		Cable	338.03	178.25	52.73					
Cable19		Cable	338.03	58.44	17.29					
Cable20		Cable	338.03	150.68	44.57					
Cable21		Cable	229.86							
Cable22		Cable	338.03	58.44	17.29					
Cable23		Cable	229.86	13.79	6.00					
Cable24		Cable	229.86	27.17	11.82					
Cable25		Cable	147.19	13.95	9.48					
Cable26		Cable	338.03	52.96	15.67					
Cable27		Cable	338.03	29.07	8.60					
Cable29		Cable	338.03	91.53	27.08					
Cable30		Cable	338.03	306.68	90.73					
Cable31		Cable	338.03	140.71	41.63					
Cable32		Cable	338.03	149.72	44.29					
Cable33		Cable	338.03	14.61	4.32					
Cable34		Cable	338.03	103.81	30.71					

Project:	ETAP	Page:	13
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

CKT / Branch		Cable & Reactor			Transformer			
ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input) MVA	Loading (output) MVA	
Cable35	Cable	229.86	19.77	8.60				
Cable36	Cable	229.86	12.09	5.26				
Cable37	Cable	338.03	65.15	19.27				
Cable38	Cable	229.86	50.69	22.05				
Cable40	Cable	301.98	76.58	25.36				
Cable41	Cable	338.03	76.59	22.66				
Cable42	Cable	338.03	23.21	6.87				
Cable43	Cable	338.03	28.80	8.52				
Cable44	Cable	338.03	14.90	4.41				
Cable45	Cable	338.03	24.58	7.27				
Cable46	Cable	229.86	8.29	3.61				
Cable47	Cable	338.03	149.72	44.29				
Cable48	Cable	229.86	12.20	5.31				
Cable49	Cable	229.86	12.20	5.31				
Cable50	Cable	229.86	125.32	54.52				
Cable51	Cable	229.86	13.60	5.92				
Cable52	Cable	301.98	8.08	2.68				
Cable53	Cable	301.98	23.46	7.77				
Cable54	Cable	338.03	334.64	99.00				
Cable55	Cable	229.86	7.47	3.25				
Cable56	Cable	147.19	0.98	0.66				
Cable57	Cable	301.98	20.02	6.63				
Cable58	Cable	301.98	17.34	5.74				
Cable59	Cable	229.86	19.89	8.65				
Cable60	Cable	301.98	190.18	62.98				
Cable61	Cable	338.03	97.16	28.74				
Cable62	Cable	261.41	6.37	2.44				
Cable63	Cable	338.03	258.19	76.38				
Cable64	Cable	229.86	13.56	5.90				
Cable65	Cable	338.03	309.06	91.43				
Cable66	Cable	338.03	22.88	6.77				
Cable67	Cable	338.03	29.09	8.61				
Cable68	Cable	301.98	10.46	3.46				
Cable69	Cable	301.98	10.67	3.53				
Cable70	Cable	301.98	16.53	5.48				

Project: **ETAP** Page: 14
 Location: 16.1.1C Date: 09-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESD Plng Config.: Normal

CKT / Branch		Cable & Reactor			Transformer				
ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input) MVA	Loading (output) MVA		
Cable71	Cable	229.86	7.76	3.38					
Cable72	Cable	301.98	11.64	3.85					
Cable73	Cable	301.98	11.58	3.83					
Cable74	Cable	301.98	21.53	7.13					
Cable75	Cable	229.86	8.16	3.55					
Cable76	Cable	301.98	15.83	5.24					
Cable77	Cable	229.86	16.72	7.28					
Cable78	Cable	301.98	10.81	3.58					
Cable79	Cable	229.86	3.40	1.48					
Cable80	Cable	301.98	10.03	3.32					
Cable81	Cable	301.98	10.03	3.32					
Cable82	Cable	229.86	7.40	3.22					
Cable83	Cable	229.86	7.45	3.24					
Cable84	Cable	301.98	14.48	4.80					
Cable85	Cable	301.98	12.07	4.00					
Cable86	Cable	301.98	14.46	4.79					
33/11kV Sector I SS	Transformer				5.000	4.863	97.3	4.635	92.7
33/11kV Sector II SS	Transformer				5.000	4.841	96.8	4.615	92.3
66/11kV (AREVA)	Transformer				5.000	4.472	89.4	4.308	86.2
66/11kV (VOLTAMP)	Transformer				10.000	7.349	73.5	7.080	70.8
66/11kV I	Transformer				20.000	5.746	28.7	5.661	28.3
66/11kV I (HYOSUNG)	Transformer				10.000	6.789	67.9	6.528	65.3
66/11kV II	Transformer				20.000	5.148	25.7	5.072	25.4
66/11kV II (HYOSUNG)	Transformer				10.000	6.789	67.9	6.528	65.3
66/33kV (AREVA)	Transformer				10.000	5.735	57.3	5.572	55.7
66/33kV (VOLTAMP)	Transformer				10.000	5.735	57.3	5.572	55.7

* Indicates a branch with operating load exceeding the branch capability.

Project:	ETAP	Page:	15
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Pling	Config.:	Normal

Branch Losses Summary Report

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
66/11kV (AREVA)	3.744	2.445	-3.720	-2.173	24.7	271.7	100.0	96.3	3.67
66/11kV (VOLTAMP)	6.038	4.190	-6.010	-3.743	28.0	447.4	100.0	96.3	3.67
66/33kV (AREVA)	4.689	3.301	-4.672	-3.036	16.6	265.9	100.0	97.2	2.84
66/33kV (VOLTAMP)	4.689	3.301	-4.672	-3.036	16.6	265.9	100.0	97.2	2.84
Cable1	1.617	0.988	-1.616	-0.987	0.4	0.2	96.3	96.3	0.02
Cable2	1.298	0.802	-1.298	-0.801	0.5	0.3	96.3	96.3	0.03
Cable6	0.132	0.082	-0.132	-0.082	0.0	0.0	96.3	96.3	0.00
Cable7	3.512	2.119	-3.510	-2.118	1.7	1.0	96.3	96.3	0.05
Cable10	1.745	1.037	-1.743	-1.036	1.9	1.1	96.3	96.2	0.10
Cable29	1.425	0.889	-1.425	-0.889	0.2	0.1	96.3	96.3	0.01
Line1	1.616	0.987	-1.607	-0.983	9.5	4.2	96.3	95.8	0.52
Line2	0.079	0.049	-0.079	-0.049	0.0	0.0	95.8	95.8	0.01
Line3	1.528	0.934	-1.519	-0.930	8.6	3.8	95.8	95.3	0.50
Line4	0.121	0.075	-0.121	-0.075	0.0	0.0	95.3	95.3	0.01
Line5	1.372	0.840	-1.369	-0.838	3.6	1.6	95.3	95.1	0.23
Line312	0.026	0.016	-0.026	-0.016	0.0	-0.1	95.3	95.3	0.01
Cable77	0.257	0.160	-0.257	-0.160	0.0	0.0	95.1	95.1	0.01
Cable81	0.154	0.096	-0.154	-0.096	0.0	0.0	95.1	95.1	0.01
Line6	0.706	0.427	-0.696	-0.423	9.8	3.8	95.1	93.8	1.23
Line7	0.679	0.413	-0.677	-0.412	2.3	0.9	93.8	93.5	0.29
Line8	0.066	0.041	-0.066	-0.041	0.0	-0.1	93.5	93.5	0.01
Line9	0.611	0.371	-0.610	-0.371	0.9	0.3	93.5	93.4	0.12
Line10	0.593	0.361	-0.593	-0.360	0.6	0.2	93.4	93.3	0.09
Line11	0.466	0.282	-0.465	-0.282	1.0	0.3	93.3	93.1	0.18
Line12	-0.015	-0.009	0.015	0.009	0.0	-0.2	93.1	93.1	0.01
Line13	0.450	0.272	-0.449	-0.272	0.9	0.3	93.1	93.0	0.17
Line14	-0.014	-0.009	0.014	0.008	0.0	-0.3	93.0	93.0	0.01
Line15	0.435	0.264	-0.435	-0.264	0.3	0.1	93.0	92.9	0.06
Line16	0.365	0.220	-0.364	-0.220	0.8	0.2	92.9	92.7	0.19
Line17	-0.014	-0.009	0.014	0.009	0.0	-0.1	92.7	92.7	0.01
Line18	0.349	0.211	-0.348	-0.211	1.9	0.4	92.7	92.3	0.47
Line19	-0.013	-0.008	0.013	0.008	0.0	-0.1	92.3	92.3	0.00
Line21	0.335	0.203	-0.334	-0.203	0.2	0.0	92.3	92.2	0.04
Line22	-0.020	-0.012	0.020	0.012	0.0	0.0	92.2	92.2	0.00

Project:	ETAP	Page:	16
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Plng		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line23	0.315	0.191	-0.314	-0.191	0.7	0.1	92.2	92.0	0.20
Line24	-0.012	-0.007	0.012	0.007	0.0	-0.3	92.0	92.0	0.01
Line25	0.302	0.184	-0.300	-0.183	2.2	0.3	92.0	91.4	0.63
Line26	-0.243	-0.150	0.244	0.150	1.1	0.0	91.0	91.4	0.37
Line27	0.056	0.033	-0.056	-0.033	0.0	-0.1	91.4	91.4	0.01
Line28	-0.034	-0.021	0.034	0.021	0.0	-0.4	91.3	91.4	0.04
Line29	0.022	0.012	-0.022	-0.012	0.0	-0.2	91.4	91.4	0.01
Line31	0.009	0.004	-0.009	-0.005	0.0	-0.3	91.4	91.4	0.01
Cable3	1.004	0.621	-1.004	-0.621	0.4	0.2	96.3	96.3	0.04
Line33	0.294	0.181	-0.294	-0.182	0.1	-1.3	96.3	96.3	0.03
Cable4	0.088	0.054	-0.088	-0.054	0.0	0.0	96.3	96.3	0.00
Line34	0.856	0.529	-0.855	-0.529	0.8	0.6	96.3	96.2	0.10
Cable5	0.158	0.098	-0.158	-0.098	0.0	0.0	96.2	96.2	0.00
Line35	0.557	0.344	-0.557	-0.344	0.2	0.1	96.2	96.1	0.04
Line36	0.266	0.164	-0.266	-0.165	0.0	-0.2	96.1	96.1	0.00
Line37	0.020	0.011	-0.020	-0.012	0.0	-1.3	96.1	96.1	0.00
Line208	-0.011	-0.007	0.011	0.005	0.0	-1.2	96.3	96.3	0.00
Cable8	3.183	1.915	-3.182	-1.914	1.0	0.6	96.3	96.3	0.03
Cable9	2.768	1.658	-2.767	-1.657	1.4	0.8	96.3	96.2	0.05
Line38	2.634	1.575	-2.616	-1.577	17.8	-2.1	96.2	95.7	0.49
Line39	0.477	0.292	-0.476	-0.293	0.1	-0.3	95.7	95.7	0.01
Line42	2.140	1.285	-2.132	-1.286	7.4	-1.4	95.7	95.5	0.25
Line40	0.353	0.216	-0.353	-0.218	0.3	-2.3	95.7	95.7	0.06
Line41	0.164	0.101	-0.164	-0.101	0.0	-0.1	95.7	95.7	0.00
Line43	0.262	0.162	-0.262	-0.163	0.0	-0.7	95.5	95.5	0.01
Line44	1.870	1.124	-1.860	-1.127	10.3	-2.7	95.5	95.1	0.40
Line45	1.443	0.869	-1.440	-0.871	3.5	-1.6	95.1	94.9	0.17
Line46	0.121	0.075	-0.121	-0.075	0.0	-0.7	94.9	94.9	0.01
Line363	0.845	0.503	-0.835	-0.517	10.3	-14.1	94.9	94.0	0.87
Line47	1.743	1.036	-1.733	-1.031	10.4	4.7	96.2	95.7	0.54
Line48	1.619	0.961	-1.601	-0.953	17.6	7.8	95.7	94.7	0.98
Cable82	0.114	0.070	-0.114	-0.070	0.0	0.0	94.7	94.7	0.00
Line20	1.488	0.883	-1.469	-0.874	18.6	8.2	94.7	93.6	1.11
Line50	-0.088	-0.055	0.088	0.055	0.0	-0.1	94.0	94.0	0.03
Line51	-0.339	-0.210	0.340	0.210	0.1	0.0	94.0	94.0	0.02
Line54	0.251	0.155	-0.251	-0.155	0.2	0.0	94.0	93.9	0.08
Line52	-0.116	-0.072	0.116	0.072	0.1	-0.1	94.0	94.0	0.04

Project:	ETAP	Page:	17
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Pling		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Cable84	0.221	0.137	-0.221	-0.137	0.0	0.0	94.0	94.0	0.02
Line53	0.159	0.098	-0.159	-0.098	0.0	0.0	94.0	94.0	0.01
Line55	-0.099	-0.061	0.099	0.061	0.1	-0.2	93.9	93.9	0.07
Cable83	0.113	0.070	-0.113	-0.070	0.0	0.0	93.9	93.9	0.00
Line56	0.021	0.010	-0.021	-0.011	0.0	-0.5	93.6	93.6	0.03
Line66	1.449	0.864	-1.446	-0.863	3.2	1.4	93.6	93.4	0.19
Line57	-0.019	-0.010	0.019	0.010	0.0	-0.1	93.6	93.6	0.01
Line58	0.015	0.008	-0.015	-0.008	0.0	-0.1	93.6	93.6	0.00
Line65	0.002	0.001	-0.002	-0.001	0.0	-0.5	93.6	93.6	0.00
Line59	0.004	0.002	-0.004	-0.002	0.0	0.0	93.6	93.6	0.00
Line60	0.011	0.006	-0.011	-0.006	0.0	0.0	93.6	93.6	0.00
Line61	0.009	0.005	-0.009	-0.005	0.0	-0.1	93.6	93.6	0.00
Line63	0.002	0.001	-0.002	-0.001	0.0	-0.5	93.6	93.6	0.00
Line62	0.005	0.003	-0.005	-0.003	0.0	-0.4	93.6	93.6	0.01
Line67	1.440	0.859	-1.416	-0.849	23.7	10.5	93.4	92.0	1.44
Line68	0.011	0.006	-0.011	-0.006	0.0	-0.1	92.0	92.0	0.00
Line72	1.406	0.843	-1.374	-0.829	31.9	14.1	92.0	90.0	1.96
Line69	0.006	0.003	-0.006	-0.003	0.0	-0.2	92.0	92.0	0.00
Line70	-0.003	-0.002	0.003	0.002	0.0	-0.1	92.0	92.0	0.00
Line71	0.003	0.002	-0.003	-0.002	0.0	-0.2	92.0	92.0	0.00
Line73	1.354	0.816	-1.335	-0.808	18.4	8.2	90.0	88.9	1.15
Line342	0.010	0.006	-0.010	-0.006	0.0	-0.1	90.0	90.0	0.00
Line74	-0.009	-0.006	0.009	0.006	0.0	0.0	88.9	88.9	0.00
Line75	0.004	0.002	-0.004	-0.002	0.0	-0.3	88.9	88.9	0.00
Line76	1.322	0.800	-1.276	-0.780	45.7	20.2	88.9	86.0	2.87
Line77	-0.067	-0.042	0.067	0.042	0.0	0.0	86.0	86.0	0.01
Line78	1.209	0.738	-1.206	-0.737	2.6	1.2	86.0	85.8	0.17
Line79	0.356	0.220	-0.356	-0.220	0.3	0.1	85.8	85.8	0.06
Line83	0.850	0.517	-0.846	-0.515	4.1	1.7	85.8	85.4	0.38
Line80	-0.124	-0.077	0.124	0.077	0.1	-0.1	85.7	85.8	0.04
Cable85	0.168	0.104	-0.168	-0.104	0.0	0.0	85.8	85.8	0.01
Line81	0.064	0.040	-0.064	-0.040	0.0	-0.2	85.8	85.7	0.05
Line85	0.831	0.506	-0.828	-0.505	2.9	1.2	85.4	85.2	0.28
Line87	0.660	0.400	-0.652	-0.397	7.3	3.0	85.2	84.3	0.88
Line88	-0.005	-0.003	0.005	0.003	0.0	-0.1	84.3	84.3	0.00
Line89	0.647	0.394	-0.644	-0.393	3.7	1.5	84.3	83.8	0.44
Line90	-0.009	-0.005	0.009	0.005	0.0	-0.1	83.8	83.8	0.00

Project:	ETAP	Page:	18
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line86	0.635	0.387	-0.626	-0.384	9.1	3.7	83.8	82.7	1.12
Line64	0.480	0.294	-0.476	-0.293	3.4	1.3	82.7	82.2	0.54
Line91	0.146	0.090	-0.146	-0.090	0.0	0.0	82.7	82.7	0.01
Line92	-0.126	-0.078	0.126	0.078	0.0	0.0	82.7	82.7	0.02
Line93	0.020	0.011	-0.020	-0.011	0.0	-0.1	82.7	82.7	0.01
Line94	-0.004	-0.002	0.004	0.002	0.0	-0.1	82.7	82.7	0.00
Line95	0.016	0.009	-0.016	-0.009	0.0	-0.1	82.7	82.7	0.01
Line96	-0.004	-0.003	0.004	0.003	0.0	-0.1	82.7	82.7	0.00
Line97	0.012	0.007	-0.012	-0.007	0.0	-0.2	82.7	82.7	0.01
Line98	0.009	0.005	-0.009	-0.005	0.0	-0.2	82.7	82.7	0.01
Line99	0.003	0.002	-0.003	-0.002	0.0	-0.3	82.7	82.7	0.00
Line82	-0.110	-0.068	0.110	0.068	0.0	0.0	82.2	82.2	0.00
Line84	0.366	0.225	-0.366	-0.224	0.4	0.1	82.2	82.1	0.08
Line100	-0.003	-0.002	0.003	0.002	0.0	-0.1	82.1	82.1	0.00
Line101	0.363	0.222	-0.362	-0.222	0.9	0.3	82.1	81.9	0.19
Line102	0.351	0.216	-0.350	-0.215	1.0	0.3	81.9	81.7	0.21
Line103	-0.103	-0.064	0.104	0.064	0.2	-0.2	81.6	81.7	0.13
Line104	0.246	0.151	-0.246	-0.151	0.3	0.0	81.7	81.6	0.09
Line105	-0.005	-0.003	0.005	0.003	0.0	-0.1	81.6	81.6	0.00
Line106	0.241	0.148	-0.240	-0.148	1.3	0.2	81.6	81.2	0.40
Line107	-0.236	-0.146	0.237	0.147	0.4	0.1	81.1	81.2	0.12
Line109	0.003	0.002	-0.003	-0.002	0.0	-0.3	81.2	81.2	0.00
Cable11	1.370	0.491	-1.369	-0.491	0.9	0.0	97.2	97.1	0.05
Cable12	3.995	2.797	-3.985	-2.797	10.5	0.0	97.2	97.0	0.17
Cable14	3.979	2.783	-3.969	-2.783	10.6	0.0	97.2	97.0	0.17
Line108	1.369	0.491	-1.365	-0.504	4.0	-12.8	97.1	96.8	0.32
Line110	0.581	0.269	-0.580	-0.271	0.1	-1.2	96.8	96.8	0.01
Line111	0.785	0.234	-0.784	-0.240	0.5	-5.8	96.8	96.7	0.07
Line112	0.342	0.209	-0.342	-0.212	0.1	-3.3	96.8	96.8	0.02
Line113	0.238	0.062	-0.238	-0.066	0.0	-4.0	96.8	96.8	0.01
Line114	0.208	0.047	-0.208	-0.049	0.0	-1.8	96.8	96.8	0.01
Line115	-0.017	-0.010	0.017	0.009	0.0	-1.4	96.8	96.8	0.00
Line116	0.191	0.040	-0.191	-0.042	0.0	-1.8	96.8	96.7	0.00
Line117	-0.031	-0.019	0.031	0.019	0.0	-0.2	96.7	96.7	0.00
Line118	0.161	0.023	-0.161	-0.028	0.0	-4.8	96.7	96.7	0.01
Line119	0.144	0.017	-0.144	-0.018	0.0	-0.5	96.7	96.7	0.00
Line120	0.051	0.007	-0.051	-0.011	0.0	-4.6	96.7	96.7	0.00

Project:	ETAP	Page:	19
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line128	0.093	0.011	-0.093	-0.014	0.0	-3.3	96.7	96.7	0.00
Line121	0.047	0.009	-0.047	-0.018	0.0	-9.8	96.7	96.7	0.01
Line122	0.000	0.000	0.000	-0.001	0.0	-0.6	96.7	96.7	0.00
Line123	0.047	0.019	-0.047	-0.021	0.0	-1.7	96.7	96.7	0.00
Line126	0.030	0.010	-0.030	-0.011	0.0	-1.2	96.7	96.7	0.00
Line124	0.017	0.005	-0.017	-0.005	0.0	-0.1	96.7	96.7	0.00
Line125	0.012	0.006	-0.012	-0.008	0.0	-1.1	96.7	96.7	0.00
Line127	0.003	-0.004	-0.003	-0.002	0.0	-5.7	96.7	96.7	0.00
Line129	-0.013	-0.008	0.013	0.006	0.0	-2.7	96.7	96.7	0.00
Line130	0.080	0.009	-0.080	-0.012	0.0	-3.2	96.7	96.7	0.00
Line131	0.068	0.005	-0.068	-0.009	0.0	-4.0	96.7	96.7	0.00
Line132	0.057	0.002	-0.057	-0.006	0.0	-3.7	96.7	96.7	0.00
Line133	0.043	-0.003	-0.043	0.002	0.0	-1.2	96.7	96.7	0.00
Line134	0.032	-0.009	-0.032	0.007	0.0	-1.8	96.7	96.7	0.00
Line135	0.022	-0.013	-0.022	0.003	0.0	-9.2	96.7	96.7	0.00
Line136	0.013	-0.009	-0.013	0.002	0.0	-6.9	96.7	96.7	0.00
Line137	0.011	-0.004	-0.011	0.000	0.0	-3.8	96.7	96.7	0.00
Line138	-0.008	-0.005	0.008	0.001	0.0	-4.4	96.7	96.7	0.00
Line139	0.003	-0.001	-0.003	-0.002	0.0	-2.2	96.7	96.7	0.00
Line140	0.774	0.234	-0.773	-0.237	0.2	-3.0	96.7	96.7	0.04
Line141	0.765	0.232	-0.765	-0.233	0.1	-0.9	96.7	96.7	0.01
Line142	0.012	0.005	-0.012	-0.007	0.0	-1.6	96.7	96.7	0.00
Line144	0.753	0.228	-0.753	-0.231	0.2	-2.9	96.7	96.6	0.03
Line143	0.004	0.001	-0.004	-0.002	0.0	-0.9	96.7	96.7	0.00
Line145	0.742	0.224	-0.742	-0.227	0.2	-3.2	96.6	96.6	0.04
Line146	0.733	0.221	-0.732	-0.222	0.1	-0.8	96.6	96.6	0.01
Line147	0.068	0.028	-0.068	-0.029	0.0	-1.0	96.6	96.6	0.00
Line156	0.664	0.194	-0.664	-0.196	0.1	-2.0	96.6	96.6	0.02
Line148	0.045	0.019	-0.045	-0.024	0.0	-4.7	96.6	96.6	0.01
Line152	0.024	0.010	-0.024	-0.012	0.0	-1.1	96.6	96.6	0.00
Line149	0.030	0.015	-0.030	-0.016	0.0	-1.1	96.6	96.6	0.00
Line153	0.021	0.010	-0.021	-0.012	0.0	-1.8	96.6	96.6	0.00
Line154	0.010	0.006	-0.010	-0.006	0.0	-0.8	96.6	96.6	0.00
Line155	0.011	0.006	-0.011	-0.007	0.0	-0.7	96.6	96.6	0.00
Line157	0.049	0.010	-0.049	-0.011	0.0	-1.2	96.6	96.6	0.00
Line167	0.615	0.186	-0.615	-0.187	0.0	-0.7	96.6	96.6	0.01
Line158	0.041	0.008	-0.041	-0.008	0.0	-0.6	96.6	96.6	0.00

Project:	ETAP	Page:	20
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line159	0.008	0.003	-0.008	-0.004	0.0	-0.5	96.6	96.6	0.00
Line161	-0.014	-0.009	0.014	0.008	0.0	-0.5	96.6	96.6	0.00
Line162	0.027	0.000	-0.027	-0.001	0.0	-1.3	96.6	96.6	0.00
Line163	0.015	-0.005	-0.015	-0.004	0.0	-8.3	96.6	96.6	0.00
Line166	0.012	0.006	-0.012	-0.007	0.0	-1.4	96.6	96.6	0.00
Line164	0.012	0.002	-0.012	-0.004	0.0	-2.3	96.6	96.6	0.00
Line165	-0.010	-0.006	0.010	0.003	0.0	-3.2	96.6	96.6	0.00
Line168	0.597	0.176	-0.597	-0.177	0.1	-1.3	96.6	96.6	0.01
Line169	0.014	0.008	-0.014	-0.009	0.0	-0.8	96.6	96.6	0.00
Line171	0.000	-0.001	0.000	0.000	0.0	-1.1	96.6	96.6	0.00
Line172	0.583	0.170	-0.583	-0.170	0.0	-0.4	96.6	96.5	0.00
Line173	0.571	0.163	-0.570	-0.168	0.2	-5.1	96.5	96.5	0.04
Line174	0.567	0.166	-0.567	-0.172	0.2	-5.7	96.5	96.5	0.05
Line175	0.554	0.164	-0.554	-0.165	0.1	-1.6	96.5	96.4	0.01
Line176	0.540	0.156	-0.539	-0.163	0.3	-6.9	96.4	96.4	0.05
Line177	0.524	0.154	-0.524	-0.155	0.0	-0.7	96.4	96.4	0.01
Line178	0.242	0.072	-0.242	-0.074	0.0	-1.4	96.4	96.4	0.00
Line199	0.283	0.082	-0.283	-0.083	0.0	-0.6	96.4	96.4	0.00
Line179	0.228	0.066	-0.228	-0.071	0.0	-5.5	96.4	96.4	0.02
Line180	0.199	0.053	-0.199	-0.054	0.0	-0.5	96.4	96.4	0.00
Line181	0.119	0.021	-0.118	-0.027	0.0	-5.4	96.4	96.4	0.01
Line186	0.081	0.032	-0.081	-0.034	0.0	-1.7	96.4	96.4	0.00
Line182	0.102	0.017	-0.102	-0.018	0.0	-1.5	96.4	96.3	0.00
Line183	0.000	0.000	0.000	-0.001	0.0	-1.1	96.3	96.3	0.00
Line184	0.102	0.019	-0.102	-0.022	0.0	-2.3	96.3	96.3	0.00
Line185	-0.026	-0.016	0.026	0.012	0.0	-4.1	96.3	96.3	0.00
Line192	0.076	0.009	-0.076	-0.011	0.0	-1.4	96.3	96.3	0.00
Line187	0.067	0.025	-0.067	-0.030	0.0	-4.1	96.4	96.3	0.01
Line188	0.036	0.010	-0.036	-0.012	0.0	-1.6	96.3	96.3	0.00
Line189	0.001	-0.010	-0.001	0.007	0.0	-2.4	96.3	96.3	0.00
Line193	0.042	-0.010	-0.042	0.003	0.0	-6.5	96.3	96.3	0.01
Line194	0.028	-0.009	-0.028	0.005	0.0	-3.6	96.3	96.3	0.00
Line197	0.014	0.005	-0.014	-0.006	0.0	-0.6	96.3	96.3	0.00
Line195	0.020	-0.010	-0.020	-0.002	0.0	-11.6	96.3	96.3	0.01
Line196	0.012	-0.003	-0.012	-0.007	0.0	-10.7	96.3	96.3	0.00
Line198	0.009	0.003	-0.009	-0.006	0.0	-3.2	96.3	96.3	0.00
Line200	0.278	0.080	-0.278	-0.084	0.0	-3.6	96.4	96.4	0.01

Project:	ETAP	Page:	21
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Pling		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line201	0.261	0.073	-0.261	-0.074	0.0	-0.8	96.4	96.4	0.00
Line202	0.248	0.065	-0.248	-0.067	0.0	-1.3	96.4	96.4	0.00
Line203	-0.011	-0.007	0.011	0.006	0.0	-0.7	96.4	96.4	0.00
Line204	0.237	0.061	-0.237	-0.063	0.0	-2.2	96.4	96.4	0.01
Line205	0.225	0.056	-0.225	-0.056	0.0	-0.2	96.4	96.4	0.00
Line206	0.037	0.018	-0.037	-0.019	0.0	-0.4	96.4	96.4	0.00
Line210	0.188	0.038	-0.188	-0.042	0.0	-3.8	96.4	96.3	0.01
Line207	0.033	0.016	-0.033	-0.018	0.0	-2.2	96.4	96.3	0.00
Line170	0.022	0.011	-0.022	-0.011	0.0	-0.2	96.3	96.3	0.00
Line209	0.011	0.006	-0.011	-0.007	0.0	-0.8	96.3	96.3	0.00
Line229	-3.595	-2.232	3.637	2.268	41.4	35.1	92.3	93.5	1.17
Line243	3.498	2.172	-3.490	-2.165	7.9	6.7	92.3	92.1	0.23
Line211	0.002	0.001	-0.002	-0.001	0.0	-0.5	96.3	96.3	0.00
Line212	0.186	0.041	-0.186	-0.046	0.0	-5.3	96.3	96.3	0.01
Line213	-0.011	-0.007	0.011	0.005	0.0	-1.3	96.3	96.3	0.00
Line214	0.175	0.041	-0.175	-0.043	0.0	-1.8	96.3	96.3	0.00
Line215	0.168	0.038	-0.168	-0.043	0.0	-4.7	96.3	96.3	0.02
Line216	0.153	0.033	-0.153	-0.035	0.0	-1.9	96.3	96.3	0.01
Line217	-0.014	-0.009	0.014	0.008	0.0	-0.4	96.3	96.3	0.00
Line218	0.086	0.017	-0.086	-0.019	0.0	-1.3	96.3	96.3	0.00
Line233	0.053	0.009	-0.053	-0.010	0.0	-0.7	96.3	96.3	0.00
Line219	0.077	0.013	-0.077	-0.016	0.0	-2.2	96.3	96.3	0.00
Line220	-0.010	-0.006	0.010	0.006	0.0	-0.3	96.3	96.3	0.00
Line221	0.068	0.010	-0.067	-0.016	0.0	-6.3	96.3	96.3	0.01
Line222	-0.013	-0.008	0.013	0.008	0.0	-0.5	96.3	96.3	0.00
Line223	0.054	0.008	-0.054	-0.009	0.0	-0.8	96.3	96.3	0.00
Line224	0.021	0.008	-0.021	-0.009	0.0	-0.5	96.3	96.3	0.00
Line226	0.033	0.001	-0.033	-0.002	0.0	-0.6	96.3	96.3	0.00
Line225	0.010	0.002	-0.010	-0.006	0.0	-4.6	96.3	96.3	0.00
Line227	0.013	-0.002	-0.013	0.002	0.0	-0.2	96.3	96.3	0.00
Line230	0.020	0.004	-0.020	-0.006	0.0	-2.1	96.3	96.3	0.00
Line228	0.005	-0.007	-0.005	-0.003	0.0	-9.9	96.3	96.3	0.00
Line231	0.012	0.001	-0.012	-0.004	0.0	-3.8	96.3	96.3	0.00
Line232	0.005	0.000	-0.005	-0.003	0.0	-2.9	96.3	96.3	0.00
Line234	0.038	0.001	-0.038	-0.004	0.0	-2.8	96.3	96.3	0.00
Line235	0.026	-0.003	-0.026	0.003	0.0	-0.6	96.3	96.3	0.00
Line236	-0.009	-0.005	0.009	0.005	0.0	-0.4	96.3	96.3	0.00

Project:	ETAP	Page:	22
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Plng		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line237	0.018	-0.008	-0.018	-0.007	0.0	-14.7	96.3	96.3	0.01
Line238	0.010	0.002	-0.010	-0.006	0.0	-4.1	96.3	96.3	0.00
Line239	3.985	2.797	-3.981	-2.795	3.6	1.8	97.0	96.9	0.09
Cable13	3.981	2.795	-3.979	-2.795	2.4	0.0	96.9	96.9	0.04
33/11kV Sector I SS	3.979	2.795	-3.949	-2.427	29.5	368.9	96.9	92.3	4.53
Line240	3.969	2.783	-3.965	-2.781	3.7	1.8	97.0	96.9	0.10
Cable15	3.965	2.781	-3.963	-2.781	2.3	0.0	96.9	96.9	0.04
33/11kV Sector II SS	3.963	2.781	-3.933	-2.414	29.4	367.1	96.9	92.3	4.53
Cable16	3.075	1.907	-3.066	-1.901	8.4	5.9	92.3	92.1	0.26
Cable30	4.605	2.811	-4.594	-2.803	10.9	7.7	92.3	92.1	0.23
Line254	0.203	0.123	-0.203	-0.126	0.1	-3.1	92.3	92.3	0.05
Cable17	0.121	0.075	-0.121	-0.075	0.0	0.0	92.1	92.1	0.01
Cable18	2.657	1.647	-2.652	-1.644	5.5	3.9	92.1	91.9	0.20
Cable20	2.242	1.389	-2.242	-1.389	0.1	0.1	91.9	91.9	0.00
Cable19	0.869	0.539	-0.869	-0.539	0.4	0.3	91.9	91.8	0.04
Cable26	0.788	0.488	-0.787	-0.488	0.4	0.3	91.9	91.8	0.05
Cable21	0.000	0.000	0.000	0.000			91.8	91.8	
Cable22	-0.869	-0.538	0.869	0.539	0.5	0.4	91.8	91.8	0.06
Cable23	0.205	0.127	-0.205	-0.127	0.0	0.0	91.8	91.8	0.01
Cable24	0.404	0.250	-0.404	-0.250	0.3	0.1	91.8	91.7	0.05
Cable25	0.207	0.128	-0.207	-0.128	0.1	0.0	91.7	91.7	0.03
Cable27	0.432	0.268	-0.432	-0.268	0.1	0.1	91.8	91.8	0.02
Line241	1.425	0.889	-1.422	-0.884	3.2	4.9	96.3	96.0	0.31
Line246	1.189	0.740	-1.187	-0.736	2.3	3.5	96.0	95.7	0.27
Cable31	2.099	1.301	-2.096	-1.299	2.9	2.1	92.1	92.0	0.13
Cable32	2.253	1.352	-2.250	-1.350	2.6	1.8	92.1	92.0	0.11
Cable33	0.218	0.135	-0.218	-0.135	0.0	0.0	92.0	92.0	0.00
Cable34	1.546	0.958	-1.546	-0.958	0.4	0.3	92.0	91.9	0.02
Line242	0.105	0.065	-0.105	-0.065	0.0	0.0	92.0	92.0	0.01
Line244	0.113	0.070	-0.113	-0.070	0.0	0.0	92.0	92.0	0.01
Cable35	0.294	0.182	-0.294	-0.182	0.0	0.0	91.9	91.9	0.01
Cable37	0.970	0.601	-0.969	-0.600	1.1	0.8	91.9	91.8	0.11
Cable36	0.180	0.112	-0.180	-0.112	0.0	0.0	91.9	91.9	0.00
Cable38	-0.754	-0.467	0.754	0.467	0.0	0.0	91.8	91.8	0.00
Cable40	1.187	0.736	-1.187	-0.736	0.2	0.1	95.7	95.7	0.01
Line245	1.187	0.736	-1.185	-0.734	1.5	2.2	95.7	95.6	0.17
Cable41	1.185	0.734	-1.185	-0.734	0.0	0.0	95.6	95.5	0.00

Project:	ETAP	Page:	23
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Plng		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Cable42	-0.359	-0.223	0.359	0.223	0.0	0.0	95.5	95.5	0.00
Cable43	-0.446	-0.276	0.446	0.276	0.1	0.0	95.5	95.5	0.01
Cable44	0.231	0.143	-0.231	-0.143	0.0	0.0	95.5	95.5	0.01
Cable45	-0.381	-0.235	0.381	0.235	0.1	0.1	95.5	95.5	0.02
Cable46	0.128	0.079	-0.128	-0.079	0.0	0.0	95.5	95.5	0.00
Line248	0.135	0.083	-0.135	-0.084	0.0	-0.6	95.5	95.5	0.01
Line247	0.078	0.048	-0.078	-0.048	0.0	0.0	95.5	95.5	0.01
Cable47	2.250	1.350	-2.250	-1.350	0.2	0.1	92.0	92.0	0.01
Cable48	-0.182	-0.113	0.182	0.113	0.0	0.0	92.0	92.0	0.01
Cable49	-0.182	-0.113	0.182	0.113	0.0	0.0	92.0	92.0	0.01
Cable50	-1.882	-1.123	1.886	1.125	4.3	1.7	91.8	92.0	0.19
Line249	1.653	0.981	-1.641	-0.985	11.8	-3.4	91.8	91.3	0.49
Cable75	0.121	0.075	-0.121	-0.075	0.0	0.0	91.3	91.3	0.00
Line250	1.248	0.754	-1.230	-0.763	17.4	-8.9	91.3	90.3	0.95
Line251	0.272	0.156	-0.272	-0.164	0.6	-7.6	91.3	91.1	0.16
Line294	1.050	0.651	-1.048	-0.650	1.3	1.1	90.3	90.2	0.13
Cable79	0.050	0.031	-0.050	-0.031	0.0	0.0	91.1	91.1	0.00
Line252	0.015	0.005	-0.015	-0.009	0.0	-4.3	91.1	91.1	0.01
Line253	0.111	0.068	-0.111	-0.069	0.0	-0.5	91.1	91.1	0.00
Cable51	0.203	0.126	-0.203	-0.126	0.0	0.0	92.3	92.3	0.01
66/11kV I	4.927	2.956	-4.920	-2.801	7.4	154.8	100.0	98.5	1.47
66/11kV II	4.415	2.648	-4.408	-2.509	6.6	138.7	100.0	98.5	1.47
Cable52	0.129	0.079	-0.129	-0.079	0.0	0.0	98.5	98.5	0.00
Cable53	0.374	0.232	-0.374	-0.232	0.1	0.0	98.5	98.5	0.02
Cable54	5.556	2.932	-5.546	-2.924	10.2	7.2	98.5	98.3	0.19
Cable60	3.016	1.911	-3.012	-1.909	4.1	2.4	98.5	98.4	0.13
Cable76	0.253	0.157	-0.253	-0.157	0.0	0.0	98.5	98.5	0.01
Line255	0.129	0.079	-0.129	-0.079	0.0	-0.1	98.5	98.5	0.03
Line256	0.032	0.020	-0.032	-0.020	0.0	-0.4	98.5	98.5	0.03
Line257	0.097	0.060	-0.097	-0.060	0.0	-0.1	98.5	98.5	0.02
Line258	0.036	0.022	-0.036	-0.023	0.0	-0.4	98.5	98.4	0.03
Line260	-0.374	-0.232	0.374	0.232	0.3	0.0	98.4	98.5	0.07
Line262	5.546	2.924	-5.420	-2.750	126.0	174.6	98.3	95.3	3.02
Line263	0.442	-0.368	-0.442	0.368	0.4	0.3	95.3	95.3	0.01
Line265	4.978	3.117	-4.938	-3.083	40.1	34.0	95.3	94.5	0.84
Line264	0.442	-0.368	-0.442	0.368	0.1	0.0	95.3	95.3	0.00
Line266	-0.288	-0.179	0.288	0.179	0.0	0.0	94.5	94.5	0.01

Project:	ETAP	Page:	24
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Pling	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line267	0.102	0.063	-0.102	-0.064	0.0	0.0	94.5	94.5	0.01
Line268	4.547	2.841	-4.531	-2.828	16.0	13.5	94.5	94.1	0.37
Line269	4.441	2.772	-4.425	-2.758	16.2	13.7	94.1	93.7	0.38
Cable74	0.327	0.203	-0.327	-0.202	0.1	0.0	93.7	93.7	0.02
Line270	4.043	2.522	-4.032	-2.513	10.7	9.1	93.7	93.5	0.27
Line271	-0.395	-0.245	0.395	0.245	0.1	0.0	93.4	93.5	0.03
Line259	2.953	1.832	-2.945	-1.825	8.2	6.9	92.1	91.8	0.28
Line261	2.890	1.792	-2.877	-1.781	12.8	10.8	91.8	91.3	0.45
Line272	0.075	0.042	-0.075	-0.042	0.0	-0.1	91.3	91.3	0.01
Line274	2.786	1.729	-2.754	-1.702	32.2	27.2	91.3	90.2	1.16
Line273	0.016	0.005	-0.016	-0.010	0.0	-4.6	91.3	91.3	0.00
Line275	0.416	0.258	-0.416	-0.258	0.4	0.2	90.2	90.1	0.10
Line276	2.338	1.444	-2.326	-1.434	12.6	10.6	90.2	89.6	0.54
Cable55	0.109	0.067	-0.109	-0.067	0.0	0.0	90.1	90.0	0.02
Cable73	0.169	0.105	-0.169	-0.105	0.0	0.0	90.1	90.0	0.01
Cable56	-0.014	-0.009	0.014	0.009	0.0	0.0	89.6	89.6	0.00
Line278	2.311	1.425	-2.309	-1.423	2.3	1.9	89.6	89.5	0.10
Cable71	0.112	0.070	-0.112	-0.070	0.0	0.0	89.5	89.5	0.00
Cable72	0.169	0.105	-0.169	-0.105	0.0	0.0	89.5	89.5	0.01
Line279	0.050	0.031	-0.050	-0.031	0.0	-0.2	89.5	89.5	0.03
Line281	1.978	1.218	-1.964	-1.206	14.4	12.0	89.5	88.8	0.72
Line280	0.035	0.021	-0.035	-0.021	0.0	0.0	89.5	89.5	0.00
Line282	-0.183	-0.113	0.183	0.113	0.0	0.0	88.8	88.8	0.01
Cable70	0.238	0.147	-0.238	-0.147	0.1	0.0	88.8	88.8	0.02
Line283	0.555	0.344	-0.555	-0.344	0.0	0.0	88.8	88.8	0.01
Line284	0.804	0.487	-0.803	-0.487	1.0	0.8	88.8	88.7	0.12
Line285	-0.135	-0.084	0.135	0.073	0.1	-10.9	88.6	88.7	0.06
Cable69	0.153	0.095	-0.153	-0.095	0.0	0.0	88.7	88.7	0.02
Line286	0.515	0.319	-0.514	-0.318	0.7	0.5	88.7	88.5	0.14
Line287	-0.200	-0.124	0.200	0.124	0.0	0.0	88.5	88.5	0.02
Cable68	0.150	0.093	-0.150	-0.093	0.0	0.0	88.5	88.5	0.01
Line288	0.164	0.102	-0.164	-0.102	0.1	-0.1	88.5	88.5	0.03
Line289	-0.164	-0.102	0.164	0.102	0.0	0.0	88.5	88.5	0.01
Cable59	0.290	0.180	-0.290	-0.180	0.0	0.0	90.0	90.0	0.01
Line291	0.545	0.338	-0.545	-0.338	0.1	0.1	90.0	90.0	0.02
Line292	-0.835	-0.517	0.836	0.519	1.6	1.3	90.0	90.2	0.20
Cable57	0.292	0.181	-0.292	-0.181	0.0	0.0	90.0	90.0	0.01

Project:	ETAP	Page:	25
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Cable58	0.253	0.157	-0.253	-0.157	0.0	0.0	90.0	90.0	0.02
Cable78	0.158	0.098	-0.158	-0.098	0.0	0.0	90.1	90.1	0.01
Line293	-0.212	-0.131	0.212	0.131	0.4	-0.1	90.1	90.2	0.16
Line295	3.012	1.909	-2.956	-1.832	55.9	76.9	98.4	96.0	2.45
66/11kV I (HYOSUNG)	5.383	4.137	-5.356	-3.731	26.9	406.1	100.0	96.1	3.85
66/11kV II (HYOSUNG)	5.383	4.137	-5.356	-3.731	26.9	406.1	100.0	96.1	3.85
Cable61	1.156	1.353	-1.156	-1.353	0.3	0.2	96.1	96.1	0.02
Cable63	4.013	2.503	-4.010	-2.501	2.6	1.9	96.1	96.1	0.07
Cable65	4.731	3.109	-4.727	-3.106	3.9	2.8	96.1	96.1	0.08
Cable66	0.356	0.220	-0.356	-0.220	0.0	0.0	96.1	96.1	0.00
Cable67	0.456	0.276	-0.456	-0.276	0.0	0.0	96.1	96.1	0.01
Line296	1.156	1.353	-1.146	-1.348	10.2	4.5	96.1	95.6	0.55
Line297	0.131	0.722	-0.128	-0.721	2.7	1.0	95.6	95.4	0.22
Line300	1.015	0.627	-1.013	-0.626	2.4	1.0	95.6	95.4	0.21
Line298	0.095	0.700	-0.094	-0.700	0.4	0.2	95.4	95.3	0.03
Line299	0.536	0.332	-0.535	-0.332	0.3	0.1	95.3	95.3	0.06
Line301	0.924	0.570	-0.917	-0.568	7.1	2.9	95.4	94.7	0.68
Line302	0.459	0.284	-0.459	-0.284	0.1	0.0	94.7	94.7	0.01
Line304	0.458	0.283	-0.458	-0.283	0.4	0.1	94.7	94.6	0.07
Line303	0.406	0.251	-0.405	-0.251	0.4	0.1	94.7	94.6	0.08
Line305	0.361	0.224	-0.361	-0.223	0.4	0.1	94.6	94.5	0.09
Line277	0.269	0.167	-0.269	-0.167	0.1	0.0	94.5	94.5	0.03
Line306	0.185	0.114	-0.185	-0.114	0.0	0.0	94.5	94.5	0.02
Line307	0.185	0.114	-0.184	-0.114	0.1	0.0	94.5	94.4	0.04
Cable62	0.097	0.060	-0.097	-0.060	0.0	0.0	94.4	94.4	0.00
Line308	4.010	2.501	-3.936	-2.398	74.6	103.2	96.1	93.7	2.40
Line309	3.916	2.386	-3.910	-2.377	6.1	8.4	93.7	93.5	0.20
Line310	0.008	0.005	-0.008	-0.005	0.0	0.0	93.5	93.5	0.00
Line311	3.902	2.373	-3.900	-2.369	2.4	3.3	93.5	93.4	0.08
Cable64	-0.205	-0.127	0.205	0.127	0.0	0.0	93.4	93.4	0.00
Line313	3.694	2.242	-3.690	-2.235	4.9	6.7	93.4	93.2	0.17
Line314	3.651	2.212	-3.648	-2.207	3.4	4.7	93.2	93.1	0.12
Line315	3.570	2.159	-3.561	-2.147	9.0	12.4	93.1	92.8	0.32
Line316	3.522	2.122	-3.517	-2.116	4.2	5.7	92.8	92.7	0.15
Line317	-1.148	-0.712	1.149	0.712	0.4	0.2	92.6	92.7	0.03
Line318	2.369	1.404	-2.355	-1.393	14.0	11.7	92.7	92.1	0.61
Line319	0.388	0.174	-0.388	-0.174	0.1	0.1	92.1	92.0	0.03

Project:	ETAP	Page:	26
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Plng		Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line320	4.727	3.106	-4.593	-2.920	134.1	185.7	96.1	92.4	3.63
Line321	3.102	1.996	-3.098	-1.991	3.9	5.4	92.4	92.3	0.16
Line322	2.774	1.790	-2.769	-1.783	5.2	7.2	92.3	92.0	0.23
Line323	1.043	0.647	-1.043	-0.646	0.3	0.4	92.0	92.0	0.04
Line324	1.725	1.136	-1.725	-1.135	0.4	0.5	92.0	92.0	0.03
Line325	0.366	0.293	-0.366	-0.293	0.1	0.0	92.0	92.0	0.02
Line326	0.350	0.284	-0.350	-0.283	0.1	0.0	92.0	92.0	0.02
Line327	-0.324	-0.201	0.324	0.201	0.1	0.0	92.0	92.0	0.02
Line328	0.027	0.083	-0.027	-0.083	0.0	-0.1	92.0	92.0	0.01
Line329	-0.207	-0.062	0.207	0.062	0.1	-0.1	92.0	92.0	0.03
Line330	-0.219	-0.069	0.219	0.069	0.0	0.0	92.0	92.0	0.01
Line331	-0.241	-0.083	0.241	0.083	0.0	0.0	92.0	92.0	0.01
Line332	-0.121	-0.075	0.121	0.075	0.0	0.0	92.0	92.0	0.00
Line333	0.025	0.016	-0.025	-0.016	0.0	0.0	92.0	92.0	0.00
Line334	0.000	0.000	0.000	0.000	0.0	0.0	92.0	92.0	0.00
Line335	0.356	0.220	-0.356	-0.220	0.0	0.0	96.1	96.1	0.01
Line336	0.249	0.154	-0.249	-0.154	0.2	-0.1	96.1	96.1	0.07
Line337	0.107	0.066	-0.107	-0.067	0.0	-0.1	96.1	96.1	0.02
Line338	0.054	0.033	-0.054	-0.033	0.0	-0.1	96.1	96.1	0.01
Line339	0.456	0.276	-0.454	-0.275	2.2	0.6	96.1	95.7	0.44
Line340	0.411	0.249	-0.410	-0.249	1.2	0.3	95.7	95.4	0.26
Line341	0.034	0.019	-0.034	-0.020	0.0	-0.6	95.4	95.4	0.06
Line348	0.376	0.230	-0.376	-0.230	0.1	0.0	95.4	95.4	0.03
Line343	0.000	0.000	0.000	0.000	0.0	0.0	95.4	95.4	0.00
Line344	0.034	0.020	-0.034	-0.020	0.0	-0.4	95.4	95.3	0.03
Line345	-0.021	-0.013	0.021	0.013	0.0	0.0	95.3	95.3	0.00
Line346	0.013	0.007	-0.013	-0.007	0.0	-0.4	95.3	95.3	0.01
Line347	0.006	0.003	-0.006	-0.004	0.0	-0.5	95.3	95.3	0.01
Line349	0.037	0.023	-0.037	-0.023	0.0	-0.1	95.4	95.4	0.01
Line350	0.339	0.207	-0.337	-0.207	1.6	0.3	95.4	95.0	0.43
Line351	0.178	0.109	-0.177	-0.109	0.3	-0.2	95.0	94.8	0.14
Line355	0.160	0.098	-0.160	-0.098	0.0	0.0	95.0	95.0	0.01
Line352	0.004	0.002	-0.004	-0.002	0.0	-0.3	94.8	94.8	0.00
Line353	0.173	0.107	-0.173	-0.107	0.2	-0.1	94.8	94.7	0.09
Line354	0.150	0.092	-0.149	-0.093	0.1	-0.1	94.7	94.7	0.08
Line356	0.035	0.021	-0.035	-0.021	0.0	-0.4	95.0	94.9	0.04
Line358	0.032	0.019	-0.032	-0.019	0.0	-0.1	94.9	94.9	0.01

Project: **ETAP** Page: 27
 Location: **16.1.1C** Date: 09-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESD Plng Config.: Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line359	0.022	0.013	-0.022	-0.013	0.0	-0.2	94.9	94.9	0.01
Line360	0.007	0.004	-0.007	-0.004	0.0	0.0	94.9	94.9	0.00
Line361	0.016	0.009	-0.016	-0.009	0.0	-0.2	94.9	94.9	0.01
Line362	0.009	0.005	-0.009	-0.005	0.0	-0.3	94.9	94.9	0.01
Line30	0.004	0.001	-0.004	-0.002	0.0	-0.9	91.4	91.3	0.01
Line32	0.005	0.003	-0.005	-0.003	0.0	0.0	91.4	91.4	0.00
Line160	0.003	0.001	-0.003	-0.002	0.0	-1.4	96.6	96.6	0.00
Line150	0.017	0.008	-0.017	-0.009	0.0	-1.8	96.6	96.6	0.00
Line151	0.005	0.002	-0.005	-0.003	0.0	-1.1	96.6	96.6	0.00
Line190	0.001	-0.003	-0.001	-0.001	0.0	-4.2	96.3	96.3	0.00
Line191	0.000	-0.004	0.000	0.000	0.0	-3.8	96.3	96.3	0.00
Cable80	0.154	0.096	-0.154	-0.096	0.0	0.0	95.1	95.0	0.01
Cable86	-0.215	-0.133	0.215	0.133	0.0	0.0	91.8	91.8	0.01
					1358.4	3621.5			

Project:	ETAP	Page:	28
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Pling	Config.:	Normal

Alert Summary Report

	% Alert Settings	Critical	Marginal
<u>Loading</u>			
Bus		100.0	95.0
Cable		100.0	95.0
Reactor		100.0	95.0
Line		100.0	95.0
Transformer		100.0	95.0
Panel		100.0	95.0
Protective Device		100.0	95.0
Generator		100.0	95.0
Inverter/Charger		100.0	95.0
<u>Bus Voltage</u>			
OverVoltage		110.0	105.0
UnderVoltage		90.0	95.0
<u>Generator Excitation</u>			
OverExcited (Q Max.)		100.0	95.0
UnderExcited (Q Min.)		100.0	

Critical Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus100	Bus	Under Voltage	11.000	kV	9.100	82.7	3-Phase
Bus101	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus102	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus103	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus104	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus105	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus106	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus107	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus108	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus109	Bus	Under Voltage	11.000	kV	9.10	82.7	3-Phase
Bus110	Bus	Under Voltage	11.000	kV	9.04	82.2	3-Phase
Bus111	Bus	Under Voltage	11.000	kV	9.04	82.2	3-Phase
Bus112	Bus	Under Voltage	11.000	kV	9.03	82.1	3-Phase
Bus113	Bus	Under Voltage	11.000	kV	9.03	82.1	3-Phase
Bus114	Bus	Under Voltage	11.000	kV	9.01	81.9	3-Phase

Project:	ETAP	Page:	29
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Critical Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus115	Bus	Under Voltage	11.000	kV	8.974	81.6	3-Phase
Bus116	Bus	Under Voltage	11.000	kV	8.99	81.7	3-Phase
Bus117	Bus	Under Voltage	11.000	kV	8.98	81.6	3-Phase
Bus118	Bus	Under Voltage	11.000	kV	8.98	81.6	3-Phase
Bus119	Bus	Under Voltage	11.000	kV	8.92	81.1	3-Phase
Bus120	Bus	Under Voltage	11.000	kV	8.93	81.2	3-Phase
Bus330	Bus	Under Voltage	11.000	kV	9.86	89.6	3-Phase
Bus331	Bus	Under Voltage	11.000	kV	9.86	89.6	3-Phase
Bus332	Bus	Under Voltage	11.000	kV	9.85	89.5	3-Phase
Bus333	Bus	Under Voltage	11.000	kV	9.84	89.5	3-Phase
Bus334	Bus	Under Voltage	11.000	kV	9.84	89.5	3-Phase
Bus335	Bus	Under Voltage	11.000	kV	9.77	88.8	3-Phase
Bus336	Bus	Under Voltage	11.000	kV	9.77	88.8	3-Phase
Bus337	Bus	Under Voltage	11.000	kV	9.77	88.8	3-Phase
Bus338	Bus	Under Voltage	11.000	kV	9.75	88.6	3-Phase
Bus339	Bus	Under Voltage	11.000	kV	9.75	88.7	3-Phase
Bus340	Bus	Under Voltage	11.000	kV	9.74	88.5	3-Phase
Bus341	Bus	Under Voltage	11.000	kV	9.74	88.5	3-Phase
Bus342	Bus	Under Voltage	11.000	kV	9.74	88.5	3-Phase
Bus343	Bus	Under Voltage	11.000	kV	9.74	88.5	3-Phase
Bus346	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus347	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus428	Bus	Under Voltage	11.000	kV	8.93	81.2	3-Phase
Bus449	Bus	Under Voltage	11.000	kV	9.74	88.5	3-Phase
Bus450	Bus	Under Voltage	11.000	kV	9.75	88.7	3-Phase
Bus451	Bus	Under Voltage	11.000	kV	9.77	88.8	3-Phase
Bus452	Bus	Under Voltage	11.000	kV	9.85	89.5	3-Phase
Bus453	Bus	Under Voltage	11.000	kV	9.85	89.5	3-Phase
Bus468	Bus	Under Voltage	11.000	kV	9.43	85.8	3-Phase
Bus85	Bus	Under Voltage	11.000	kV	9.78	88.9	3-Phase
Bus86	Bus	Under Voltage	11.000	kV	9.78	88.9	3-Phase
Bus87	Bus	Under Voltage	11.000	kV	9.77	88.9	3-Phase
Bus88	Bus	Under Voltage	11.000	kV	9.46	86.0	3-Phase
Bus89	Bus	Under Voltage	11.000	kV	9.46	86.0	3-Phase
Bus90	Bus	Under Voltage	11.000	kV	9.44	85.8	3-Phase
Bus91	Bus	Under Voltage	11.000	kV	9.43	85.7	3-Phase

Project:	ETAP	Page:	30
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Pling	Config.:	Normal

Critical Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus92	Bus	Under Voltage	11.000	kV	9.435	85.8	3-Phase
Bus93	Bus	Under Voltage	11.000	kV	9.43	85.7	3-Phase
Bus94	Bus	Under Voltage	11.000	kV	9.40	85.4	3-Phase
Bus95	Bus	Under Voltage	11.000	kV	9.37	85.2	3-Phase
Bus96	Bus	Under Voltage	11.000	kV	9.27	84.3	3-Phase
Bus97	Bus	Under Voltage	11.000	kV	9.27	84.3	3-Phase
Bus98	Bus	Under Voltage	11.000	kV	9.22	83.8	3-Phase
Bus99	Bus	Under Voltage	11.000	kV	9.22	83.8	3-Phase

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
33/11kV Sector I SS	Transformer	Overload	5.000	MVA	4.863	97.3	3-Phase
33/11kV Sector II SS	Transformer	Overload	5.000	MVA	4.84	96.8	3-Phase
Bus10	Bus	Under Voltage	11.000	kV	10.29	93.5	3-Phase
Bus11	Bus	Under Voltage	11.000	kV	10.29	93.5	3-Phase
Bus12	Bus	Under Voltage	11.000	kV	10.27	93.4	3-Phase
Bus13	Bus	Under Voltage	11.000	kV	10.27	93.3	3-Phase
Bus14	Bus	Under Voltage	11.000	kV	10.24	93.1	3-Phase
Bus15	Bus	Under Voltage	11.000	kV	10.25	93.1	3-Phase
Bus16	Bus	Under Voltage	11.000	kV	10.23	93.0	3-Phase
Bus17	Bus	Under Voltage	11.000	kV	10.23	93.0	3-Phase
Bus18	Bus	Under Voltage	11.000	kV	10.22	92.9	3-Phase
Bus19	Bus	Under Voltage	11.000	kV	10.20	92.7	3-Phase
Bus20	Bus	Under Voltage	11.000	kV	10.20	92.7	3-Phase
Bus21	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus22	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus224	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus23	Bus	Under Voltage	11.000	kV	10.14	92.2	3-Phase
Bus24	Bus	Under Voltage	11.000	kV	10.14	92.2	3-Phase
Bus25	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus259	Bus	Under Voltage	11.000	kV	10.16	92.3	3-Phase
Bus26	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus260	Bus	Under Voltage	11.000	kV	10.13	92.1	3-Phase
Bus261	Bus	Under Voltage	11.000	kV	10.13	92.1	3-Phase
Bus262	Bus	Under Voltage	11.000	kV	10.11	91.9	3-Phase
Bus263	Bus	Under Voltage	11.000	kV	10.11	91.9	3-Phase

Project:	ETAP	Page:	31
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus264	Bus	Under Voltage	11.000	kV	10.101	91.8	3-Phase
Bus265	Bus	Under Voltage	11.000	kV	10.09	91.8	3-Phase
Bus266	Bus	Under Voltage	11.000	kV	10.09	91.8	3-Phase
Bus267	Bus	Under Voltage	11.000	kV	10.09	91.7	3-Phase
Bus268	Bus	Under Voltage	11.000	kV	10.09	91.7	3-Phase
Bus269	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Bus27	Bus	Under Voltage	11.000	kV	10.01	91.0	3-Phase
Bus270	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Bus273	Bus	Under Voltage	11.000	kV	10.13	92.1	3-Phase
Bus274	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus275	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus276	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus277	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus278	Bus	Under Voltage	11.000	kV	10.11	91.9	3-Phase
Bus279	Bus	Under Voltage	11.000	kV	10.11	91.9	3-Phase
Bus28	Bus	Under Voltage	11.000	kV	10.05	91.4	3-Phase
Bus280	Bus	Under Voltage	11.000	kV	10.11	91.9	3-Phase
Bus281	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Bus29	Bus	Under Voltage	11.000	kV	10.05	91.3	3-Phase
Bus292	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus293	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus294	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus295	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Bus296	Bus	Under Voltage	11.000	kV	10.04	91.3	3-Phase
Bus297	Bus	Under Voltage	11.000	kV	9.94	90.3	3-Phase
Bus298	Bus	Under Voltage	11.000	kV	10.02	91.1	3-Phase
Bus299	Bus	Under Voltage	11.000	kV	10.02	91.1	3-Phase
Bus30	Bus	Under Voltage	11.000	kV	10.05	91.4	3-Phase
Bus300	Bus	Under Voltage	11.000	kV	10.02	91.1	3-Phase
Bus301	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus302	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus31	Bus	Under Voltage	11.000	kV	10.05	91.4	3-Phase
Bus315	Bus	Under Voltage	11.000	kV	10.39	94.5	3-Phase
Bus316	Bus	Under Voltage	11.000	kV	10.39	94.5	3-Phase
Bus317	Bus	Under Voltage	11.000	kV	10.39	94.5	3-Phase
Bus318	Bus	Under Voltage	11.000	kV	10.35	94.1	3-Phase

Project:	ETAP	Page:	32
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Pling		Config.:	Normal

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus319	Bus	Under Voltage	11.000	kV	10.310	93.7	3-Phase
Bus320	Bus	Under Voltage	11.000	kV	10.28	93.4	3-Phase
Bus321	Bus	Under Voltage	11.000	kV	10.28	93.5	3-Phase
Bus322	Bus	Under Voltage	11.000	kV	10.13	92.1	3-Phase
Bus323	Bus	Under Voltage	11.000	kV	10.09	91.8	3-Phase
Bus324	Bus	Under Voltage	11.000	kV	10.05	91.3	3-Phase
Bus325	Bus	Under Voltage	11.000	kV	10.04	91.3	3-Phase
Bus326	Bus	Under Voltage	11.000	kV	10.04	91.3	3-Phase
Bus327	Bus	Under Voltage	11.000	kV	9.92	90.2	3-Phase
Bus328	Bus	Under Voltage	11.000	kV	9.91	90.1	3-Phase
Bus329	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus344	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus345	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus348	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus349	Bus	Under Voltage	11.000	kV	9.91	90.1	3-Phase
Bus350	Bus	Under Voltage	11.000	kV	9.92	90.2	3-Phase
Bus361	Bus	Under Voltage	11.000	kV	10.42	94.7	3-Phase
Bus362	Bus	Under Voltage	11.000	kV	10.41	94.7	3-Phase
Bus363	Bus	Under Voltage	11.000	kV	10.41	94.6	3-Phase
Bus364	Bus	Under Voltage	11.000	kV	10.41	94.6	3-Phase
Bus365	Bus	Under Voltage	11.000	kV	10.40	94.5	3-Phase
Bus366	Bus	Under Voltage	11.000	kV	10.39	94.5	3-Phase
Bus367	Bus	Under Voltage	11.000	kV	10.39	94.5	3-Phase
Bus368	Bus	Under Voltage	11.000	kV	10.39	94.4	3-Phase
Bus369	Bus	Under Voltage	11.000	kV	10.39	94.4	3-Phase
Bus371	Bus	Under Voltage	11.000	kV	10.31	93.7	3-Phase
Bus372	Bus	Under Voltage	11.000	kV	10.28	93.5	3-Phase
Bus373	Bus	Under Voltage	11.000	kV	10.28	93.5	3-Phase
Bus374	Bus	Under Voltage	11.000	kV	10.27	93.4	3-Phase
Bus375	Bus	Under Voltage	11.000	kV	10.28	93.4	3-Phase
Bus376	Bus	Under Voltage	11.000	kV	10.26	93.2	3-Phase
Bus377	Bus	Under Voltage	11.000	kV	10.24	93.1	3-Phase
Bus378	Bus	Under Voltage	11.000	kV	10.21	92.8	3-Phase
Bus379	Bus	Under Voltage	11.000	kV	10.19	92.6	3-Phase
Bus380	Bus	Under Voltage	11.000	kV	10.19	92.7	3-Phase
Bus381	Bus	Under Voltage	11.000	kV	10.13	92.1	3-Phase

Project:	ETAP	Page:	33
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename: ESD Plng		Config.:	Normal

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus383	Bus	Under Voltage	11.000	kV	10.168	92.4	3-Phase
Bus384	Bus	Under Voltage	11.000	kV	10.15	92.3	3-Phase
Bus385	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus386	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus387	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus388	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus389	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus390	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus391	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus392	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus393	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus394	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus395	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus396	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus413	Bus	Under Voltage	11.000	kV	10.45	95.0	3-Phase
Bus415	Bus	Under Voltage	11.000	kV	10.43	94.8	3-Phase
Bus416	Bus	Under Voltage	11.000	kV	10.42	94.7	3-Phase
Bus417	Bus	Under Voltage	11.000	kV	10.41	94.7	3-Phase
Bus418	Bus	Under Voltage	11.000	kV	10.45	95.0	3-Phase
Bus420	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus421	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus423	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus424	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus425	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus426	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus427	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus429	Bus	Under Voltage	11.000	kV	10.05	91.4	3-Phase
Bus430	Bus	Under Voltage	11.000	kV	10.05	91.3	3-Phase
Bus431	Bus	Under Voltage	11.000	kV	10.05	91.4	3-Phase
Bus447	Bus	Under Voltage	11.000	kV	10.43	94.8	3-Phase
Bus448	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus454	Bus	Under Voltage	11.000	kV	9.91	90.0	3-Phase
Bus455	Bus	Under Voltage	11.000	kV	10.31	93.7	3-Phase
Bus456	Bus	Under Voltage	11.000	kV	10.04	91.3	3-Phase
Bus459	Bus	Under Voltage	11.000	kV	9.91	90.1	3-Phase
Bus460	Bus	Under Voltage	11.000	kV	10.02	91.1	3-Phase

Project: **ETAP** Page: 34
 Location: 16.1.1C Date: 09-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESD Plng Config.: Normal

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus464	Bus	Under Voltage	11.000	kV	10.418	94.7	3-Phase
Bus465	Bus	Under Voltage	11.000	kV	10.33	93.9	3-Phase
Bus466	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus467	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus469	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Bus56	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus57	Bus	Under Voltage	11.000	kV	10.44	94.9	3-Phase
Bus60	Bus	Under Voltage	11.000	kV	10.42	94.7	3-Phase
Bus61	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus62	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus63	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus64	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus65	Bus	Under Voltage	11.000	kV	10.34	94.0	3-Phase
Bus66	Bus	Under Voltage	11.000	kV	10.33	93.9	3-Phase
Bus67	Bus	Under Voltage	11.000	kV	10.33	93.9	3-Phase
Bus68	Bus	Under Voltage	11.000	kV	10.30	93.6	3-Phase
Bus69	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus70	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus71	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus72	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus73	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus74	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus75	Bus	Under Voltage	11.000	kV	10.29	93.6	3-Phase
Bus78	Bus	Under Voltage	11.000	kV	10.28	93.4	3-Phase
Bus79	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus80	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus81	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus82	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus83	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase
Bus84	Bus	Under Voltage	11.000	kV	9.90	90.0	3-Phase
Bus9	Bus	Under Voltage	11.000	kV	10.32	93.8	3-Phase
Cable54	Cable	Overload	338.032	Amp	334.64	99.0	3-Phase
RMU MBC	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
RMU Near Bridge	Bus	Under Voltage	11.000	kV	10.10	91.8	3-Phase
Telecom RMU	Bus	Under Voltage	11.000	kV	10.12	92.0	3-Phase


Project:	ETAP	Page:	35
Location:	16.1.1C	Date:	09-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESD Plng	Config.:	Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	39.269	27.116	47.721	82.29 Lagging
Source (Non-Swing Buses):	0.000	0.000	0.000	
Total Demand:	39.269	27.116	47.721	82.29 Lagging
Total Motor Load:	15.923	9.868	18.733	85.00 Lagging
Total Static Load:	21.988	13.627	25.868	85.00 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	1.358	3.622		
System Mismatch:	0.000	0.000		

Number of Iterations: 3

One-Line Diagram - ESSD Gedu=>B100 (Load Flow Analysis)



Project:	ETAP	Page:	1
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus Loading Summary Report

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MVA			
Bus1	66.000								10.021	86.5	87.7	
Bus2	33.000								3.577	92.1	63.3	
Bus3	33.000								2.076	95.9	36.7	
Bus4	33.000								2.067	95.6	36.9	
Bus5	33.000								1.295	88.4	23.1	
Bus6	33.000		0.018	0.011					0.111	87.1	2.0	
Bus7	33.000		0.058	0.036					0.092	86.1	1.6	
Bus8	33.000		0.021	0.013					0.025	85.0	0.4	
Bus9	33.000								1.226	85.5	21.9	
Bus10	33.000		0.001	0.001					0.138	84.3	2.5	
Bus11	33.000								0.139	82.5	2.5	
Bus12	33.000		0.015	0.009					0.045	97.9	0.8	
Bus13	33.000		0.008	0.005					0.030	98.7	0.5	
Bus14	33.000		0.005	0.003					0.022	96.8	0.4	
Bus15	33.000		0.010	0.006					0.019	86.5	0.3	
Bus16	33.000		0.007	0.004					0.008	85.0	0.1	
Bus17	33.000								0.105	67.1	1.9	
Bus19	33.000		0.005	0.003					0.006	85.0	0.1	
Bus20	33.000								0.096	71.2	1.7	
Bus21	33.000		0.021	0.013					0.098	64.1	1.8	
Bus22	33.000		0.002	0.001					0.002	85.0	-	
Bus23	33.000								0.049	84.8	0.9	
Bus24	33.000		0.005	0.003					0.047	85.2	0.8	
Bus25	33.000								0.042	83.9	0.8	
Bus26	33.000		0.003	0.002					0.021	78.7	0.4	
Bus29	33.000		0.004	0.002					0.013	65.6	0.2	
Bus30	33.000		0.003	0.002					0.008	67.5	0.1	
Bus31	33.000		0.002	0.002					0.003	85.0	0.1	
Bus32	33.000		0.005	0.003					0.023	81.7	0.4	
Bus33	33.000		0.003	0.002					0.017	78.7	0.3	
Bus38	33.000								0.831	100.0	14.8	
Bus39	33.000		0.009	0.006					0.011	85.0	0.2	
Bus40	33.000								0.830	100.0	14.8	
Bus41	33.000		0.010	0.006					0.821	100.0	14.7	
Bus42	33.000								0.810	100.0	14.5	
Bus43	33.000		0.014	0.009					0.024	93.3	0.4	
Bus44	33.000		0.009	0.005					0.010	85.0	0.2	
Bus45	33.000								0.787	100.0	14.1	
Bus46	33.000		0.006	0.004					0.007	85.0	0.1	

Project:	ETAP	Page:	2
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus47		33.000										0.083	95.4	1.5	
Bus48		33.000				0.002	0.001					0.080	92.2	1.4	
Bus49		33.000										0.078	91.5	1.4	
Bus51		33.000				0.008	0.005					0.076	90.4	1.4	
Bus52		33.000				0.019	0.012					0.067	90.1	1.2	
Bus53		33.000										0.045	91.4	0.8	
Bus54		33.000				0.008	0.005					0.010	85.0	0.2	
Bus55		33.000				0.011	0.007					0.038	87.4	0.7	
Bus56		33.000				0.012	0.008					0.025	86.2	0.4	
Bus57		33.000				0.009	0.006					0.011	85.0	0.2	
Bus58		33.000				0.008	0.005					0.009	85.0	0.2	
Bus59		33.000										0.707	100.0	12.6	
Bus60		33.000				0.024	0.015					0.700	100.0	12.5	
Bus61		33.000				0.006	0.004					0.007	85.0	0.1	
Bus62		33.000										0.676	100.0	12.1	
Bus63		33.000										0.670	100.0	12.0	
Bus64		33.000				0.008	0.005					0.014	93.6	0.2	
Bus65		33.000				0.005	0.003					0.006	85.0	0.1	
Bus66		33.000										0.657	100.0	11.8	
Bus67		33.000				0.009	0.005					0.010	85.0	0.2	
Bus68		33.000				0.018	0.011					0.022	85.0	0.4	
Bus69		33.000										0.648	100.0	11.6	
Bus70		33.000										0.629	99.9	11.3	
Bus71		33.000				0.005	0.003					0.005	85.0	0.1	
Bus72		33.000										0.020	93.2	0.4	
Bus73		33.000				0.003	0.002					0.004	85.0	0.1	
Bus74		33.000				0.011	0.007					0.017	80.6	0.3	
Bus75		33.000				0.011	0.007					0.611	99.9	10.9	
Bus76		33.000				0.007	0.005					0.600	99.9	10.7	
Bus77		33.000				0.004	0.003					0.592	99.9	10.6	
Bus78		33.000										0.588	99.9	10.5	
Bus79		33.000				0.007	0.005					0.013	66.1	0.2	
Bus81		33.000				0.002	0.001					0.002	85.0	-	
Bus82		33.000										0.580	99.8	10.4	
Bus83		33.000				0.004	0.003					0.579	99.7	10.4	
Bus84		33.000										0.575	99.5	10.3	
Bus85		33.000				0.004	0.003					0.015	75.2	0.3	
Bus86		33.000				0.004	0.003					0.013	52.2	0.2	
Bus88		33.000												-	
Bus89		33.000										0.566	99.1	10.2	
Bus90		33.000										0.566	99.0	10.2	
Bus91		33.000				0.003	0.002					0.004	85.0	0.1	

Project:	ETAP	Page:	3
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus93		33.000										0.566	98.6	10.2	
Bus94		33.000		0.101	0.062	0.025	0.016					0.148	85.0	2.7	
Bus95		33.000										0.565	98.4	10.2	
Bus96		33.000										0.432	99.7	7.8	
Bus97		33.000										0.012	94.8	0.2	
Bus98		33.000				0.004	0.003					0.005	85.0	0.1	
Bus99		33.000				0.005	0.003					0.008	87.2	0.1	
Bus100		33.000				0.002	0.001					0.003	85.0	-	
Bus101		33.000										0.420	99.6	7.6	
Bus102		33.000				0.029	0.018					0.034	85.0	0.6	
Bus104		33.000										0.391	99.7	7.0	
Bus105		33.000										0.387	98.9	7.0	
Bus106		33.000				0.008	0.005					0.020	96.5	0.4	
Bus109		33.000				0.021	0.013					0.024	85.0	0.4	
Bus110		33.000										0.369	98.8	6.6	
Bus111		33.000				0.025	0.015					0.029	85.0	0.5	
Bus112		33.000										0.347	99.0	6.2	
Bus113		33.000										0.321	99.4	5.8	
Bus114		33.000				0.014	0.008					0.059	87.0	1.1	
Bus115		33.000				0.038	0.023					0.045	85.0	0.8	
Bus116		33.000										0.284	94.0	5.1	
Bus117		33.000										0.187	85.3	3.4	
Bus118		33.000		0.002	0.001	0.158	0.098					0.187	85.0	3.4	
Bus119		33.000												-	
Bus120		33.000				0.018	0.011					0.145	74.5	2.6	
Bus121		33.000										0.123	73.1	2.2	
Bus122		33.000				0.002	0.001					0.005	95.5	0.1	
Bus123		33.000				0.002	0.001					0.003	85.0	0.1	
Bus124		33.000										0.117	72.9	2.1	
Bus125		33.000				0.004	0.002					0.009	77.5	0.2	
Bus126		33.000		0.000	0.000	0.002	0.001					0.003	85.0	0.1	
Bus127		33.000										0.005	76.9	0.1	
Bus129		33.000										0.104	75.0	1.9	
Bus130		33.000		0.000	0.000	0.002	0.001					0.019	53.9	0.3	
Bus131		33.000										0.016	49.4	0.3	
Bus133		33.000				0.003	0.002					0.007	94.9	0.1	
Bus135		33.000				0.007	0.004					0.008	85.0	0.2	
Bus136		33.000										0.088	78.0	1.6	
Bus137		33.000										0.082	74.6	1.5	
Bus138		33.000		0.000	0.000	0.007	0.004					0.008	85.0	0.1	
Bus139		33.000										0.014	93.1	0.3	
Bus140		33.000				0.007	0.004					0.008	85.0	0.1	

Project:	ETAP	Page:	4
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus141	33.000					0.016	0.010					0.019	85.0	0.3	
Bus142	33.000											0.077	62.4	1.4	
Bus143	33.000											0.065	48.4	1.2	
Bus144	33.000		0.000	0.000		0.012	0.007					0.014	85.0	0.2	
Bus145	33.000											0.020	93.2	0.4	
Bus159	33.000											0.046	27.9	0.8	
Bus165	11.000											6.257	85.4	337.9	
Bus166	11.000											0.926	85.4	50.0	
Bus167	11.000	0.099	0.061	0.073	0.045							0.203	85.0	11.0	
Bus168	11.000					0.010	0.006					0.012	85.0	0.6	
Bus169	11.000											0.135	85.8	7.3	
Bus170	11.000					0.010	0.006					0.124	85.6	6.7	
Bus171	11.000					0.004	0.002					0.005	85.0	0.2	
Bus172	11.000											0.113	85.4	6.1	
Bus173	11.000					0.035	0.021					0.108	85.1	5.9	
Bus174	11.000	0.001	0.001	0.056	0.035							0.068	85.0	3.7	
Bus175	11.000	0.001	0.001	0.044	0.027							0.800	84.7	43.2	
Bus176	11.000	0.006	0.003	0.171	0.106							0.747	84.7	40.3	
Bus177	11.000	0.003	0.002	0.093	0.058							0.538	84.6	29.1	
Bus178	11.000	0.003	0.002	0.098	0.061							0.425	84.5	23.0	
Bus179	11.000	0.006	0.003	0.171	0.106							0.306	84.3	16.5	
Bus180	11.000	0.004	0.002	0.108	0.067							0.131	85.0	7.1	
Bus181	11.000	0.005	0.003	0.156	0.096							0.222	86.0	12.0	
Bus182	11.000	0.007	0.004	0.218	0.135							0.487	85.5	26.3	
Bus183	11.000	0.003	0.002	0.083	0.052							0.588	85.4	31.8	
Bus184	11.000											0.004	2.7	0.2	
Bus185	11.000											0.004	3.2	0.2	
Bus186	11.000					0.000	-					0.000	85.0	-	
Bus187	11.000											3.917	85.0	211.7	
Bus188	11.000	0.003	0.002	0.129	0.080							3.910	85.0	211.7	
Bus189	11.000											3.662	85.2	203.3	
Bus190	11.000	0.001	0.001	0.040	0.025							0.048	85.0	2.7	
Bus191	11.000					0.005	0.003					0.006	85.0	0.3	
Bus192	11.000											3.438	85.6	200.7	
Bus193	11.000	0.001	0.001	0.043	0.027							0.052	85.0	3.2	
Bus194	11.000											3.247	85.3	200.4	
Bus195	11.000	1.756	1.089	0.690	0.428							2.878	85.0	184.7	
Bus196	11.000											3.083	85.0	197.1	
Bus197	11.000	0.001	0.001	0.070	0.043							0.195	85.2	12.4	
Bus198	11.000	0.001	0.000	0.040	0.025							0.111	85.2	7.1	
Bus199	11.000					0.003	0.002					0.003	85.0	0.2	
Bus200	11.000											0.063	85.2	4.0	

Project:	ETAP	Page:	5
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load						
	ID	kV	Rated Amp	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
				MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar				
Bus201		11.000				0.051	0.032					0.060	85.0	3.9	
Bus202		11.000										0.328	86.0	17.7	
Bus203		11.000										0.328	86.0	17.7	
Bus204		11.000		0.003	0.002	0.155	0.096					0.186	85.0	10.1	
Bus205		11.000				0.006	0.004					0.142	86.7	7.7	
Bus206		11.000				0.010	0.006					0.135	86.5	7.3	
Bus207		11.000				0.004	0.002					0.005	85.0	0.3	
Bus208		11.000										0.123	86.4	6.7	
Bus209		11.000				0.022	0.014					0.119	86.3	6.5	
Bus210		11.000				0.011	0.007					0.013	85.0	0.7	
Bus211		11.000										0.093	86.1	5.1	
Bus212		11.000				0.010	0.006					0.012	85.0	0.7	
Bus213		11.000				0.022	0.014					0.068	85.8	3.7	
Bus214		11.000				0.019	0.012					0.043	85.9	2.3	
Bus215		11.000				0.017	0.011					0.020	85.0	1.1	
Bus216		11.000										2.633	84.3	142.8	
Bus217		33.000										1.532	85.0	27.1	
Bus218		33.000										1.539	84.0	27.4	
Bus219		33.000										1.128	82.6	20.1	
Bus220		11.000										0.285	91.7	15.4	
Bus221		11.000										0.285	91.7	15.4	
Bus222		11.000				0.159	0.098					0.187	85.0	10.1	
Bus223		11.000											-		
Bus224		11.000										0.104	98.8	5.6	
Bus225		11.000										0.064	37.7	3.5	
Bus226		11.000				0.098	0.061					0.115	85.0	6.2	
Bus227		11.000				0.020	0.012					0.094	99.1	5.1	
Bus228		11.000										0.104	98.6	5.6	
Bus229		11.000				0.009	0.005					0.010	85.0	0.6	
Bus230		11.000										0.212	85.6	11.5	
Bus231		11.000										0.212	85.5	11.5	
Bus232		11.000				0.034	0.021					0.040	85.0	2.2	
Bus233		11.000				0.023	0.014					0.027	85.0	1.5	
Bus234		11.000										0.172	85.6	9.3	
Bus235		11.000				0.038	0.023					0.145	85.7	7.9	
Bus236		11.000				0.041	0.026					0.101	85.9	5.5	
Bus237		11.000				0.025	0.015					0.029	85.0	1.6	
Bus238		11.000										0.052	86.3	2.8	
Bus239		11.000				0.021	0.013					0.024	85.0	1.3	
Bus240		11.000				0.228	0.142					1.038	85.0	56.3	
Bus241		11.000				0.221	0.137					0.769	85.0	41.7	
Bus242		11.000				0.213	0.132					0.509	85.1	27.6	

Project:	ETAP	Page:	6
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus243		11.000			0.189	0.117			0.259	85.1	14.1	
Bus244		11.000			0.014	0.009			0.016	85.0	0.9	
Bus245		11.000			0.018	0.011			0.021	85.0	1.1	
Bus246		11.000							1.007	85.0	54.6	
Bus247		11.000			0.170	0.106			0.200	85.0	10.9	
Bus248		11.000							1.005	85.0	54.6	
Bus249		11.000			0.212	0.131			0.249	85.0	13.6	
Bus250		11.000							0.801	85.0	43.7	
Bus251		11.000			0.212	0.131			0.249	85.0	13.6	
Bus252		11.000							0.551	85.0	30.1	
Bus253		11.000							0.302	85.0	16.5	
Bus254		11.000			0.128	0.080			0.302	85.0	16.5	
Bus255		11.000			0.128	0.080			0.151	85.0	8.3	
Bus264		11.000			0.075	0.047			0.089	85.0	4.8	
Bus265		11.000			0.081	0.050			0.096	85.0	5.2	
Bus266		11.000			0.020	0.012			0.023	85.0	1.3	
Bus267		11.000							0.268	85.3	14.5	
Bus268		11.000							0.268	85.2	14.5	
Bus269		11.000							0.245	85.2	13.3	
Bus270		11.000							0.149	85.2	8.1	
Bus271		11.000			0.052	0.032			0.061	85.0	3.3	
Bus272		11.000							0.056	85.7	3.0	
Bus273		11.000			0.048	0.030			0.056	85.0	3.0	
Bus274		11.000										
Bus275		33.000			0.006	0.004			0.008	85.0	0.1	
Bus276		33.000			0.002	0.001			0.011	99.2	0.2	
Bus277		33.000			0.008	0.005			0.010	85.0	0.2	
Bus278		33.000			0.001	0.001			0.001	85.0	-	
Bus279		33.000			0.001	0.001			0.002	85.0	-	
Bus280		33.000			0.003	0.002			0.004	85.0	0.1	
Bus281		33.000			0.001	0.001			0.008	89.1	0.1	
Bus282		33.000							0.007	86.3	0.1	
Bus283		33.000			0.003	0.002			0.003	85.0	0.1	
Bus284		33.000							0.004	75.5	0.1	
Bus285		33.000			0.002	0.001			0.003	85.0	0.1	
Bus286		33.000			0.001	-			0.001	85.0	-	
Bus287		33.000							0.035	36.8	0.6	
Bus288		33.000			0.001	-			0.008	52.0	0.1	
Bus289		33.000							0.004	91.4	0.1	
Bus290		33.000			0.000	-			0.022	38.2	0.4	
Bus291		33.000							0.001	85.0	-	
Bus292		33.000			0.003	0.002			0.004	85.0	0.1	

Project:	ETAP	Page:	7
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus293		33.000			0.000	-			0.000	85.0	-	-
Bus294		33.000							0.019	42.3	0.3	
Bus295		33.000			0.001	0.001			0.001	85.0	-	
Bus296		33.000			0.003	0.002			0.017	42.3	0.3	
Bus297		33.000			0.003	0.002			0.007	60.6	0.1	
Bus298		33.000			0.001	0.001			0.001	85.0	-	
Bus299		33.000			0.002	0.001			0.002	85.0	-	
Bus300		33.000							0.019	72.4	0.3	
Bus301		33.000			0.005	0.003			0.006	85.0	0.1	
Bus302		33.000							0.011	90.3	0.2	
Bus303		33.000			0.006	0.004			0.010	93.0	0.2	
Bus304		33.000			0.001	0.001			0.002	85.0	-	
Bus305		33.000			0.003	0.002			0.004	85.0	0.1	
Bus306		33.000			0.003	0.002			0.004	85.0	0.1	
Bus307		33.000			0.001	0.001			0.001	85.0	-	
Bus308		33.000			0.001	0.001			0.001	85.0	-	
Bus309		33.000			0.002	0.001			0.003	85.0	-	

* Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:	ETAP	Page:	8
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch Loading Summary Report

CKT / Branch	Cable & Reactor			Transformer						
	ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input)	Loading (output)		
							MVA	%	MVA	%
Cable1		Cable	274.79	36.72	13.36					
Cable2		Cable	301.98	43.22	14.31					
Cable3		Cable	229.86	50.01	21.75					
Cable4		Cable	301.98	40.32	13.35					
Cable5		Cable	301.98	29.08	9.63					
Cable6		Cable	301.98	22.96	7.60					
Cable7		Cable	301.98	16.52	5.47					
Cable8		Cable	301.98	5.29	1.75					
Cable9		Cable	301.98	1.80	0.60					
Cable10		Cable	338.03	11.52	3.41					
Cable11		Cable	301.98	12.01	3.98					
Cable12		Cable	301.98	26.30	8.71					
Cable13		Cable	301.98	31.78	10.52					
Cable14		Cable	338.03	0.22	0.07					
Cable15		Cable	338.03	211.69	62.62					
Cable16		Cable	338.03	17.72	5.24					
Cable17		Cable	274.79	27.10	9.86					
Cable18		Cable	338.03	15.38	4.55					
Cable19		Cable	338.03	3.45	1.02					
Cable20		Cable	338.03	56.30	16.65					
Cable21		Cable	338.03	41.72	12.34					
Cable22		Cable	338.03	27.64	8.18					
Cable23		Cable	338.03	14.07	4.16					
Cable24		Cable	338.03	0.89	0.26					
Cable25		Cable	338.03	54.60	16.15					
Cable26		Cable	338.03	16.51	4.88					
Cable27		Cable	338.03	8.25	2.44					
Cable30		Cable	338.03	14.53	4.30					
Cable31		Cable	338.03	3.02	0.89					
Cable32		Cable	338.03							
33/11kV I		Transformer				5.000	1.539	30.8	1.519	30.4
33/11kV II		Transformer				5.000	1.128	22.6	1.115	22.3
66/11KV I		Transformer				5.000	3.217	64.3	3.127	62.5

Project: **ETAP** Page: 9
 Location: 16.1.1C Date: 08-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESSD Gedu Config.: Normal

CKT / Branch		Cable & Reactor			Transformer				
ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input) MVA	%	Loading (output) MVA	%
66/11KV II	Transformer				5.000	3.217	64.3	3.127	62.5
66/33kV II	Transformer				8.000	2.208	27.6	2.184	27.3
66/33/11kV	3W XFMR p				5.000	1.409	28.2		
	3W XFMR s				2.500	1.393	55.7		
	3W XFMR t				2.500	0.000	0.0		

* Indicates a branch with operating load exceeding the branch capability.

Project: **ETAP** Page: 10
 Location: **16.1.1C** Date: 08-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESSD Gedu Config.: Normal

Branch Losses Summary Report

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
66/11KV I	2.685	1.773	-2.673	-1.624	12.4	148.6	100.0	97.2	2.80
66/11KV II	2.685	1.773	-2.673	-1.624	12.4	148.6	100.0	97.2	2.80
66/33kV II	2.013	0.906	-2.009	-0.856	3.9	50.7	100.0	98.9	1.08
Cable1	1.991	0.588	-1.991	-0.588	0.4	0.0	98.9	98.9	0.02
Cable17	1.303	0.806	-1.303	-0.806	0.3	0.0	98.9	98.9	0.02
Line1	1.991	0.588	-1.977	-0.606	14.1	-18.2	98.9	98.1	0.81
Line2	0.831	0.003	-0.831	-0.005	0.2	-2.1	98.1	98.1	0.02
Line3	1.146	0.603	-1.145	-0.605	0.4	-2.0	98.1	98.0	0.04
Line4	0.097	0.053	-0.097	-0.055	0.0	-1.5	98.0	98.0	0.00
Line7	1.048	0.552	-1.048	-0.555	0.6	-3.1	98.0	98.0	0.06
Line5	0.079	0.044	-0.079	-0.047	0.0	-3.0	98.0	98.0	0.00
Line6	0.021	0.011	-0.021	-0.013	0.0	-2.3	98.0	98.0	0.00
Line8	0.116	-0.081	-0.116	0.073	0.0	-8.3	98.0	98.0	0.00
Line201	0.932	0.636	-0.932	-0.636	0.0	-0.2	98.0	98.0	0.00
Line9	0.115	-0.074	-0.115	0.070	0.0	-3.8	98.0	98.0	0.00
Line10	0.070	-0.078	-0.070	0.078	0.0	-0.6	98.0	98.0	0.00
Line11	0.044	0.008	-0.044	-0.008	0.0	-0.1	98.0	98.0	0.00
Line12	0.029	-0.001	-0.029	-0.001	0.0	-2.4	98.0	98.0	0.00
Line13	0.022	-0.003	-0.022	-0.006	0.0	-9.0	98.0	98.0	0.00
Line14	0.016	0.002	-0.016	-0.010	0.0	-7.1	98.0	98.0	0.00
Line15	0.007	0.003	-0.007	-0.004	0.0	-0.6	98.0	98.0	0.00
Line16	0.002	-0.004	-0.002	-0.001	0.0	-5.2	98.0	98.0	0.00
Line17	0.068	-0.074	-0.068	0.066	0.0	-7.4	98.0	98.0	0.01
Line18	-0.005	-0.003	0.005	0.001	0.0	-2.5	98.0	98.0	0.00
Line19	0.063	-0.067	-0.063	0.062	0.0	-5.1	98.0	98.0	0.00
Line20	0.042	-0.075	-0.042	0.026	0.0	-49.2	98.0	98.0	0.00
Line21	-0.002	-0.001	0.002	-0.004	0.0	-5.0	98.0	98.0	0.00
Line22	0.040	-0.022	-0.040	0.022	0.0	-0.3	98.0	98.0	0.00
Line23	0.035	-0.025	-0.035	0.023	0.0	-1.7	98.0	98.0	0.00
Line24	0.017	-0.012	-0.017	0.011	0.0	-0.6	98.0	98.0	0.00
Line30	0.019	-0.011	-0.019	0.010	0.0	-1.3	98.0	98.0	0.00
Line25	0.013	-0.013	-0.013	0.013	0.0	-0.4	98.0	98.0	0.00
Line27	-0.009	0.008	0.009	-0.010	0.0	-2.2	98.0	98.0	0.00
Line28	0.005	-0.010	-0.005	0.004	0.0	-6.1	98.0	98.0	0.00

Project:	ETAP	Page:	11
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
Line29	0.002	-0.006	-0.002	-0.002	0.0	-7.1	98.0	98.0	0.00
Line31	0.014	-0.013	-0.014	0.009	0.0	-4.5	98.0	98.0	0.00
Line32	0.010	-0.011	-0.010	0.005	0.0	-5.8	98.0	98.0	0.00
Line36	0.831	0.005	-0.830	-0.011	0.5	-5.5	98.1	98.0	0.05
Line37	-0.009	-0.006	0.009	0.002	0.0	-4.1	98.0	98.0	0.00
Line38	0.821	0.009	-0.820	-0.018	0.7	-8.5	98.0	97.9	0.08
Line39	0.810	0.011	-0.810	-0.013	0.1	-1.4	97.9	97.9	0.01
Line40	0.023	0.003	-0.023	-0.009	0.0	-5.9	97.9	97.9	0.00
Line42	0.787	0.010	-0.787	-0.014	0.3	-4.0	97.9	97.9	0.04
Line41	0.009	0.000	-0.009	-0.005	0.0	-5.3	97.9	97.9	0.00
Line43	0.080	0.015	-0.080	-0.024	0.0	-9.1	97.9	97.9	0.02
Line55	0.708	-0.001	-0.707	-0.002	0.2	-3.4	97.9	97.9	0.03
Line44	-0.006	-0.004	0.006	-0.001	0.0	-4.1	97.9	97.9	0.00
Line45	0.074	0.025	-0.074	-0.031	0.0	-6.2	97.9	97.9	0.01
Line46	0.072	0.030	-0.072	-0.032	0.0	-1.9	97.9	97.9	0.00
Line47	0.068	0.032	-0.068	-0.032	0.0	-0.8	97.9	97.8	0.00
Line48	0.003	0.000	-0.003	-0.002	0.0	-2.0	97.9	97.9	0.00
Line49	0.060	0.027	-0.060	-0.029	0.0	-1.5	97.8	97.8	0.00
Line50	0.041	0.017	-0.041	-0.018	0.0	-1.3	97.8	97.8	0.00
Line51	0.033	0.015	-0.033	-0.018	0.0	-3.2	97.8	97.8	0.00
Line52	0.008	0.003	-0.008	-0.005	0.0	-1.9	97.8	97.8	0.00
Line53	0.022	0.011	-0.022	-0.013	0.0	-1.4	97.8	97.8	0.00
Line54	0.009	0.005	-0.009	-0.006	0.0	-0.7	97.8	97.8	0.00
Line56	-0.008	-0.005	0.008	-0.002	0.0	-6.5	97.9	97.9	0.00
Line57	0.700	0.004	-0.700	-0.004	0.0	-0.3	97.9	97.9	0.00
Line58	0.676	-0.011	-0.676	0.000	0.6	-10.4	97.9	97.8	0.08
Line59	-0.006	-0.004	0.006	0.000	0.0	-3.2	97.8	97.8	0.00
Line60	0.670	-0.001	-0.670	0.000	0.0	-0.3	97.8	97.8	0.00
Line61	0.013	-0.001	-0.013	-0.001	0.0	-2.2	97.8	97.8	0.00
Line63	0.657	0.001	-0.657	-0.007	0.3	-5.5	97.8	97.7	0.04
Line62	0.005	-0.004	-0.005	-0.003	0.0	-7.1	97.8	97.8	0.00
Line64	0.009	-0.002	-0.009	-0.005	0.0	-7.6	97.7	97.7	0.00
Line65	0.648	0.009	-0.648	-0.012	0.2	-3.3	97.7	97.7	0.02
Line66	-0.018	-0.011	0.018	0.009	0.0	-2.2	97.7	97.7	0.00
Line67	0.629	0.003	-0.629	-0.010	0.3	-6.8	97.7	97.7	0.05
Line68	0.018	-0.010	-0.018	0.007	0.0	-3.2	97.7	97.7	0.00
Line72	0.611	0.020	-0.610	-0.023	0.1	-3.2	97.7	97.6	0.02

Project:	ETAP	Page:	12
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
Line69	-0.005	-0.003	0.005	-0.001	0.0	-3.6	97.7	97.7	0.00
Line70	0.014	-0.006	-0.014	0.003	0.0	-2.9	97.7	97.7	0.00
Line71	-0.003	-0.002	0.003	-0.010	0.0	-12.0	97.7	97.7	0.00
Line73	0.599	0.016	-0.599	-0.022	0.2	-5.6	97.6	97.6	0.04
Line74	0.592	0.017	-0.592	-0.020	0.1	-3.0	97.6	97.6	0.02
Line75	0.587	0.018	-0.587	-0.024	0.2	-5.8	97.6	97.5	0.04
Line76	0.008	-0.006	-0.008	0.005	0.0	-1.2	97.5	97.5	0.00
Line81	0.579	0.030	-0.579	-0.038	0.3	-8.0	97.5	97.5	0.06
Line78	0.001	-0.009	-0.001	-0.001	0.0	-10.1	97.5	97.5	0.00
Line82	-0.002	-0.001	0.002	0.000	0.0	-1.2	97.5	97.5	0.00
Line83	0.577	0.038	-0.577	-0.044	0.2	-5.8	97.5	97.4	0.04
Line85	0.572	0.041	-0.572	-0.050	0.4	-9.2	97.4	97.4	0.06
Line86	0.011	-0.007	-0.011	0.007	0.0	-0.1	97.4	97.4	0.00
Line88	0.561	0.057	-0.561	-0.073	0.3	-15.9	97.4	97.3	0.07
Line87	0.007	-0.010	-0.007	0.008	0.0	-1.5	97.4	97.4	0.00
Line89	0.002	-0.011	-0.002	-0.001	0.0	-12.3	97.4	97.4	0.00
Line90	0.000	0.000	0.000	-0.005	0.0	-4.6	97.3	97.3	0.00
Line91	0.561	0.078	-0.561	-0.078	0.0	-0.5	97.3	97.3	0.00
Line92	0.003	0.002	-0.003	-0.002	0.0	-0.1	97.3	97.3	0.00
Line93	0.558	0.076	-0.557	-0.080	0.1	-3.9	97.3	97.3	0.02
Line77	0.556	0.096	-0.556	-0.101	0.1	-5.5	97.3	97.3	0.02
Line94	0.001	-0.016	-0.001	-0.001	0.0	-16.4	97.3	97.3	0.00
Line79	-0.126	-0.078	0.126	0.076	0.0	-2.6	97.3	97.3	0.01
Line80	0.430	0.026	-0.430	-0.027	0.0	-0.9	97.3	97.3	0.00
Line84	0.011	-0.007	-0.011	0.002	0.0	-5.3	97.3	97.3	0.00
Line98	0.419	0.034	-0.419	-0.035	0.0	-1.7	97.3	97.3	0.00
Line95	0.004	0.002	-0.004	-0.003	0.0	-0.5	97.3	97.3	0.00
Line96	0.007	-0.004	-0.007	0.001	0.0	-2.9	97.3	97.3	0.00
Line97	0.002	-0.004	-0.002	-0.001	0.0	-5.3	97.3	97.3	0.00
Line99	0.029	0.018	-0.029	-0.018	0.0	-0.2	97.3	97.3	0.00
Line100	0.390	0.018	-0.390	-0.029	0.1	-11.7	97.3	97.2	0.03
Line101	0.006	0.004	-0.006	-0.004	0.0	-0.4	97.2	97.2	0.00
Line102	0.383	0.026	-0.383	-0.056	0.3	-30.4	97.2	97.1	0.08
Line103	0.019	0.001	-0.019	-0.002	0.0	-1.1	97.1	97.1	0.00
Line108	0.364	0.055	-0.364	-0.057	0.0	-2.2	97.1	97.1	0.01
Line104	0.011	-0.003	-0.011	0.000	0.0	-3.2	97.1	97.1	0.00
Line107	-0.021	-0.013	0.021	0.011	0.0	-1.6	97.1	97.1	0.00

Project:	ETAP	Page:	13
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line109	0.343	0.046	-0.343	-0.048	0.0	-1.6	97.1	97.1	0.00
Line110	-0.025	-0.015	0.025	0.015	0.0	-0.2	97.1	97.1	0.00
Line111	0.319	0.033	-0.319	-0.035	0.0	-2.4	97.1	97.1	0.01
Line112	0.052	0.028	-0.052	-0.029	0.0	-1.1	97.1	97.1	0.00
Line114	0.267	0.007	-0.267	-0.010	0.0	-3.1	97.1	97.1	0.01
Line113	0.038	0.021	-0.038	-0.023	0.0	-2.8	97.1	97.1	0.00
Line116	0.159	0.097	-0.159	-0.097	0.0	-0.4	97.1	97.1	0.00
Line119	0.108	-0.087	-0.108	0.086	0.0	-1.4	97.1	97.1	0.00
Line117	0.159	0.097	-0.159	-0.099	0.0	-1.3	97.1	97.1	0.01
Line118	0.000	0.000	0.000	0.000	0.0	-0.1	97.1	97.1	0.00
Line120	0.090	-0.096	-0.090	0.084	0.0	-12.2	97.1	97.1	0.00
Line121	0.005	-0.003	-0.005	-0.001	0.0	-3.7	97.1	97.1	0.00
Line124	0.085	-0.082	-0.085	0.080	0.0	-1.5	97.1	97.1	0.00
Line122	0.002	0.000	-0.002	-0.001	0.0	-1.9	97.1	97.1	0.00
Line123	0.007	-0.004	-0.007	0.004	0.0	-0.2	97.1	97.1	0.00
Line128	0.078	-0.076	-0.078	0.069	0.0	-7.3	97.1	97.1	0.00
Line125	0.004	-0.006	-0.004	0.003	0.0	-2.8	97.1	97.1	0.00
Line126	-0.002	-0.001	0.002	-0.002	0.0	-3.6	97.1	97.1	0.00
Line127	0.001	-0.001	-0.001	-0.001	0.0	-1.6	97.1	97.1	0.00
Line129	0.010	-0.016	-0.010	0.014	0.0	-1.7	97.1	97.1	0.00
Line134	0.068	-0.053	-0.068	0.052	0.0	-1.4	97.1	97.1	0.00
Line130	0.008	-0.016	-0.008	0.014	0.0	-2.1	97.1	97.1	0.00
Line131	0.006	-0.012	-0.006	-0.002	0.0	-14.1	97.1	97.1	0.00
Line132	0.001	-0.001	-0.001	-0.001	0.0	-2.4	97.1	97.1	0.00
Line133	0.003	0.000	-0.003	-0.002	0.0	-1.8	97.1	97.1	0.00
Line135	-0.007	-0.004	0.007	0.003	0.0	-1.4	97.1	97.1	0.00
Line136	0.061	-0.055	-0.061	0.051	0.0	-3.5	97.1	97.1	0.00
Line105	0.013	0.003	-0.013	-0.005	0.0	-2.1	97.1	97.1	0.00
Line138	0.048	-0.054	-0.048	0.050	0.0	-4.0	97.1	97.1	0.00
Line115	-0.007	-0.004	0.007	0.002	0.0	-2.6	97.1	97.1	0.00
Line137	0.007	0.004	-0.007	-0.004	0.0	-0.5	97.1	97.1	0.00
Line139	-0.016	-0.010	0.016	0.009	0.0	-0.6	97.1	97.1	0.00
Line140	0.032	-0.060	-0.032	0.057	0.0	-2.6	97.1	97.1	0.00
Line141	0.019	-0.002	-0.019	0.001	0.0	-1.1	97.1	97.1	0.00
Line158	0.013	-0.055	-0.013	0.044	0.0	-11.1	97.1	97.1	0.00
Line142	-0.012	-0.007	0.012	0.006	0.0	-1.0	97.1	97.1	0.00
Line143	0.007	-0.007	-0.007	0.003	0.0	-4.5	97.1	97.1	0.00

Project:	ETAP	Page:	14
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line149	0.013	-0.044	-0.013	0.032	0.0	-11.7	97.1	97.1	0.00
Cable2	0.678	0.425	-0.678	-0.425	0.0	0.0	97.2	97.2	0.01
Cable3	0.791	0.482	-0.791	-0.481	0.1	0.0	97.2	97.2	0.01
Cable14	0.000	-0.004	0.000	0.004	0.0	0.0	97.2	97.2	0.00
Cable15	3.332	2.065	-3.330	-2.063	2.5	1.8	97.2	97.1	0.08
Cable16	0.282	0.167	-0.282	-0.167	0.0	0.0	97.2	97.2	0.00
Cable18	0.261	0.113	-0.261	-0.113	0.0	0.0	97.2	97.2	0.00
Cable13	0.502	0.306	-0.502	-0.306	0.2	0.1	97.2	97.2	0.04
Line162	0.172	0.107	-0.172	-0.107	0.1	-0.3	97.2	97.1	0.09
Line163	0.116	0.069	-0.116	-0.070	0.2	-0.9	97.2	97.0	0.17
Line164	-0.010	-0.006	0.010	0.006	0.0	-0.5	97.0	97.0	0.01
Line165	0.106	0.064	-0.106	-0.064	0.0	-0.1	97.0	97.0	0.02
Line166	0.096	0.058	-0.096	-0.059	0.2	-0.6	97.0	96.9	0.15
Line167	-0.004	-0.002	0.004	0.002	0.0	-0.1	96.9	96.9	0.00
Line168	0.092	0.056	-0.092	-0.057	0.2	-0.6	96.9	96.7	0.16
Line169	0.058	0.036	-0.058	-0.036	0.0	-0.2	96.7	96.7	0.03
Cable4	0.632	0.397	-0.632	-0.397	0.1	0.0	97.2	97.2	0.01
Cable5	0.455	0.287	-0.455	-0.287	0.0	0.0	97.2	97.2	0.00
Cable6	0.359	0.228	-0.359	-0.227	0.1	0.1	97.2	97.1	0.04
Cable7	0.258	0.165	-0.258	-0.165	0.1	0.0	97.1	97.1	0.02
Cable8	0.081	0.055	-0.081	-0.055	0.0	0.0	97.1	97.1	0.00
Cable9	-0.030	-0.014	0.030	0.014	0.0	0.0	97.1	97.1	0.00
Cable11	-0.191	-0.113	0.191	0.113	0.0	0.0	97.1	97.1	0.01
Cable12	-0.416	-0.253	0.416	0.253	0.1	0.1	97.1	97.2	0.03
Line170	0.000	-0.004	0.000	0.004	0.0	-0.6	97.2	97.2	0.00
Line171	0.000	-0.004	0.000	0.000	0.0	-3.6	97.2	97.2	0.00
Line172	3.330	2.063	-3.324	-2.059	5.7	4.8	97.1	96.9	0.18
Line174	3.192	1.977	-3.121	-1.917	71.3	60.2	96.9	94.6	2.39
Line175	0.041	0.025	-0.041	-0.025	0.0	0.0	94.6	94.6	0.00
Line176	3.080	1.891	-2.944	-1.776	136.0	114.9	94.6	89.9	4.61
Line177	-0.005	-0.003	0.005	0.002	0.0	-0.6	89.9	89.9	0.01
Line178	2.939	1.774	-2.769	-1.697	170.6	77.5	89.9	85.1	4.88
Line179	-0.045	-0.028	0.045	0.028	0.0	-0.1	85.1	85.1	0.01
Line180	2.724	1.669	-2.622	-1.622	102.5	46.6	85.1	82.1	2.98
Line181	-2.447	-1.516	2.456	1.520	9.3	4.2	81.8	82.1	0.29
Line182	0.166	0.102	-0.166	-0.102	0.1	0.0	82.1	82.0	0.04
Line183	0.095	0.058	-0.095	-0.058	0.1	-0.1	82.0	82.0	0.05

Project:	ETAP	Page:	15
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
Line184	0.054	0.033	-0.054	-0.033	0.0	-0.3	82.0	81.9	0.06
Line185	-0.003	-0.002	0.003	0.001	0.0	-0.1	81.9	81.9	0.00
Line186	0.051	0.032	-0.051	-0.032	0.0	-0.2	81.9	81.9	0.02
Line187	0.282	0.167	-0.282	-0.167	0.3	0.0	97.2	97.1	0.10
Line188	0.158	0.098	-0.158	-0.098	0.0	0.0	97.1	97.1	0.01
Line189	0.124	0.069	-0.123	-0.071	0.4	-1.7	97.1	96.8	0.33
Line190	0.117	0.067	-0.117	-0.068	0.2	-0.8	96.8	96.6	0.15
Line191	0.107	0.062	-0.107	-0.062	0.1	-0.6	96.6	96.5	0.11
Line192	-0.004	-0.002	0.004	0.002	0.0	-0.1	96.5	96.5	0.00
Line193	0.103	0.060	-0.103	-0.060	0.1	-0.4	96.5	96.4	0.10
Line194	0.080	0.046	-0.080	-0.047	0.2	-1.0	96.4	96.2	0.22
Line195	-0.011	-0.007	0.011	0.007	0.0	0.0	96.2	96.2	0.00
Line196	0.010	0.006	-0.010	-0.006	0.0	-0.7	96.2	96.2	0.02
Line197	0.058	0.035	-0.058	-0.035	0.0	-0.3	96.2	96.2	0.04
Line198	0.037	0.021	-0.037	-0.022	0.0	-0.4	96.2	96.1	0.04
Line199	0.017	0.010	-0.017	-0.011	0.0	-0.9	96.1	96.1	0.04
Cable10	0.182	0.110	-0.182	-0.110	0.0	0.0	96.8	96.8	0.00
Cable19	0.024	0.059	-0.024	-0.059	0.0	0.0	96.8	96.8	0.00
Cable20	0.883	0.546	-0.882	-0.546	0.3	0.2	96.8	96.8	0.04
Cable25	0.856	0.530	-0.856	-0.530	0.0	0.0	96.8	96.8	0.01
Cable30	0.229	0.140	-0.229	-0.140	0.0	0.0	96.8	96.8	0.00
Cable31	0.048	0.029	-0.048	-0.029	0.0	0.0	96.8	96.8	0.00
Cable32	0.000	0.000	0.000	0.000			96.8	96.8	
33/11kV I	-1.291	-0.800	1.294	0.835	2.9	34.5	96.8	98.1	1.33
33/11kV II	-0.930	-0.614	0.932	0.636	1.8	22.0	96.8	98.0	1.20
Line200	1.303	0.806	-1.294	-0.835	9.3	-28.4	98.9	98.1	0.78
Line202	0.261	0.113	-0.261	-0.113	0.2	-0.1	97.2	97.1	0.10
Line203	0.159	0.098	-0.159	-0.098	0.0	0.0	97.1	97.1	0.00
Line204	0.102	0.015	-0.102	-0.015	0.0	-0.2	97.1	97.1	0.02
Line205	0.000	0.000	0.000	-0.001	0.0	-0.8	97.1	97.1	0.00
Line206	0.102	0.016	-0.102	-0.017	0.3	-1.3	97.1	96.8	0.31
Line207	0.024	0.059	-0.024	-0.060	0.0	-1.0	96.8	96.7	0.07
Line208	-0.074	-0.001	0.074	0.000	0.0	-0.2	96.7	96.7	0.02
Line209	-0.093	-0.012	0.093	0.012	0.0	-0.4	96.7	96.8	0.04
Line210	0.009	0.005	-0.009	-0.005	0.0	-0.2	96.8	96.8	0.00
Line173	0.182	0.110	-0.182	-0.110	0.1	-0.1	96.8	96.8	0.04
Line211	0.148	0.089	-0.147	-0.089	0.0	-0.1	96.8	96.7	0.02

Project:	ETAP	Page:	16
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
Line212	0.034	0.021	-0.034	-0.021	0.0	-0.1	96.8	96.7	0.01
Line213	-0.023	-0.014	0.023	0.014	0.0	-0.1	96.7	96.7	0.00
Line214	0.124	0.075	-0.124	-0.075	0.0	0.0	96.7	96.7	0.01
Line215	0.087	0.051	-0.087	-0.052	0.0	-0.1	96.7	96.7	0.02
Line216	0.045	0.026	-0.045	-0.026	0.0	-0.6	96.7	96.7	0.04
Line217	-0.025	-0.015	0.025	0.014	0.0	-1.5	96.6	96.7	0.05
Line218	0.021	0.013	-0.021	-0.013	0.0	-0.1	96.7	96.7	0.00
Cable21	0.654	0.405	-0.654	-0.405	0.1	0.0	96.8	96.7	0.01
Cable22	0.433	0.268	-0.433	-0.268	0.1	0.1	96.7	96.7	0.02
Cable23	0.221	0.136	-0.221	-0.136	0.0	0.0	96.7	96.7	0.01
Cable24	0.014	0.009	-0.014	-0.009	0.0	0.0	96.7	96.7	0.00
Line219	0.018	0.010	-0.018	-0.011	0.0	-0.7	96.7	96.7	0.02
Line220	0.856	0.530	-0.854	-0.529	1.7	1.3	96.8	96.6	0.21
Line221	-0.170	-0.106	0.170	0.105	0.1	-0.2	96.5	96.6	0.06
Line222	0.684	0.424	-0.681	-0.422	2.9	2.0	96.6	96.1	0.45
Line223	-0.212	-0.131	0.212	0.131	0.0	0.0	96.1	96.1	0.01
Line224	0.469	0.290	-0.469	-0.290	0.3	0.2	96.1	96.1	0.07
Line225	-0.212	-0.131	0.212	0.131	0.0	0.0	96.1	96.1	0.00
Line226	0.257	0.159	-0.257	-0.159	0.1	0.0	96.1	96.0	0.04
Cable26	0.257	0.159	-0.257	-0.159	0.0	0.0	96.0	96.0	0.00
Cable27	0.128	0.080	-0.128	-0.080	0.0	0.0	96.0	96.0	0.00
Line234	-0.075	-0.047	0.075	0.046	0.0	-0.2	96.6	96.6	0.03
Line235	-0.081	-0.050	0.081	0.050	0.0	-0.2	96.6	96.7	0.03
Line236	-0.020	-0.012	0.020	0.012	0.0	-0.1	96.7	96.7	0.00
Line237	0.229	0.140	-0.228	-0.140	0.1	-0.1	96.8	96.7	0.05
Line238	0.209	0.128	-0.208	-0.128	0.1	-0.1	96.7	96.7	0.07
Line239	0.127	0.078	-0.127	-0.078	0.1	-0.2	96.7	96.6	0.05
Line240	0.052	0.032	-0.052	-0.032	0.0	-0.4	96.6	96.6	0.03
Line241	0.048	0.029	-0.048	-0.030	0.0	-0.9	96.8	96.7	0.06
Line106	0.008	-0.001	-0.008	-0.005	0.0	-6.3	97.1	97.1	0.00
Line144	0.006	-0.004	-0.006	0.002	0.0	-1.3	97.1	97.1	0.00
Line145	0.003	0.001	-0.003	-0.002	0.0	-0.7	97.1	97.1	0.00
Line146	0.003	-0.004	-0.003	0.002	0.0	-1.9	97.1	97.1	0.00
Line147	0.002	0.001	-0.002	-0.001	0.0	-0.3	97.1	97.1	0.00
Line148	0.001	-0.003	-0.001	0.000	0.0	-3.3	97.1	97.1	0.00
Line150	0.004	-0.009	-0.004	0.007	0.0	-2.2	97.1	97.1	0.00
Line154	0.008	-0.023	-0.008	0.020	0.0	-3.0	97.1	97.1	0.00

Project: **ETAP** Page: 17
 Location: 16.1.1C Date: 08-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESSD Gedu Config.: Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd
	MW	Mvar	MW	Mvar	kW	kvar	From	To	% Drop in Vmag
Line151	0.003	-0.007	-0.003	0.001	0.0	-6.5	97.1	97.1	0.00
Line152	0.003	0.001	-0.003	-0.002	0.0	-0.8	97.1	97.1	0.00
Line153	0.000	-0.002	0.000	0.000	0.0	-1.9	97.1	97.1	0.00
Line155	0.008	-0.020	-0.008	0.017	0.0	-3.0	97.1	97.1	0.00
Line156	0.000	0.000	0.000	0.000	0.0	-0.4	97.1	97.1	0.00
Line157	0.001	0.000	-0.001	-0.001	0.0	-0.8	97.1	97.1	0.00
Line159	0.007	-0.017	-0.007	0.014	0.0	-3.4	97.1	97.1	0.00
Line160	0.004	-0.015	-0.004	0.004	0.0	-11.7	97.1	97.1	0.00
Line161	0.001	-0.006	-0.001	-0.001	0.0	-6.4	97.1	97.1	0.00
Line26	0.005	-0.003	-0.005	-0.003	0.0	-5.7	98.0	98.0	0.00
Line33	0.001	0.000	-0.001	-0.001	0.0	-0.7	98.0	98.0	0.00
Line34	0.009	-0.005	-0.009	-0.003	0.0	-7.8	98.0	98.0	0.00
Line35	0.003	-0.001	-0.003	-0.002	0.0	-2.7	98.0	98.0	0.00
66/33/11kV	1.288	0.571	-1.285	-0.539	2.7	32.3	100.0	98.9	1.08
66/33/11kV	0.000	0.000	0.000	0.000			100.0	100.1	0.12
					574.9	5.2			

Project:	ETAP	Page:	18
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

Alert Summary Report

	% Alert Settings	Critical	Marginal
<u>Loading</u>			
Bus		100.0	95.0
Cable		100.0	95.0
Reactor		100.0	95.0
Line		100.0	95.0
Transformer		100.0	95.0
Panel		100.0	95.0
Protective Device		100.0	95.0
Generator		100.0	95.0
Inverter/Charger		100.0	95.0
<u>Bus Voltage</u>			
OverVoltage		110.0	105.0
UnderVoltage		90.0	95.0
<u>Generator Excitation</u>			
OverExcited (Q Max.)		100.0	95.0
UnderExcited (Q Min.)		100.0	

Critical Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus191	Bus	Under Voltage	11.000	kV	9.893	89.9	3-Phase
Bus192	Bus	Under Voltage	11.000	kV	9.89	89.9	3-Phase
Bus193	Bus	Under Voltage	11.000	kV	9.36	85.1	3-Phase
Bus194	Bus	Under Voltage	11.000	kV	9.36	85.1	3-Phase
Bus195	Bus	Under Voltage	11.000	kV	9.00	81.8	3-Phase
Bus196	Bus	Under Voltage	11.000	kV	9.03	82.1	3-Phase
Bus197	Bus	Under Voltage	11.000	kV	9.02	82.0	3-Phase
Bus198	Bus	Under Voltage	11.000	kV	9.02	82.0	3-Phase
Bus199	Bus	Under Voltage	11.000	kV	9.01	81.9	3-Phase
Bus200	Bus	Under Voltage	11.000	kV	9.01	81.9	3-Phase
Bus201	Bus	Under Voltage	11.000	kV	9.01	81.9	3-Phase

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus189	Bus	Under Voltage	11.000	kV	10.401	94.6	3-Phase

Project: **ETAP** Page: 19
Location: 16.1.1C Date: 08-12-2019
Contract: SN: BHUTANPWR
Engineer: Study Case: 2030 LFC Revision: Base
Filename: ESSD Gedu Config.: Normal

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus190	Bus	Under Voltage	11.000	kV	10.401	94.6	3-Phase


Project:	ETAP	Page:	20
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Gedu	Config.:	Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND


	MW	Mvar	MVA	% PF
Source (Swing Buses):	8.671	5.023	10.021	86.53 Lagging
Source (Non-Swing Buses):	0.000	0.000	0.000	
Total Demand:	8.671	5.023	10.021	86.53 Lagging
Total Motor Load:	2.007	1.244	2.361	85.00 Lagging
Total Static Load:	6.089	3.774	7.164	85.00 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	0.575	0.005		
System Mismatch:	0.000	0.000		

Number of Iterations: 4

One-Line Diagram - OLV1 (Load Flow Analysis)



Tsimasham substation



Project:	ETAP	Page:	1
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Tsimalakha	Config.:	Normal

Bus Loading Summary Report

Bus			Directly Connected Load				Total Bus Load				Percent Loading	
ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MVA	% PF	Amp	
Bus1	66.000								0.732	89.3	6.4	
Bus2	33.000								0.729	89.6	12.8	
Bus3	33.000								0.297	91.2	5.2	
Bus4	33.000								0.297	91.2	5.2	
Bus5	33.000		0.018	0.011					0.061	92.8	1.1	
Bus6	33.000		0.023	0.014					0.042	90.4	0.7	
Bus7	33.000		0.015	0.010					0.018	85.0	0.3	
Bus8	33.000		0.016	0.010					0.239	90.0	4.2	
Bus9	33.000		0.015	0.009					0.221	89.7	3.9	
Bus10	33.000								0.205	89.4	3.6	
Bus11	33.000		0.046	0.028					0.054	85.0	0.9	
Bus12	33.000		0.014	0.009					0.017	85.0	0.3	
Bus13	33.000								0.153	90.2	2.7	
Bus14	33.000		0.041	0.025					0.137	90.2	2.4	
Bus15	33.000								0.091	91.3	1.6	
Bus16	33.000								0.062	91.7	1.1	
Bus17	33.000		0.017	0.010					0.020	85.0	0.3	
Bus18	33.000		0.040	0.025					0.047	85.0	0.8	
Bus19	33.000		0.025	0.016					0.030	85.0	0.5	
Bus20	33.000								0.432	88.3	7.6	
Bus21	33.000		0.034	0.021					0.437	87.4	7.7	
Bus22	33.000		0.093	0.058					0.109	85.0	1.9	
Bus23	33.000		0.194	0.120					0.228	85.0	4.0	
Bus24	33.000								0.291	87.7	5.1	
Bus25	33.000		0.010	0.006					0.012	85.0	0.2	
Bus26	33.000								0.065	94.3	1.1	
Bus27	33.000		0.015	0.009					0.057	90.6	1.0	
Bus29	33.000		0.003	0.002					0.041	89.6	0.7	
Bus30	33.000		0.026	0.016					0.037	89.6	0.7	
Bus31	33.000		0.007	0.005					0.009	85.0	0.2	
Bus32	66.000								3.626	84.0	31.7	
Bus33	11.000								3.564	85.2	190.3	
Bus34	11.000								0.290	92.9	15.5	
Bus35	11.000		0.027	0.017					0.289	92.8	15.5	
Bus36	11.000		0.030	0.019					0.706	85.5	38.1	
Bus37	11.000		0.106	0.066					0.706	85.5	38.1	
Bus38	11.000		0.228	0.142					0.669	85.5	36.2	
Bus39	11.000								0.124	85.0	6.7	
Bus40	11.000								0.541	85.6	29.5	

Project:	ETAP	Page:	2
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Tsimalakha	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			Percent Loading	
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp		
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar				
Bus41		11.000								0.272	86.1	14.9	
Bus42		11.000			0.142	0.088				0.167	85.0	9.1	
Bus43		11.000			0.065	0.040				0.106	87.5	5.8	
Bus44		11.000			0.008	0.005				0.010	85.0	0.5	
Bus45		11.000								0.031	90.8	1.7	
Bus46		11.000			0.001	0.001				0.021	92.6	1.2	
Bus47		11.000								0.020	92.8	1.1	
Bus48		11.000			0.000	-				0.011	86.2	0.6	
Bus49		11.000			0.009	0.006				0.011	85.0	0.6	
Bus50		11.000			0.005	0.003				0.010	93.6	0.5	
Bus51		11.000			0.002	0.001				0.004	87.2	0.2	
Bus52		11.000			0.002	0.001				0.002	85.0	0.1	
Bus53		11.000								0.460	80.1	24.6	
Bus54		11.000								0.457	79.8	24.7	
Bus55		11.000								0.001	-	0.1	
Bus56		11.000										-	
Bus57		11.000								0.001	-	-	
Bus58		11.000										-	
Bus59		11.000										-	
Bus60		11.000								0.001	-	-	
Bus61		11.000										-	
Bus62		11.000								0.000	-	-	
Bus63		11.000										-	
Bus64		11.000								0.792	85.3	42.3	
Bus65		11.000								0.788	85.2	42.3	
Bus66		11.000			0.389	0.241				0.458	85.0	24.6	
Bus67		11.000			0.199	0.123				0.330	85.5	17.7	
Bus68		11.000			0.015	0.009				0.018	85.0	1.0	
Bus69		11.000								0.096	86.5	5.1	
Bus70		11.000			0.027	0.017				0.032	85.0	1.7	
Bus71		11.000								0.079	85.5	4.2	
Bus72		11.000			0.040	0.025				0.048	85.0	2.6	
Bus73		11.000								0.439	85.1	23.5	
Bus74		11.000								0.439	85.0	23.5	
Bus75		11.000			0.169	0.105				0.199	85.0	10.7	
Bus76		11.000			0.172	0.106				0.240	85.0	12.8	
Bus77		11.000			0.032	0.020				0.038	85.0	2.0	
Bus78		11.000								1.207	85.0	64.5	
Bus79		11.000								1.205	85.0	64.5	
Bus80		11.000								0.476	91.8	25.5	
Bus81		11.000			0.167	0.104				0.197	85.0	10.5	
Bus82		11.000								0.954	85.0	51.2	

Project:	ETAP	Page:	3
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filname:	ESSD Tsimalakha	Config.:	Normal

Bus	Directly Connected Load								Total Bus Load			
	Constant kVA		Constant Z		Constant I		Generic		MVA	% PF	Amp	Percent Loading
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar			
Bus83		11.000			0.148	0.092			0.953	85.0	51.2	
Bus84		11.000			0.661	0.410			0.778	85.0	41.8	
Bus85		11.000							0.736	79.7	39.4	
Bus86		11.000			0.044	0.027			0.052	85.0	2.8	
Bus87		11.000			0.324	0.201			0.382	85.0	20.4	

* Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:	ETAP	Page:	4
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Tsimalakha	Config.:	Normal

Branch Loading Summary Report

CKT / Branch	Cable & Reactor			Transformer						
	ID	Type	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	Loading (input)	Loading (output)		
							MVA	%	MVA	%
Cable1		Cable	274.79	5.22	1.90					
Cable2		Cable	274.79	7.59	2.76					
Cable3		Cable	229.86	15.48	6.73					
Cable4		Cable	301.98	24.57	8.14					
Cable5		Cable	338.03	42.31	12.52					
Cable6		Cable	229.86	23.47	10.21					
Cable7		Cable	301.98	64.46	21.34					
Cable8		Cable	301.98	20.38	6.75					
66/11kV I		Transformer				3.000	1.192	39.7	1.172	39.1
66/11kV II		Transformer				3.000	1.240	41.3	1.219	40.6
66/11kV III		Transformer				3.000	1.194	39.8	1.173	39.1
66/33kV		Transformer				7.875	0.732	9.3	0.729	9.3

* Indicates a branch with operating load exceeding the branch capability.

Project: **ETAP** Page: 5
 Location: **16.1.1C**
 Contract:
 Engineer: Study Case: 2030 LFC Date: 08-12-2019
 Filename: ESSD Tsimalakha SN: BHUTANPWR
 Revision: Base
 Config.: Normal

Branch Losses Summary Report

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
66/33kV	0.653	0.330	-0.653	-0.324	0.4	5.6	100.0	99.6	0.40
Cable1	0.271	0.122	-0.271	-0.122	0.0	0.0	99.6	99.6	0.00
Cable2	0.382	0.203	-0.382	-0.203	0.0	0.0	99.6	99.6	0.00
Line1	0.271	0.122	-0.271	-0.122	0.0	-0.1	99.6	99.6	0.00
Line2	0.056	0.018	-0.056	-0.023	0.0	-4.9	99.6	99.6	0.01
Line5	0.215	0.104	-0.215	-0.104	0.0	-0.1	99.6	99.6	0.00
Line3	0.038	0.011	-0.038	-0.018	0.0	-6.7	99.6	99.6	0.01
Line4	0.015	0.004	-0.015	-0.010	0.0	-5.7	99.6	99.6	0.00
Line6	0.199	0.094	-0.199	-0.098	0.0	-3.9	99.6	99.6	0.01
Line7	0.184	0.089	-0.184	-0.092	0.0	-3.6	99.6	99.6	0.01
Line8	0.046	0.028	-0.046	-0.028	0.0	-0.3	99.6	99.6	0.00
Line9	0.138	0.064	-0.138	-0.066	0.0	-1.7	99.6	99.6	0.00
Line10	-0.014	-0.009	0.014	0.008	0.0	-1.0	99.6	99.6	0.00
Line11	0.124	0.058	-0.124	-0.059	0.0	-1.0	99.6	99.6	0.00
Line12	0.083	0.034	-0.083	-0.037	0.0	-3.3	99.6	99.6	0.00
Line13	0.057	0.022	-0.057	-0.023	0.0	-0.7	99.6	99.6	0.00
Line16	0.025	0.015	-0.025	-0.016	0.0	-0.9	99.6	99.6	0.00
Line14	0.017	-0.002	-0.017	-0.010	0.0	-12.4	99.6	99.6	0.00
Line15	0.040	0.025	-0.040	-0.025	0.0	-0.2	99.6	99.6	0.00
Line17	0.382	0.203	-0.382	-0.213	0.1	-9.8	99.6	99.6	0.04
Line18	0.093	0.057	-0.093	-0.058	0.0	-1.0	99.6	99.6	0.00
Line19	0.255	0.135	-0.255	-0.140	0.0	-4.5	99.6	99.6	0.01
Line20	-0.194	-0.120	0.194	0.118	0.0	-1.8	99.5	99.6	0.00
Line21	0.061	0.021	-0.061	-0.022	0.0	-0.3	99.6	99.6	0.00
Line22	-0.010	-0.006	0.010	0.003	0.0	-3.7	99.5	99.6	0.00
Line23	0.051	0.019	-0.051	-0.024	0.0	-4.9	99.6	99.5	0.00
Line24	0.036	0.015	-0.036	-0.018	0.0	-3.3	99.5	99.5	0.00
Line26	0.033	0.016	-0.033	-0.017	0.0	-0.3	99.5	99.5	0.00
Line28	0.007	0.000	-0.007	-0.005	0.0	-4.2	99.5	99.5	0.00
66/11kV I	1.001	0.647	-0.999	-0.613	2.6	34.0	100.0	98.3	1.71
66/11kV II	1.042	0.673	-1.039	-0.638	2.7	35.4	100.0	98.3	1.71
66/11kV III	1.003	0.648	-1.000	-0.614	2.6	34.1	100.0	98.3	1.71
Cable3	0.269	0.107	-0.269	-0.107	0.0	0.0	98.3	98.3	0.01
Cable4	0.369	0.275	-0.369	-0.275	0.0	0.0	98.3	98.3	0.01

Project: **ETAP** Page: 6
 Location: **16.1.1C**
 Contract:
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESSD Tsimalakha Config.: Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Cable5	0.675	0.414	-0.675	-0.414	0.1	0.1	98.3	98.3	0.01
Cable6	0.374	0.231	-0.374	-0.231	0.0	0.0	98.3	98.3	0.01
Cable7	1.026	0.635	-1.026	-0.635	0.1	0.1	98.3	98.3	0.01
Cable8	0.324	0.201	-0.324	-0.201	0.0	0.0	98.3	98.3	0.01
Line27	0.269	0.107	-0.268	-0.107	1.3	-0.2	98.3	97.8	0.49
Line29	0.241	0.090	-0.239	-0.091	1.5	-0.5	97.8	97.2	0.61
Line30	0.604	0.366	-0.603	-0.366	0.5	0.2	97.2	97.1	0.08
Line46	-0.365	-0.275	0.365	0.275	0.0	0.0	97.2	97.2	0.01
Line31	0.573	0.347	-0.572	-0.347	1.3	0.5	97.1	96.9	0.21
Line32	0.106	0.065	-0.106	-0.066	0.0	0.0	96.9	96.9	0.01
Line33	0.466	0.281	-0.463	-0.280	3.1	0.9	96.9	96.3	0.61
Line34	0.235	0.139	-0.235	-0.139	0.3	-0.1	96.3	96.2	0.10
Line35	0.093	0.051	-0.093	-0.051	0.1	-0.3	96.2	96.1	0.08
Line36	0.142	0.088	-0.142	-0.088	0.0	0.0	96.2	96.2	0.00
Line37	0.028	0.011	-0.028	-0.013	0.0	-1.8	96.1	96.0	0.12
Line38	-0.008	-0.005	0.008	0.005	0.0	-0.1	96.0	96.0	0.00
Line39	0.020	0.008	-0.020	-0.008	0.0	-0.2	96.0	96.0	0.01
Line40	0.019	0.007	-0.019	-0.008	0.0	-0.1	96.0	96.0	0.00
Line41	0.010	0.005	-0.010	-0.006	0.0	-0.9	96.0	96.0	0.02
Line43	0.009	0.003	-0.009	-0.003	0.0	-0.7	96.0	96.0	0.01
Line42	0.009	0.006	-0.009	-0.006	0.0	-0.3	96.0	95.9	0.00
Line44	0.004	0.000	-0.004	-0.002	0.0	-2.0	96.0	95.9	0.02
Line45	0.002	0.001	-0.002	-0.001	0.0	-0.2	95.9	95.9	0.00
Line47	0.369	0.275	-0.365	-0.274	3.9	1.3	98.3	97.2	1.10
Line48	0.000	-0.001	0.000	0.001	0.0	-0.1	97.2	97.2	0.00
Line49	0.000	0.000	0.000	0.000	0.0	-0.1	97.2	97.2	0.00
Line50	0.000	-0.001	0.000	0.001	0.0	0.0	97.2	97.2	0.00
Line51	0.000	0.000	0.000	0.000	0.0	-0.1	97.2	97.2	0.00
Line52	0.000	-0.001	0.000	0.001	0.0	-0.2	97.2	97.2	0.00
Line53	0.000	0.000	0.000	0.000	0.0	0.0	97.2	97.2	0.00
Line54	0.000	-0.001	0.000	0.000	0.0	-0.4	97.2	97.2	0.00
Line55	0.000	0.000	0.000	0.000	0.0	0.0	97.2	97.2	0.00
Line56	0.000	0.000	0.000	0.000	0.0	-0.1	97.2	97.2	0.00
Line57	0.675	0.414	-0.671	-0.413	3.9	1.5	98.3	97.7	0.53
Line58	0.390	0.241	-0.389	-0.241	0.3	0.1	97.7	97.7	0.06
Line59	0.282	0.171	-0.282	-0.171	0.2	0.0	97.7	97.7	0.05
Line60	0.083	0.048	-0.083	-0.048	0.0	-0.1	97.7	97.7	0.01

Project: **ETAP** Page: 7
 Location: 16.1.1C Date: 08-12-2019
 Contract: SN: BHUTANPWR
 Engineer: Study Case: 2030 LFC Revision: Base
 Filename: ESSD Tsimalakha Config.: Normal

Branch ID	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop in Vmag
	MW	Mvar	MW	Mvar	kW	kvar	From	To	
Line61	-0.015	-0.009	0.015	0.007	0.0	-2.3	97.6	97.7	0.05
Line62	0.068	0.041	-0.068	-0.041	0.0	-0.2	97.7	97.7	0.03
Line63	-0.027	-0.017	0.027	0.017	0.0	-0.1	97.6	97.7	0.01
Line64	0.041	0.024	-0.040	-0.025	0.0	-0.7	97.7	97.6	0.07
Line65	0.374	0.231	-0.373	-0.231	0.7	0.2	98.3	98.1	0.19
Line66	0.170	0.105	-0.169	-0.105	0.2	-0.2	98.1	98.0	0.13
Line67	0.204	0.126	-0.204	-0.126	0.0	0.0	98.1	98.1	0.00
Line68	0.032	0.020	-0.032	-0.020	0.0	0.0	98.1	98.1	0.00
Line69	1.026	0.635	-1.025	-0.634	1.2	0.9	98.3	98.2	0.13
Line71	0.437	0.189	-0.437	-0.189	0.9	0.2	98.2	98.0	0.20
Line76	0.588	0.445	-0.587	-0.444	1.1	0.7	98.2	98.0	0.19
Line70	0.167	0.104	-0.167	-0.104	0.0	0.0	98.0	97.9	0.03
Line72	0.269	0.086	-0.269	-0.086	0.3	-0.1	98.0	97.9	0.10
Line73	0.811	0.502	-0.811	-0.502	0.4	0.2	97.9	97.8	0.05
Line77	-0.542	-0.417	0.542	0.417	0.6	0.3	97.9	98.0	0.11
Line74	0.662	0.410	-0.661	-0.410	0.7	0.2	97.8	97.7	0.09
Line78	0.044	0.027	-0.044	-0.027	0.0	-0.2	98.0	97.9	0.02
					31.6	24.0			

Project:	ETAP	Page:	8
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Tsimalakha	Config.:	Normal

Alert Summary Report

	% Alert Settings	
	Critical	Marginal
<u>Loading</u>		
Bus	100.0	95.0
Cable	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
<u>Bus Voltage</u>		
OverVoltage	110.0	105.0
UnderVoltage	90.0	95.0
<u>Generator Excitation</u>		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

Project:	ETAP	Page:	9
Location:	16.1.1C	Date:	08-12-2019
Contract:		SN:	BHUTANPWR
Engineer:	Study Case: 2030 LFC	Revision:	Base
Filename:	ESSD Tsimalakha	Config.:	Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	3.699	2.297	4.355	84.95 Lagging
Source (Non-Swing Buses):	0.000	0.000	0.000	
Total Demand:	3.699	2.297	4.355	84.95 Lagging
Total Motor Load:	0.000	0.000	0.000	
Total Static Load:	3.668	2.273	4.315	85.00 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	0.032	0.024		
System Mismatch:	0.000	0.000		

Number of Iterations: 3

Annexure 5: Feeder Wise Reliability Indices

Sl.No.	Year	Month	Reliability Indices	11 KV THPA-Polythene feeder	11 KV Karbarey-Ramety Feeder	11 KV Tading Rural Feeder	11 KV Pepsi BPC Colony Feeder	11 KV New Hospital Feeder
1	2017	January	SAIFI	0.02	0.13	0.19	0.06	
			SAIDI	0.02	0.04	0.75	0.13	
2		February	SAIFI	0.02	0.32			
			SAIDI	0.01	0.08			
3		March	SAIFI	0.02	0.42	0.27		
			SAIDI	0.00	0.32	0.02		
4		April	SAIFI	0.01	0.21	0.34		
			SAIDI	0.00	0.09	0.21		
5		May	SAIFI	0.01	1.93	0.13		
			SAIDI	0.02	1.65	0.02		
6		June	SAIFI		1.10	0.86		
			SAIDI		0.60	0.59		
7		July	SAIFI	0.02	0.54	0.39		
			SAIDI	0.01	0.70	0.37		
8		August	SAIFI	0.03	0.54	0.72	0.09	
			SAIDI	0.02	0.75	1.72	0.03	
9		September	SAIFI			0.52	0.06	0.00
			SAIDI			0.46	0.16	0.01
10		October	SAIFI		0.27	0.39		
			SAIDI		0.11	0.18		
11		November	SAIFI	0.01		0.13		
			SAIDI	0.01		0.10		
12		December	SAIFI			0.07	0.06	0.00
		Total		SAIFI	0.12	5.47	4.01	0.28
				SAIDI	0.10	4.35	4.49	0.34
								0.01
1	2018	January	SAIFI		0.20	0.13		
			SAIDI		0.08	0.44		
2		February	SAIFI		0.14	0.26	0.06	
			SAIDI		0.03	0.15	0.79	
3		March	SAIFI		0.80	1.41		
			SAIDI		0.86	0.78		
4		April	SAIFI	0.01	0.99	0.70		
			SAIDI	0.01	0.61	0.95		
5		May	SAIFI	0.08	1.44	1.84	0.27	0.01
			SAIDI	0.04	4.10	5.12	0.14	0.00
6		June	SAIFI	0.21	2.74	3.97	0.75	0.01
			SAIDI	0.07	2.69	6.59	0.24	0.00
7		July	SAIFI	0.01	0.65	1.58	0.06	
			SAIDI	0.07	0.66	1.93	0.07	
8		August	SAIFI	0.06	0.91	1.75	0.06	
			SAIDI	0.18	0.59	2.03	0.03	
9		September	SAIFI	0.03	1.41	1.23	0.31	
			SAIDI	0.71	3.03	1.79	0.40	
10		October	SAIFI	0.02	0.57	1.39	0.07	
			SAIDI	0.03	0.61	1.80	0.16	
11		November	SAIFI		0.19	0.31	0.03	
			SAIDI		0.76	0.14	0.01	
12		December	SAIFI	0.02	0.13	0.36		
		Total		SAIFI	0.43	10.17	14.93	1.60
				SAIDI	1.11	14.13	22.02	1.86
		Overall total		SAIFI	0.28	7.82	9.47	0.94
				SAIDI	0.61	9.24	13.25	1.10
								0.00

Sl.No.	Year	Month	Reliability Indices	11 KV Helipad linked feeder	33 KV Druk Iron & Steel feeder	33 kV Sector II	33 kV Sector II	33 kV Serina Bosokha	11 kV Gurungdara Rural
1	2017	January	SAIFI	0.03	0.00			1.48	
2		February	SAIFI	0.06			0.30	1.04	0.07
3		March	SAIFI	0.03			0.01	1.98	0.37
4		April	SAIFI	0.03	0.00		0.65	1.89	0.04
5		May	SAIFI	0.07	0.00	0.32		4.10	0.04
6		June	SAIFI		0.00		0.32	1.76	0.18
7		July	SAIFI	0.03			5.05	2.30	
8		August	SAIFI		0.00	2.84		0.37	0.03
9		September	SAIFI	0.10	0.00			1.74	
10		October	SAIFI	0.16		0.32		1.01	
11		November	SAIFI					0.36	0.03
12		December	SAIFI	0.06			0.94	0.09	
	Total		SAIFI	0.57	0.00	3.48	7.25	17.27	0.49
	Total		SAIDI	4.97	0.02	0.53	0.42	23.69	1.41
1	2018	January	SAIFI	0.00				0.64	
2		February	SAIFI					0.31	
3		March	SAIFI	0.03				1.37	
4		April	SAIFI	0.06		0.30		2.07	
5		May	SAIFI	0.07				4.25	
6		June	SAIFI		0.28			2.40	0.03
7		July	SAIFI	0.77		0.30	1.83	0.98	0.20
8		August	SAIFI	0.25		2.55	1.44	5.06	0.28
9		September	SAIFI		0.71		2.55	4.81	0.05
10		October	SAIFI	0.06		3.33	0.71	3.09	0.03
11		November	SAIFI	0.24		0.97	0.71	8.11	0.00
12		December	SAIFI		0.06		1.03	1.58	
	Total		SAIFI	1.34	-	6.02	13.74	22.70	0.47
	Overall total		SAIDI	0.84	-	6.13	9.33	53.74	0.70
	Overall total		SAIFI	0.96	0.00	4.75	10.49	19.99	0.48
	Overall total		SAIDI	2.91	0.01	3.33	4.88	38.72	1.06

Sl.No.	Year	Month	Reliability Indices	11 kV TCBL Fdr	11 kV Industrial area upper Terrace	11 kV Industrial area lower Terrace	11 kV Druk Cement Fdr	11 kV Bhutan Steel Fdr	11 kV Malbase Colony Fdr
1	2017	January	SAIFI	0.00		0.00	0.04		
2		February	SAIDI	0.01		0.00	0.04		
3			SAIFI	0.00	0.00	0.00	0.04	0.00	
4		March	SAIDI	0.02	0.00	0.01	0.23	0.00	
5			SAIFI				0.04		
6		April	SAIDI				0.02		
7			SAIFI	0.01	0.00				
8		May	SAIDI	0.01	0.00		0.16	0.00	
9			SAIFI				0.29	0.00	
10		June	SAIDI						
11			SAIFI	0.00	0.00	0.00			
12		July	SAIDI	0.01	0.00	0.00			
			SAIFI				0.00	0.01	
		August	SAIDI				0.00	0.01	
9			SAIFI			0.01	0.12	0.00	
10		September	SAIDI			0.07	0.12	0.01	
11			SAIFI		0.00		0.04	0.00	
12		October	SAIDI		0.00		0.01	0.00	
			SAIFI						
		November	SAIDI		0.00	0.00		0.00	
11			SAIFI		0.00			0.00	
12		December	SAIDI		0.00				
			SAIFI	0.02	0.00	0.02	0.55	0.00	0.01
			SAIDI	0.04	0.01	0.10	0.73	0.01	0.01
1	2018	January	SAIFI	0.00	0.00	0.00	0.16	0.00	
2		February	SAIDI	0.01	0.00	0.02	0.34	0.00	
3		March	SAIFI				0.04		
4			SAIDI				0.13		
5		April	SAIFI		0.00		0.04	0.00	
6			SAIDI		0.00		0.01	0.00	
7		May	SAIFI	0.00	0.00	0.00	0.11	0.00	
8			SAIDI	0.01	0.00	0.02	0.82	0.00	
9		June	SAIFI	0.00	0.00		0.11		0.01
10			SAIDI	0.00	0.00		0.04		0.03
11		July	SAIFI	0.00	0.00	0.00	0.11	0.00	0.01
12			SAIDI	0.00	0.00	0.00	0.20	0.00	0.01
		August	SAIFI		0.00				
8			SAIDI		0.00				
9		September	SAIFI		0.00		0.08	0.00	0.01
10			SAIDI		0.00		0.14	0.00	0.03
11		October	SAIFI	0.00			0.04		
12			SAIDI	0.00			0.04		
		November	SAIFI	0.00			0.08		
11			SAIDI	0.00			0.02		
12		December	SAIFI				0.15		
			SAIDI				0.25		
		Total	SAIFI	0.01	0.00	0.01	0.92	0.00	0.03
			SAIDI	0.03	0.01	0.04	2.01	0.00	0.07
		Overall total	SAIFI	0.02	0.00	0.02	0.73	0.00	0.02
			SAIDI	0.04	0.01	0.07	1.37	0.01	0.04

Sl.No.	Year	Month	Reliability Indices	11 kV Malbase Burkey Fdr-B460	33kV Gurungdara I-B140	33kV Gurungdara II	33kV Mirchinge hu	11kV BBPL Fdr	11kV M/Wave Fdr
1	2017	January	SAIFI				0.09	0.26	0.04
2		February	SAIDI				0.02	0.38	0.00
3		March	SAIFI				0.09		0.13
4		April	SAIDI				0.02		2.01
5		May	SAIFI		1.54		0.26	0.17	
6		June	SAIDI		0.27		0.22	5.51	
7		July	SAIFI	0.00	4.62	0.19	0.52	0.13	
8		August	SAIDI	0.00	5.07	0.08	0.16	1.87	
9		September	SAIFI	0.00	5.63	0.26	1.16	0.09	
10		October	SAIDI	0.00	4.82	0.16	0.81	13.65	
11		November	SAIFI	0.00	1.53	0.05	0.39	0.04	
12		December	SAIDI	0.00	0.68	0.01	0.29	0.06	
	Total		SAIFI	0.01	0.00	22.43	0.92	4.36	0.77
	Total		SAIDI	0.01	0.00	25.71	0.80	3.31	26.60
1	2018	January	SAIFI		1.51		0.13		
2		February	SAIDI		3.83		0.13		
3		March	SAIFI		1.51		0.13	0.04	
4		April	SAIDI		3.67		0.15	0.53	
5		May	SAIFI		3.49	0.42	0.88	0.54	
6		June	SAIDI		12.14	0.51	0.71	5.61	
7		July	SAIFI	0.00		0.05	0.38	0.17	
8		August	SAIDI	0.00		0.01	0.20	0.00	
9		September	SAIFI	0.00	2.00		0.63		
10		October	SAIDI	0.00	1.65		0.64		
11		November	SAIFI	0.01	0.00	2.50	0.05	0.50	0.00
12		December	SAIDI	0.01	0.00	3.87	0.11	0.97	0.01
	Total		SAIFI	0.05	0.00	20.87	0.70	3.39	0.75
	Overall total		SAIDI	0.15	0.00	47.15	0.83	3.99	6.19
	Overall total		SAIFI	0.03	0.00	21.65	0.81	3.87	0.76
	Overall total		SAIDI	0.08	0.00	36.43	0.81	3.65	16.40

Sl.No.	Year	Month	Reliability Indices	11kV THPA-1 Fdr	11kV Geduchu Fdr	11kV Padechu Fdr	11kv Old Tsimalakh a	11kv THPA -I	11KV BVC Fdr
1	2017	January	SAIFI						
2		February	SAIFI	0.03			0.51		
3		March	SAIFI	0.24	0.00			0.06	
4		April	SAIFI		0.00		0.51		0.06
5		May	SAIFI	0.24	0.00			0.13	
6		June	SAIFI				1.01		0.06
7		July	SAIFI		0.00		1.52		0.06
8		August	SAIFI	0.03			1.01		
9		September	SAIFI				1.01		0.06
10		October	SAIFI	0.03	0.00		1.51		
11		November	SAIFI						
12		December	SAIFI	0.03			0.50		
	Total		SAIFI	0.61	0.00	-	7.58	-	0.44
			SAIDI	1.23	0.00	-	7.74	-	0.01
1	2018	January	SAIFI				2.01		0.06
2		February	SAIFI		0.00				0.79
3		March	SAIFI	0.10	0.00		2.00		0.18
4		April	SAIFI	0.30			0.50		0.12
5		May	SAIFI	0.13			0.99		
6		June	SAIFI	0.13	0.08		2.48		0.06
7		July	SAIFI		0.49				0.12
8		August	SAIFI		0.08		2.97		
9		September	SAIFI	0.03	0.04		0.99		0.18
10		October	SAIFI	0.03					
11		November	SAIFI				0.99		
12		December	SAIFI	0.07	0.08		0.49		
	Total		SAIFI	0.80	0.78	-	13.41	-	0.68
			SAIDI	0.88	1.30	-	8.69	-	3.18
	Overall total		SAIFI	0.71	0.39	-	10.50	-	0.56
			SAIDI	1.06	0.65	-	8.21	-	1.60

Sl.No.	Year	Month	Reliability Indices	11kV THPA II	11kV THPA III	33kV Shemagan gkha	33kV Chapcha	11kV Chukha Colony	11kV Dzongsite Colony
1	2017	January	SAIFI						
2			SAIDI						
3		February	SAIFI			0.20			
4			SAIDI			0.46			
5		March	SAIFI				0.24	0.63	
6			SAIDI				0.05	0.10	
7		April	SAIFI			0.07	0.08	0.21	
8			SAIDI			0.01	0.01	0.00	
9		May	SAIFI			0.27	0.16		
10			SAIDI			0.10	0.03		
11		June	SAIFI			0.07	0.08		0.04
12			SAIDI			0.05	0.02		0.19
		July	SAIFI			0.20	0.16	0.21	
			SAIDI			0.06	0.02	0.01	
		August	SAIFI			0.14	0.08	0.21	
			SAIDI			0.05	0.07	0.00	
		September	SAIFI		0.03	0.13			
			SAIDI		0.00	0.02			
		October	SAIFI			0.13		0.21	
			SAIDI			0.02		0.02	
		November	SAIFI		0.03			0.21	
			SAIDI		0.00			0.00	
		December	SAIFI						0.02
			SAIDI						0.03
		Total	SAIFI	-	0.06	1.22	0.79	1.67	0.06
			SAIDI	-	0.00	0.77	0.20	0.14	0.22
1	2018	January	SAIFI			1.01	0.08		0.02
2			SAIDI			6.52	0.34		0.03
3		February	SAIFI			1.01	0.31		
4			SAIDI			3.34	1.17		
5		March	SAIFI			1.00	0.31		
6			SAIDI			5.35	4.49		
7		April	SAIFI			0.33	0.23		
8			SAIDI			2.64	2.20		
9		May	SAIFI						
10			SAIDI						
11		June	SAIFI			0.07	0.07		
12			SAIDI			0.02	0.03		
		July	SAIFI				0.07	1.02	
			SAIDI				0.00	0.98	
		August	SAIFI				0.20	0.41	
			SAIDI				0.08	0.03	
		September	SAIFI				0.20	0.20	
			SAIDI				0.07	0.00	
		October	SAIFI						0.04
			SAIDI						0.02
		November	SAIFI				0.15	0.41	0.02
			SAIDI				0.06	1.04	0.01
		December	SAIFI				0.08		
			SAIDI				0.11		
		Total	SAIFI	-	-	3.41	1.69	2.04	0.08
			SAIDI	-	-	17.88	8.55	2.06	0.07
		Overall total	SAIFI	-	0.03	2.32	1.24	1.85	0.07
			SAIDI	-	0.00	9.33	4.38	1.10	0.14

Annexure 6: Material Cost for Upgrading single phase (11 kV and 33 kV) Lines to three-phase

Sl. No	Name of ESDs	Total Cost in Nu. For upgradation of Line to 3Φ from 1Φ		Total cost in Nu.
		11 kV Line in Km	33 kV Line in Km	
		Cost in Nu.	Cost in Nu.	
1	Bumthang	604,083.80	626,364.17	1,230,447.97
2	Chukhha	1,372,746.06	6,450,371.80	7,823,117.86
3	Dagana	—	2,495,645.61	2,495,645.61
4	Haa	—	341,755.04	341,755.04
5	Lhuntse	1,648,680.77	6,292,698.01	7,941,378.78
6	Mongar	—	—	—
7	Paro	1,576,599.08	1,663,407.47	3,240,006.55
8	Pemagatshel	—	2,467,625.51	2,467,625.51
9	Punakha	612,259.13	8,183,731.48	8,795,990.60
10	S/Jongkhar	—	7,593,301.40	7,593,301.40
11	Samtse	2,031,083.74	536,799.03	2,567,882.76
12	Sarpang	756,490.07	1,112,902.61	1,869,392.68
13	Trashi Gang	251,649.96	626,304.45	877,954.41
14	Trashiyangtse		2,207,281.49	2,207,281.49
15	Thimphu	5,228,316.74	-	5,228,316.74
16	Trongsa	—	651,860.25	651,860.25
17	Tsirang	—	1,693,286.88	1,693,286.88
18	Wangdue	98,146.90	3,133,078.14	3,231,225.04
19	Zhemgang	—	5,303,863.16	5,303,863.16
TOTAL		14,180,056.24	51,380,276.50	65,560,332.75

The cost of extending one phase in case of ACSR conductor and AAAC covered conductor were considered and incase of HV ABC, the cost of constructing three core cable has been considered in estimation. Above estimation indicates the total material cost involved in upgrading the existing single-phase line to three phase under each ESD.

The total cost including material cost (Nu. 65 million), transportation cost (Nu. 3.47 million) and labor cost (Nu. 28 million) will amount to Nu. 97 million.

11 kV and 33 kV Single-phase Line Length in km under each ESD

Sl. No	Name of ESDs	11kV 1Φ Line (km)	33kV 1Φ Line (km)	Total 1Φ Line (km)
1	Bumthang	6.96276	5.6246	12.58736
2	Chukhha	21.569	78.274	99.843

Sl. No	Name of ESDs	11kV 1Φ Line (km)	33kV 1Φ Line (km)	Total 1Φ Line (km)
3	Dagana	0	30.527	30.527
4	Haa	0	4.391	4.391
5	Lhuntse	18.7075	80.851	99.5585
6	Mongar	0	0	0
7	Paro	24.772	14.937	39.709
8	Pemagatshel	0	31.705	31.705
9	Punakha	9.62	58.4	68.02
10	S/Jongkhar	0	93.672	93.672
11	Samtse	31.913	6.897	38.81
12	Sarpang	11.8862	14.299	26.1852
13	Trashigang	3.954	8.047	12.001
14	Trashiyangtse	0	28.36	28.36
15	Thimphu	5.93	0	5.93
16	Trongsa	0	5.383	5.383
17	Tsirang	0	21.756	21.756
18	Wangdue	1.01	29.7	30.71
19	Zhemgang	0	66.785	66.785
TOTAL		136.32446	579.6086	715.93306

Annexure 7: Distribution Transformer Loading

SL.No	Name of substation location	Capacity (kVA)	Peak Load (kVA)	% Loading Peak	Peak Load(kVA)	% Loading Peak	Transformer ID	
1	Damdata s/s	125	90.89	72.71%	114.28	91.42%	133.78	107.02% B30T1
	33kV Feeder B250 (Sector II)							
2	Sector II s/s (33/11kV)	5000	3.40	68.00%	4.39	87.76%	5.15	103.02% B250PT1
	11kV Feeder B280 (Water Booster)							
3	Lower Market U/S	750	525.05	70.01%	680.84	90.78%	780.97	104.13% B280T2
	11kV Feeder B270 (PWD)							
4	Upper Market s/s	1000	789.68	78.97%	921.12	92.11%	1037.62	103.76% B280T7
5	Tinkilo s/s	125	100.89	80.71%	117.68	94.12%	132.57	106.02% B270T11
	11kV Feeder B80 (Rangaytrung)							
6	Rangaytrung s/s	125	89.56	71.65%	155.88	124.71%	162.38	129.90% B80T4
	11kV Feeder B90 (Gurungdara)							
7	Barsa s/s	63	44.67	70.90%	61.54	97.68%	67.84	107.68% B80T2
	11kV Feeder B50 (BCCL Colony)							
8	Bimobile s/s	63	58.99	93.63%	64.92	103.05%	69.56	110.41% B50T4
	11kV Feeder B400 (Druk Cement)							
9	Bimobile s/s (Balujora)	500	428.56	85.71%	466.21	93.24%	524.79	104.96% B400T5
10	Toribari s/s	250	220.90	88.36%	240.31	96.12%	270.50	108.20% B400T8
	11kV Feeder B460 (Burkey)							
11	Malbase Village s/s	63	44.90	71.27%	66.24	105.15%	73.97	117.42% B460T2
	Total Distribution Transformers	11						

Annexure-8: Material Cost of three phase (3Φ) Transformers

Sl. No	Name of ESDs	Cost for replacement of single-phase transformers and distribution boards with three-phase		Total cost in Nu.
		11 kV transformers	33 kV transformers	
		Cost in Nu.	Cost in Nu.	
1	Bumthang	421,565.09	132,535.04	554,100.14
2	Chukhha	956,241.73	9,144,917.99	10,101,159.72
3	Dagana	—	6,361,682.08	6,361,682.08
4	Haa	—	3,048,306.00	3,048,306.00
5	Lhuntse	731,506.19	8,747,312.86	9,478,819.05
6	Mongar	182,876.55	4,108,586.34	4,291,462.89
7	Paro	836,897.46	1,060,280.35	1,897,177.81
8	Pemagatshel	91,438.27	6,759,287.21	6,850,725.48
9	Punakha	274,314.82	4,771,261.56	5,045,576.38
10	S/Jongkhar	—	15,506,600.07	15,506,600.07
11	Samtse	6,674,993.95	4,241,121.39	10,916,115.34
12	Sarpang	2,053,501.01	3,445,911.13	5,499,412.14
13	Trashi Gang	906,662.46	4,903,796.60	5,810,459.06
14	Trashiyangtse	—	4,638,726.52	4,638,726.52
15	Thimphu	723,785.91	—	723,785.91
16	Trongsa	91,438.27	3,445,911.13	3,537,349.40
17	Tsirang	—	5,168,866.69	5,168,866.69
18	Wangdue	182,876.55	1,457,885.48	1,640,762.02
19	Zhemgang	105,391.27	11,928,153.90	12,033,545.17
TOTAL		14,233,489.55	98,871,142.33	113,104,631.87

Here the existing single-phase transformers and distribution boards were replaced by three phase system, therefore the estimation includes the cost of three phase transformers and distribution boards. In line with Distribution Design and Construction Standard (DDCS) 2015, the transformer capacities according to voltage level are standardized as shown below:

33 kV System		11 kV System	
3 Φ	1Φ	3 Φ	1Φ
25 kVA	25 kVA, 16 kVA	25 kVA, 16 kVA	25 kVA, 16 kVA, 10 kVA

Therefore, during the estimation, on 33 kV system, the cost of 25 kVA transformers was taken for 10 kVA and 16 kVA transformers and for 11 kV system, the cost of 16 kVA transformers was taken for 10 kVA ratings. The total cost for replacing the 1-phase transformers under whole ESD including transportation cost (Nu. 2.6 million) and labor cost (Nu. 70 million) is Nu. 186 million. Therefore, the total cost under this option will amount to Nu. 283 million.

11 kV & 33 kV Single-phase Transformers used under each ESD

Sl. No	Name of ESDs	TRANSFORMERS (Nos.)					
		11/0.240 kV			33/0.240 kV		
		10 kVA	16kVA	25kVA	10 kVA	16kVA	25kVA
1	Bumthang	—	—	4	—	1	—
2	Chukhha	2	5	3	19	31	19
3	Dagana	—	—	—	4	43	1
4	Haa	—	—	—	8	13	2
5	Lhuntse	3	5	—	3	19	44
6	Mongar		2	—	12	17	2
7	Paro	5	3	1	6	2	—
8	Pemagatshel	—	1	—	4	8	39
9	Punakha	1	2	—	2	5	29
10	S/Jongkhar	—	—	—	18	24	75
11	Samtse	15	58	—	—	32	—
12	Sarpang	10	9	3	9	8	9
13	Trashi Gang	3	—	6	—	—	37
14	Trashiyangtse	—	—	—	16	19	—
15	Thimphu*	—	1	6	—	—	—
16	Trongsa	1	—	—	9	17	—
17	Tsirang	—	—	—	7	32	—
18	Wangdue	1	1	—	—	2	9
19	Zhemgang	—	—	1	27	36	27
	TOTAL	41	87	24	144	309	293

